


VA\Projects\2013\131-12992-04 PWGSC CBESA Stewart PoE New Building Development - Elec\Prefabricated Building\WSP Data\Production\131-12992-04-E-005_12/05/2015_9:52 AM: TYLER.DAVIDSON



GENERAL NOTES:
1. ALL DEVICES SHOWN ON THIS PLAN ARE TO BE INSTALLED BY OTHERS. ELECTRICAL CONTRACTOR SHALL COORDINATE WITH OWNERS REQUIREMENTS AND PROVIDE ALL CONDUIT PATHWAYS FOR THESE DEVICES.

KEYNOTES:
1. SWITCH TO ACTIVATE SIRENS AND VISUAL INDICATOR.
2. INSTALL ON MILLWORK.
3. HOME RUN CAT-5E CABLES IN CONDUIT BACK TO CCTV RACK IN LAN ROOM.
4. PROVIDE CONDUIT FROM NEAREST DEVICE, JUNCTION BOX OR PANEL BOARD FOR ELECTRICAL DEVICES IN CANOPY BUILDING.
5. PUSH BUTTON TO ACTIVATE SIRENS AND VISUAL INDICATORS.



400-401 GARBALLY ROAD
VICTORIA (BRITISH COLUMBIA) CANADA V8T 5M3
TEL.: 250-384-5510 | FAX: 250-386-2844 | WWW.WSPGROUP.COM
PROJECT: 131-12992-04

NOT FOR CONSTRUCTION FOR INFORMATION PURPOSES ONLY

Revision/Revision	Description/Description	Date/Date
5		
4		
3	RE-ISSUED FOR CONCEPTUAL DESIGN	15/05/12
2	RE-ISSUED FOR CONCEPTUAL DESIGN	15/05/05
1	ISSUED FOR CONCEPTUAL DESIGN	15/04/21
0	ISSUED FOR 60% REVIEW	14/12/10

Client/client

CANADA BORDER SERVICES AGENCY

Project title/Titre du projet

**STEWART PORT OF ENTRY REDEVELOPMENT
STEWART, B.C.**

Consultant Signature Only

Designed by/Concept par
J.d.B./T.D.

Drawn by/Dessiné par
T.D./P.P./S.G.

PWGSC Project Manager/Administrateur de Projets TPSCG
Julian Ho

Regional Manager, Architectural and Engineering Services
Gestionnaire régionale, Services d'architectural et de génie, TPSCG
Prestipal Paul

Drawing title/Titre du dessin

**ELECTRICAL
CCTV, INTRUSION DETECTION
AND DURESS SYSTEMS PLAN**

Project No./No. du projet
R.071365.001

Sheet/ Feuille
EB-005

Revision no./
La Révision no.
3

OF 06