

Part 1 General

1.1 REFERENCES

- .1 U.S. Environmental Protection Agency (EPA) / Office of Water
 - .1 EPA 832/R-92-005, Storm Water Management for Construction Activities: Developing Pollution Prevention Plans and Best Management Practices.

Part 2 Products

2.1 EQUIPMENT

- .1 Use cold milling, planning or grinding equipment with automatic grade controls capable of operating from stringline, and capable of removing part of pavement surface to depths or grades indicated.

Part 3 Execution

3.1 PREPARATION

- .1 Prior to beginning removal operation, inspect and verify with Departmental Representative areas, depths and lines of asphalt pavement to be removed.
- .2 Protection: protect existing pavement not designated for removal, light units and structures from damage. In event of damage, immediately replace or make repairs to approval of Departmental Representative at no additional cost.

3.2 REMOVAL

- .1 Remove existing asphalt pavement to lines and grades as indicated.
- .2 Use equipment and methods of removal and hauling which do not damage or disturb underlying pavement.
- .3 Prevent contamination of removed asphalt pavement by topsoil, underlying gravel or other materials.
- .4 Suppress dust generated by removal process.

3.3 FINISH TOLERANCES

- .1 Finished surfaces in areas where asphalt pavement has been removed to be within +/-5 mm of grade specified but not uniformly high or low.

3.4 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.

- .3 Sweep remaining asphalt pavement surfaces clean of debris resulting from removal operations using rotary power brooms and hand brooming as required.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Definitions:
 - .1 Hazardous Materials: dangerous substances, dangerous goods, hazardous commodities and hazardous products, include but not limited to: poisons, corrosive agents, flammable substances, ammunition, explosives, radioactive substances, or materials that endanger human health or environment if handled improperly.
 - .2 Waste Management Co-ordinator (WMC): contractor representative responsible for supervising waste management activities as well as co-ordinating related, required submittal and reporting requirements.
 - .3 Waste Audit (WA): detailed inventory of materials in building. Involves quantifying by volume/weight amounts of materials and wastes generated during construction, demolition, deconstruction, or renovation project. Indicates quantities of reuse, recycling and landfill.
 - .4 Waste Reduction Workplan (WRW): written report which addresses opportunities for reduction, reuse, or recycling of materials. WRW is based on information acquired from WA.
- .2 Reference Standards:
 - .1 Canadian Environmental Protection Act (CEPA)
 - .1 CCME PN 1326-2008, Environmental Code of Practice for Aboveground and Underground Storage Tank Systems for Petroleum Products and Allied Petroleum Products.
 - .2 CSA International
 - .1 CSA S350-M1980(R2003), Code of Practice for Safety in Demolition of Structures.
 - .3 Department of Justice Canada (Jus)
 - .1 Canadian Environmental Assessment Act (CEAA), 1995, c. 37.
 - .2 Canadian Environmental Protection Act (CEPA), 1999, c. 33.
 - .1 SOR/2003-2, On-Road Vehicle and Engine Emission Regulations.
 - .2 SOR/2006-268, Regulations Amending the On-Road Vehicle and Engine Emission Regulations.
 - .3 Transportation of Dangerous Goods Act (TDGA), 1992, c. 34.
 - .4 U.S. Environmental Protection Agency (EPA)
 - .1 EPA CFR 86.098-10, Emission standards for 1998 and later model year Otto-cycle heavy-duty engines and vehicles.
 - .2 EPA CFR 86.098-11, Emission standards for 1998 and later model year diesel heavy-duty engines and vehicles.

- .3 EPA 832/R-92-005, Storm Water Management for Construction Activities: Developing Pollution Prevention Plans and Best Management Practices.

1.2 ADMINISTRATIVE REQUIREMENTS

- .1 Scheduling:
 - .1 Employ necessary means to meet project time lines without compromising specified minimum rates of material diversion.
 - .1 In event of unforeseen delay notify Departmental Representative in writing.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 – Shop Drawings, Product data and Samples and Section 01 74 21 - Construction/Demolition Waste Management Disposal.
- .2 WMC is responsible for fulfilment of reporting requirements.

1.4 QUALITY ASSURANCE

- .1 Regulatory Requirements: Ensure Work is performed in compliance with applicable Provincial regulations.

1.5 SITE CONDITIONS

- .1 Environmental protection:
 - .1 Ensure Work is done in accordance with Section 01 35 43 - Environmental Procedures.
 - .2 Ensure Work does not adversely affect adjacent watercourses, groundwater and wildlife, or contribute to excess air and noise pollution.
 - .3 Fires and burning of waste or materials is not permitted on site.
 - .4 Do not bury rubbish waste materials.
 - .5 Do not dispose of waste or volatile materials including but not limited to: mineral spirits, oil, petroleum based lubricants, or toxic cleaning solutions into watercourses, storm or sanitary sewers.
 - .1 Ensure proper disposal procedures are maintained throughout project.
 - .6 Do not pump water containing suspended materials into watercourses, storm or sanitary sewers, or onto adjacent properties.
 - .7 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with authorities having jurisdiction.
 - .8 Protect trees, plants and foliage on site and adjacent properties where indicated.
 - .9 Prevent extraneous materials from contaminating air beyond application area, by providing temporary enclosures during demolition work.
 - .10 Cover or wet down dry materials and waste to prevent blowing dust and debris. Control dust on all temporary roads.

1.6 EXISTING CONDITIONS

- .1 Site Decommissioning:
 - .1 The original facility was constructed in 1996 and it is not anticipated that hazardous materials exist on, within or around the building or the construction site. It is also anticipated that there are no areas of archaeological-significance in the work area. However, if any hazardous material is encountered or if any item that might be considered archaeologically-significant is encountered, then the contractor is to immediately stop work and notify the proper authorities.
- .2 The contractor retains ownership of and is responsible to remove the existing building, generator and generator shed, and any other above-grade objects shown to be removed or which are not intended to remain. Removal of any materials shall be done without disruption of operations of the port of entry facility.
- .3 The contractor is to coordinate his work and assist the Canada Border Services Agency (CBSA) staff with moving from the existing building to the new building. The contractor is to contact the CBSA's site superintendent to determine the date of the move, and to obtain a detailed inventory of what items are to be moved. In general, the move includes, but is not limited to:
 - .1 CCTV equipment
 - .2 Filing cabinets and chairs,
 - .3 Electronic equipment and computers
 - .4 All loose items and contents of shelves, cabinets and storage
 - .5 A safe (weight unknown)
 - .6 All contents of the arming room, whether or not attached to the building, unless designated otherwise to remain. The arming room includes an arms cabinet which weighs approximately 115 kg when empty, or approximately 290 kg when full. The contractor is to coordinate the transfer of arms and ammunition with CBSA's superintendent.
- .4 Items to remain with the existing building include desks, lockers, millwork, window coverings and most items fixed to the structure (with exception of the arms room, noted in 1.6.3.6. The contractor is responsible for disposal of all such items.
- .5 The existing building and generator shall be removed within 14 days of occupancy of the new building. Storage on-site or any material which is to be removed in part or in whole is not permitted beyond 14 days of occupancy.
- .6 Move flagpole and base to new location as shown. Fill-in the remaining excavated annular space around the flagpole base with concrete or compacted road-base gravel.
- .7 If material resembling spray or trowel applied asbestos or other designated substance listed as hazardous be encountered in course of demolition, stop work, take preventative measures, and notify Departmental Representative immediately. Proceed only after receipt of written instructions have been received from Departmental Representative.
- .8 Structures to be demolished are based on their condition at time of examination prior to tendering.

Part 2 Products

2.1 EQUIPMENT

- .1 Leave machinery running only while in use, except where extreme temperatures prohibit shutting machinery down.

Part 3 Execution

3.1 PREPARATION

- .1 Protection of in-place conditions:
 - .1 Work in accordance with Section 01 35 43 - Environmental Procedures.
 - .2 Prevent movement, settlement or damage of adjacent structures and services.
 - .1 Provide bracing, shoring and underpinning as required.
 - .2 Repair damage caused by demolition as directed by Departmental Representative.
 - .3 Support affected structures and, if safety of structure being demolished, adjacent structures, or services appears to be endangered, take preventative measures, stop Work and immediately notify Departmental Representative.
 - .4 Prevent debris from blocking surface drainage system, elevators, mechanical and electrical systems which must remain in operation.
- .2 Surface Preparation:
 - .1 Disconnect and re-route as required electrical and telephone service lines entering buildings to be demolished.
 - .1 Post warning signs on electrical lines and equipment which must remain energized to serve other properties during period of demolition.
 - .2 Disconnect and cap designated mechanical services.
 - .1 Sewer lines.

3.2 DEMOLITION

- .1 Do demolition work in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.
- .2 Do blasting operations in accordance with CSA S350.
- .3 Remove contaminated or dangerous materials as defined by authorities having jurisdiction, relating to environmental protection, from site and dispose of in safe manner to minimize danger at site or during disposal.
- .4 If found, remove contaminated or hazardous materials as defined by authorities having jurisdiction as directed by Departmental Representative from site and dispose of in safe manner and in accordance with TDGA and other applicable requirements.
- .5 Demolish foundation walls and footings.
- .6 Remove existing equipment, services, and obstacles where required for refinishing or making good of existing surfaces, and replace as work progresses.

- .7 At end of each day's work, leave Work in safe and stable condition.
- .8 Demolish to minimize dusting.
- .9 Demolish masonry and concrete walls in pieces suitable for reuse as specified.
- .10 Remove structural framing.
- .11 Contain fibrous materials to minimize release of airborne fibres while being transported within facility.
- .12 Remove and dispose of demolished materials except where noted otherwise and in accordance with authorities having jurisdiction.

3.3 CLEANING

- .1 Waste Management: separate waste materials for reuse in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.
- .2 Designate appropriate security resources / measures to prevent vandalism, damage and theft.
- .3 Locate stockpiled materials convenient for use in new construction. Eliminate double handling wherever possible.
- .4 Stockpile materials designated for alternate disposal in location which facilitates removal from site and examination by potential end markets, and which does not impede disassembly, processing, or hauling procedures.
- .5 Remove stockpiled material as directed by Departmental Representative when it interferes with operations of project construction.
- .6 Transport material designated for alternate disposal using approved haulers and facilities in accordance with applicable regulations.
- .7 Dispose of materials not designated for alternate disposal in accordance with applicable regulations.

END OF SECTION