

Part 1 General

1.1 ENVIRONMENTAL REQUIREMENTS

- .1 Operation of construction equipment in water is prohibited.
- .2 Dumping excavated fill, waste material, or debris in watercourse or wetland is prohibited.
- .3 Underwater blasting within 100 m of indicated spawning beds is not permitted.

1.2 REFERENCES

- .1 U.S. Environmental Protection Agency (EPA) / Office of Water
 - .1 EPA 832/R-92-005, Storm Water Management for Construction Activities:
Developing Pollution Prevention Plans and Best Management Practices.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 EXISTING CONDITIONS

- .1 Maintain existing flow pattern in natural watercourse systems.
- .2 In natural systems maintain existing riffle pool and step pool patterns.
- .3 In wetland systems, maintain existing hydrological conditions.

3.2 SITE CLEARING AND PLANT PROTECTION

- .1 Temporary Erosion and Sedimentation Control:
 - .1 Provide temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to requirements of authorities having jurisdiction and sediment and erosion control drawings.
 - .2 Inspect, repair, and maintain erosion and sedimentation control measures during construction until permanent vegetation has been established.
 - .3 Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.
- .2 Minimize disturbance to vegetated buffer zones and protect trees and plants on site and adjacent properties where indicated.
- .3 Wrap trees and shrubs adjacent to construction work, storage areas and trucking lanes in burlap.

- .4 Protect roots of designated trees to dripline during excavation and site grading to prevent disturbance or damage.
 - .1 Avoid unnecessary traffic, dumping and storage of materials over root zones.
- .5 Remove only trees that may offer future blockage problems as instructed by Departmental Representative.
- .6 Maintain temporary erosion and pollution control features installed under this contract.

3.3 DRAINAGE

- .1 Pumping water containing suspended materials into watercourse is prohibited.

END OF SECTION