





LEGEND	
	POWER JUNCTION BOX, (SURFACE MOUNT)
	TELEPHONE/DATA JACK OUTLET. RUN 3/4" C/W CAT6 CABLE TO IT ROOM. REUSE EXISTING WHERE POSSIBLE. PROVIDE NEW WHERE REQUIRED.
	LOW VOLTAGE MECHANICAL THERMOSTAT.
	MOTOR DISCONNECT. SIZE AS PER CEC REQUIREMENTS.
	MOTOR MAGNETIC STARTER.
	MOTOR
	FIRE ALARM SPEAKER.
	PICTOGRAM "RUNNING MAN" EXIT SIGN. STANDARD OF ACCEPTANCE: READY-LITE RA SERIES.
	LOW VOLTAGE WALL MOUNTED LIGHT SWITCH.
	15A SINGLE POLE LIGHT TOGGLE SWITCH.
	EXISTING PULL STATION.
	EXISTING DISTRIBUTION PANEL.
	LOW VOLTAGE CEILING MOUNT 360° MOTION SENSOR. RE-USE EXISTING RELAYS AND LOW VOLTAGE EQUIPMENT WHERE POSSIBLE.
	PACK POLE.
	EXISTING 2 X 4 FLUORESCENT LIGHT FIXTURE LAY IN GRID. FIXTURE TO BE REUSED. ALLOW FOR WIRING EXTENSION, SEISMIC RETRAIN AND TERMINATIONS FOR COMPLETE OPERATIONAL SYSTEM.
	EXISTING 6" POT LIGHT FIXTURE RECESSED IN GRID. FIXTURE TO BE REUSED. ALLOW FOR WIRING EXTENSION, SEISMIC RETRAIN AND TERMINATIONS FOR COMPLETE OPERATIONAL SYSTEM.
	15A DUPLEX RECEPTACLE C/W GROUND.
	15A FOURPLEX RECEPTACLE C/W GROUND.
	15A SPLIT RECEPTACLE C/W GROUND. BREAKER PROTECTING THIS RECEPTACLE SHALL BE DOUBLE POLE.
	20A RECEPTACLE C/W GROUND. BREAKER PROTECTING THIS RECEPTACLE SHALL BE 20A-1P.



KEY PLAN
SCALE 1:500



EXISTING POWER AND TEL/DATA LAYOUT
SCALE=1:50



4	ISSUED FOR TENDER	13-05-2015
3	REVISED 99% SUBMISSION	17-04-2015
2	99% SUBMISSION	07-04-2015
1	66% SUBMISSION	27-03-2015

Revision/	Description/Description	Date/Date
Client/client		

**CAN-NOR and
PUBLIC WORKS &
GOVERNMENT SERVICES**

800 BURNARD ST.
VANCOUVER, BC

Project title/Titre du projet
**2nd & 4th Floor - 300 Main Street
Whitehorse, YT**

**CAN-NOR Relocation
Consolidated**

Consultant Signature Only

Designed by/Concept par
AD

Drawn by/Dessiné par
AD

PWGSC Project Manager/Administrateur de Projets TPSGC
Cyndi Oster

PWGSC Architectural and Engineering Resources Manager/
Ressources Architectural et de Directeur d'ingénierie, TPSGC
Preetipal Paul

Client/client
CAN-NOR

Drawing title/Titre du dessin

**CAN-NOR (4th FLOOR)
EXISTING POWER AND
TEL/DATA LAYOUT**

Project No./No. du
projet
R.072738.001

Sheet/ Feuille
**E5
OF 07**

Revision no./
La Révision
no.
0