



LEGEND	
	POWER JUNCTION BOX. (SURFACE MOUNT)
	TELEPHONE/DATA JACK OUTLET. RUN 3/4" C/W CAT5 CABLE TO IT ROOM. REUSE EXISTING WHERE POSSIBLE, PROVIDE NEW WHERE REQUIRED.
	LOW VOLTAGE MECHANICAL THERMOSTAT.
	MOTOR DISCONNECT. SIZE AS PER CEC REQUIREMENTS.
	MOTOR MAGNETIC STARTER.
	MOTOR
	FIRE ALARM SPEAKER.
	PICTOGRAM "RUNNING MAN" EXIT SIGN. STANDARD OF ACCEPTANCE: READY-LITE RA SERIES.
	LOW VOLTAGE WALL MOUNTED LIGHT SWITCH.
	15A SINGLE POLE LIGHT TOGGLE SWITCH.
	EXISTING PULL STATION.
	EXISTING DISTRIBUTION PANEL.
	LOW VOLTAGE CEILING MOUNT 360° MOTION SENSOR. RE-USE EXISTING RELAYS AND LOW VOLTAGE EQUIPMENT WHERE POSSIBLE.
	PACK POLE.
	EXISTING 2 X 4 FLUORESCENT LIGHT FIXTURE LAY IN GRID. FIXTURE TO BE REUSED. ALLOW FOR WIRING EXTENSION, SEISMIC RETRAIN AND TERMINATIONS FOR COMPLETE OPERATIONAL SYSTEM.
	EXISTING 6" POT LIGHT FIXTURE RECESSED IN GRID. FIXTURE TO BE REUSED. ALLOW FOR WIRING EXTENSION, SEISMIC RETRAIN AND TERMINATIONS FOR COMPLETE OPERATIONAL SYSTEM.
	15A DUPLEX RECEPTACLE C/W GROUND.
	15A FOURPLEX RECEPTACLE C/W GROUND.
	15A SPLIT RECEPTACLE C/W GROUND. BREAKER PROTECTING THIS RECEPTACLE SHALL BE DOUBLE POLE.
	20A RECEPTACLE C/W GROUND. BREAKER PROTECTING THIS RECEPTACLE SHALL BE 20A-1P.






KEY PLAN  
SCALE 1:500



KEY NOTES:  
R: RELOCATE, USE EXISTING CIRCUIT  
E: EXISTING TO REMAIN  
N: NEW  
EM.CCT: CONNECT TO EXISTING EMERGENCY CIRCUIT

RE-USE EXISTING LIGHT FIXTURES, LIGHT SWITCHES, RELAYS AND CIRCUITS WHERE POSSIBLE. REPAIR WHERE NEEDED  
ALLOW FOR MIN. 15 FIXTURES REPAIR IN THE BID PRICE. ALL EXISTING T-BAR FIXTURES TO BE REUSED. TYPICAL FOR 45-  
2'x4' FIXTURES AND 8" POT LIGHTS.

NEW LIGHTING AND LIFE SAFETY LAYOUT  
SCALE=1:50



Revision/	Description/Description	Date/Date
4	ISSUED FOR TENDER	13-05-2015
3	REVISED 99% SUBMISSION	17-04-2015
2	99% SUBMISSION	07-04-2015
1	86% SUBMISSION	27-03-2015

Client/client  
**CAN-NOR and  
PUBLIC WORKS &  
GOVERNMENT SERVICES**  
  
800 BURNARD ST.  
VANCOUVER, BC

Project title/Titre du projet  
**2nd & 4th Floor - 300 Main Street  
Whitehorse, YT**  
  
**CAN-NOR Relocation  
Consolidated**

Consultant Signature Only  
  
Designed by/Concept par  
**AD**  
Drawn by/Dessiné par  
**AD**  
PWGSC Project Manager/Administrateur de Projets TPSCG  
**Cyndi Oster**  
PWGSC, Architectural and Engineering Resources Manager/  
Ressources Architectural et de Directeur d'ingénierie, TPSCG  
**Prestipal Paul**  
Client/client  
**CAN-NOR**  
Drawing title/Titre du dessin

**CAN-NOR (4th FLOOR)  
NEW LIGHTING AND  
LIFE SAFETY LAYOUT**

Project No./No. du projet <b>R.072738.001</b>	Sheet/ Feuille <b>E6</b> OF 07	Revision no./ La Révision no. <b>0</b>
---	--------------------------------------	---