


**MAIN FLOOR PLAN - ZONE A  
SECURITY - ZONE 1 & 2**

SCALE: 1:200



TOTAL	SUMMARY
11	EXISTING TO BE REUSED ACCESS CONTROL ELECTRIC DOOR CARD READER
3	NEW ACCESS CONTROL ELECTRIC DOOR CARD READER
3	NEW MOTION SENSORS
1	NEW KEYPAD
8	NEW GLASS BREAKER SENSORS

NOTES

- SUPPLY AND INSTALL WIRING FROM SECURITY AND ACCESS CONTROL DEVICES TO NEW CONTROL PANEL IN MAIN FLOOR MAIL ROOM. DEVICES TO BE SUPPLIED AND INSTALLED BY ALLIANCE SECURITY UNDER THIS CONTRACT. REFER TO SK-4 FOR WIRING DETAILS.
- CLOSED CIRCUIT VIDEO EQUIPMENT SYSTEM AND ALL CABLING TO BE RELOCATED BY CHUBB SECURITY UNDER THIS CONTRACT.
- ACCESS CONTROL PANEL TO BE SUPPLIED AND INSTALLED BY ALLIANCE SECURITY UNDER THIS CONTRACT.
- LEAVE EXISTING ACCESS CONTROL WIRING COILED AND LABELED IN ACCESSIBLE FLOOR SPACE FOR FUTURE RECONNECTION. ARRANGE FOR EDWARDS TO DECOMMISSION EXISTING DOOR CONTROLS. COORDINATE SCHEDULES SO DOORS ARE NOT LEFT UNSUPERVISED.

LEGEND

	ACCESS CONTROL ELECTRIC DOOR CARD READER, PROXIMITY TYPE
	EXISTING TO BE REUSED WITH COMPATIBLE NEW ACCESS CONTROL ELECTRIC DOOR CARD READER, PROXIMITY TYPE
	ACCESS CONTROL ELECTRIC STRIKE
	ACCESS CONTROL ELECTRIC DOOR CONTACT
	ACCESS CONTROL INTERFACE KEYPAD
	INTRUSION ALARM MOTION DETECTOR
	ACCESS CONTROL REQUEST-TO-EXIT DEVICE
	GLASS BREAKER SENSORS
	GLASS BREAKER SENSORS
	CONTROL TRANSFORMER
GENERAL SUBSCRIPTS	
E	EXISTING

0	ISSUED FOR ADDENDUM	06/29/2015
revisions		date
project		project

**ESDC CONSOLIDATION  
JEAN CANFIELD BLDG.  
191 UNIVERSITY AVE.  
CHARLOTTETOWN  
QUEEN'S CO. PEI**

drawing / dessin

**MAIN FLOOR PLAN  
ZONE A  
ELECTRICAL  
DOOR CONTROL  
ZONE 1 & 2**

designed	E.S.C. P.ENG/A.D.J., P.ENG	conçu
date	2015-06-11	
drawn	M.E.M., C.E.T.	dessiné
date	2015-06-11	

approved / approuvé

date / date

Tender / Soumission

PWGC Project Manager / Administrateur de projets TPSGC

project number / no. du projet

**R.061033.001**

drawing no. / no. du dessin

**SK-1**