



INDIAN HEAD AAFC
B017 ADDITION
INDIAN HEAD, SK

Any representations in the tender documents are for the general information of bidders and are not in any way warranted or guaranteed by or on behalf of the owner or the owner's consultants and its subcontractor's employees, and neither the owner nor its consultants or its employees, shall be liable for any representations negligent or otherwise contained in the documents. These design documents are prepared solely for the use by the party with whom the design professional has entered into a contract and there are no representations of any kind made by the design professional to any party with whom the design professional has not entered into a contract. The contractor shall check all dimensions, elevations and other data as represented on all drawings in the set for consistency and correctness and report to the consultant any discrepancies prior to proceeding with construction. Any costs to the contractor arising from failure to execute this requirement is a cost to the contractor and not to the owner nor the consultant. This term supercedes the specifications. All construction work to be completed in accordance with all applicable code and requirements of all utilities as set out by governing authorities.

Issue Record:
YY.MM.DD/Issued For/Issued To/Issued By

Revisions:
R# Brief Description/YY.MM.DD/Revised By

WALL SECTIONS &
DETAILS

Designed By: CAL Scale: AS INDICATED

Drawn By: ST/JN Date: MARCH 2013

Checked By: CAL Date: -

Project No.: 4796



A3.2

Revision No.: R# Date: YYYY.MM.DD

Issued For: -

Date Issued: YYYY.MM.DD

Date Plotted: 2015.06.15



WALL ASSEMBLIES

E-1 EXTERIOR WALL

- FR: N/A STC: N/A
- PRE-FINISHED LIGHT GAUGE METAL WALL CLADDING SYSTEM, COLOR SELECTION BY OWNER (MATCH EXISTING).
- WALL GIRTS @ MIN 48" O.C. (VERIFY)
- R-28 SEMI RIGID BATT INSULATION
- 6 mil POLY VAPOUR BARRIER
- PRE-FINISHED METAL LINER PANEL @ INTERIOR (TYPICAL)

E-2 EXISTING WALL

- PRE-FINISHED METAL PANELS @ EXTERIOR
- WALL GIRTS (VERIFY SPACING)
- BATT INSULATION
- 6 mil POLY VAPOUR BARRIER
- INTERIOR LINER PANELS
- FURR OUT @ NEW SPACE W/ 7/8" HAT CHANNELS & PREFIN METAL LINER PANELS.

P-1 INTERIOR WALL

- FR: N/A STC: N/A
- METAL LINER PANEL OVER 1/2" PLYWOOD BACKING
- 2"x8" WOOD STUDS @ 16" O.C., FULL HT. (3" FLOAT) C/W ACOUSTICAL INSULATION
- 1/2" GWB (USE MOISTURE RESISTANT GWB FOR PLUMBING WALLS) OR METAL LINER PANEL, AS PER FINISH NOTES.

FLOOR ASSEMBLIES

F1

- APRON SLAB @ GARAGE/SIDEWALK/CONC PAD
- 7" CONCRETE SLAB ON GRADE
- INTEGRATED HARDENER (SEE STRUCTURAL FOR REINF)
- 6 mil POLY VAPOUR BARRIER
- MIN. 12" COMPACTED GRANULAR FILL
- NON-SKID SURFACE ON SIDEWALK AND CONC PAD.

F1a

- SLAB @ ENTRY
- 5" CONCRETE SLAB ON GRADE
- INTEGRATED HARDENER (SEE STRUCTURAL FOR REINF)
- MIN. 12" COMPACTED GRANULAR FILL
- NON-SKID SURFACE.

F2

- MEZZANINE FLOOR
- 3/4" T&G PLYWOOD SUB FLOOR
- 2"x8" WOOD JOIST
- FINISH WITH RESIN EPOXY PAINT WITH ANTI-SLIP PROVISIONS.

F3 MEZZANINE FLOOR

- 3/4" T&G PLYWOOD SUB FLOOR
- 2"x10" WOOD JOIST
- FINISH WITH RESIN EPOXY PAINT WITH ANTI-SLIP PROVISIONS.

F4 EXISTING FLOOR

ROOF ASSEMBLIES

R1 ROOF OVER ADDITION

- FR: N/A STC: N/A
- STANDING SEAM PRE-FINISHED METAL ROOF SYSTEM (PART OF METAL BLDG PACKAGE)
- PRE-ENGINEERED STEEL BUILDING SYSTEM, PREFINISHED
- R28 BATT INSULATION C/W VAPOUR BARRIER (PART OF METAL BLDG PACKAGE)
- 6 MIL POLY VAPOUR BARRIER
- PRE-FINISHED METAL LINER PANELS.

R2 EXISTING ROOF