

SPECIFICATION

Wharf Extension Branch, NL 721395

DFO File # FP802-150072

Prepared for: Fisheries and Oceans Canada

Date: June 1, 2015 (Revision 1)

LIST OF DRAWINGS

Wharf Extension
Branch, NL
721395

Page 1

2015-06-01

DRAWING NO

TITLE

C1 of 6	Existing Site and Demolition Plan
C2 of 6	New Site Plan
C3 of 6	New Wharf Layout
C4 of 6	New Elevations
C5 of 6	New Sections
C6 of 6	New Details

LIST OF CONTENTS

Section 00 01 11

Wharf Extension
Branch, NL
721395

Page 1

2015-06-01

<u>Section</u>	<u>Title</u>	<u>Pages</u>
01 10 10	GENERAL INSTRUCTIONS	14
01 29 83	PAYMENT PROCEDURES FOR TESTING LABORATORY SERVICES	3
01 33 00	SUBMITTAL PROCEDURES	6
01 35 24	SPECIAL PROCEDURES ON FIRE SAFETY REQUIREMENTS	6
01 35 25	SPECIAL PROCEDURES ON LOCKOUT REQUIREMENTS	7
01 35 28	HEALTH AND SAFETY REQUIREMENTS	15
01 35 43	ENVIRONMENTAL PROCEDURES	5
01 45 00	TESTING AND QUALITY CONTROL	5
01 50 00	TEMPORARY FACILITIES	3
01 56 00	TEMPORARY BARRIERS AND ENCLOSURES	2
01 59 20	SITE MONITOR'S CAMP AND BOARD	2
01 61 00	COMMON PRODUCT REQUIREMENTS	5
01 74 11	CLEANING	2
01 74 21	CONSTRUCTION/DEMOLITION WASTE MANAGEMENT AND DISPOSAL	6
01 78 00	CLOSEOUT SUBMITTALS	2
02 41 16	SITWORK, DEMOLITION AND REMOVAL	3
03 10 00	CONCRETE FORMING AND ACCESSORIES	5
03 20 00	CONCRETE REINFORCING	5
03 30 00	CAST-IN-PLACE CONCRETE	13
05 50 00	METAL FABRICATIONS	5
06 05 73	WOOD TREATMENT	4
07 92 10	JOINT SEALING	7
26 05 34	CONDUITS, CONDUIT FASTENINGS & CONDUIT FITTINGS	2
26 52 60	POLE	1
31 23 25	ROCK AND GRAVEL FILL	2
31 32 21	GEOTEXTILE	5
31 36 19	ROCK MATTRESS	5
31 37 10	RIP-RAP	2
31 53 13	TIMBER CRIBWORK	10
31 53 16	STRUCTURAL TIMBER	9
32 11 23	GRANULAR BASE COURSES	6
35 20 23	DREDGING	11
35 59 29	MOORING DEVICES	3

1.1 SCOPE

- .1 The scope of work for this project is the provision of construction activities to provide safer, more reliable berthing and offloading facilities at this existing site as is more specifically described in the Description of Work and the Drawings and Specifications. The work consists of the furnishing of all plant, labour, equipment and material for marginal wharf extension at Branch, in strict accordance with specifications and accompanying drawings and subject to all terms and conditions of the Contract. Bidders are advised that opportunities and requirements may arise than may warrant changes to the work that are in keeping with this general scope of work. Such changes will be made through the Change Order processes as outlined in the contract documents.

1.2 DESCRIPTION OF WORK

- .1 In general, work under this contract consists of, but will not necessarily be limited to, the following:
- .1 Miscellaneous removal of existing fenders and wheelguard from the existing structure to accommodate the new construction. An existing untreated round timber cribwork structure will also have to be removed, and disposed off site, to accommodate the new construction (reference the drawings in this regard).
 - .2 Construction of a new treated timber crib marginal wharf with reinforced concrete deck, to the dimensions as indicated on the drawings.
 - .3 Cribseat excavation and supply/installation of rock mattress, as noted on the drawings.
 - .4 Supply and installation of

mooring cleats, structural timber for coping, wheelguard, wheelguard blocking, fenders, ladders and associated hardware for new wharf construction.

.5 Supply and installation of rock/gravel fill, geotextile, granular base and steel angle, as noted on the drawings.

.6 Harbour dredging, as noted on the drawings.

1.3 SITE OF WORK .1 Work will be carried out at Branch, NL, in the location as shown on the accompanying drawings.

1.4 DATUM .1 Datum used for this project is Lowest Normal Tides (LNT) and is assumed to be 3.635 metres below BM PWC 1-10. Confirm with Departmental Representative prior to construction.

.2 Bidders are advised to consult the Tide Tables issued by Fisheries and Oceans in order to make sure of the tidal conditions affecting work.

1.5 FAMILIARIZATION WITH SITE .1 Before submitting a bid, bidders can visit the site and its surroundings, at their own expense, to review and verify the form, nature and extent of the work, materials needed for the completion of the work, the means of access to the site, severity, exposure and uncertainty of weather, soil conditions, any accommodations they may require, and in general shall obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their bid or costs to do the work. No allowance shall be made subsequently in this connection on account of error or

negligence to properly observe and determine the conditions that will apply.

- .2 Contractors, bidders or those they invite to site are to review specification Section 01 35 28 - Health and Safety Requirements before visiting site. Take all appropriate safety measures for any visit to site, either before or after acceptance of bid.
- .3 Obtain prior permission from the Departmental Representative before carrying out such site inspection.

1.6 CODES AND STANDARDS

- .1 Perform work in accordance with the latest edition of the National Building Code of Canada, FCC Standard 373 - Standard for Piers and Wharves (http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/commissioner/373/page00.shtml), and any other code of provincial or local application including all amendments up to project bid closing date provided that in any case of conflict or discrepancy, the more stringent requirements shall apply.
- .2 Materials and workmanship must meet or exceed requirements of specified standards, codes and referenced documents.

1.7 TERM DEPARTMENTAL REPRESENTATIVE

- .1 Unless specifically stated otherwise, the term Departmental Representative where used in the Specifications and on the Drawings shall mean the Engineer as defined in the General Conditions of the Contract.

1.8 SETTING OUT WORK

- .1 Set grades and layout work in detail from control points and grades established by Departmental Representative.
- .2 Assume full responsibility for and execute

complete layout of work to locations, lines and elevations indicated or as directed by Departmental Representative.

- .3 Provide devices needed to layout and construct work.
- .4 Supply such devices as straight edges and templates required to facilitate Departmental Representative's inspection of work.
- .5 Supply stakes and other survey markers required for laying out work.

1.9 COST BREAKDOWN

- .1 Before submitting first progress claim submit breakdown of Contract price in detail as directed by Departmental Representative and aggregating contract price.
- .2 Provide cost breakdown in same format as the numerical and subject title system used in this specification project manual and thereafter sub-divided into major work components as directed by Departmental Representative.
- .3 Upon approval by Departmental Representative, cost breakdown will be used as basis for progress payment.
- .4 All work items not designated in the unit price table as a measurement for payment, are incidental to the project or are to be included in the lump sum arrangement, as noted on the Tender Form.

1.10 WORK SCHEDULE

- .1 Submit within 7 work days of notification of acceptance of bid, a construction schedule showing commencement and completion of all work within the time stated on the Bid and Acceptance Form and the date stated in the bid acceptance letter.

- .2 Provide sufficient details in schedule to clearly illustrate entire implementation plan, depicting efficient coordination of tasks and resources, to achieve completion of work on time and permit effective monitoring of work progress in relation to established milestones.
- .3 As a minimum, work schedule to be prepared and submitted in the form of Bar (GANTT) Charts, indicating work activities, tasks and other project elements, their anticipated durations and planned dates for achieving key activities and major project milestones provided in sufficient details and supported by narratives to demonstrate a reasonable plan for completion of project within designated time, e.g., show target dates for the placement of each crib, if applicable. Generally Bar Charts derived from commercially available computerized project management system are preferred but not mandatory.
- .4 Submit schedule updates on a minimum monthly basis and more often, when requested by Departmental Representative, due to frequent changing project conditions. Provide a narrative explanation of necessary changes and schedule revisions at each update.
- .5 The schedule, including all updates, shall be to Departmental Representative's approval. Take necessary measures to complete work within approved time. Do not change schedule without Departmental Representative's approval.
- .6 All work on the project will be completed within the time indicated on the Bid and Acceptance Form.

1.11 ABBREVIATIONS

- .1 Following abbreviations of standard specifications have been used in this specification and on the drawings:
- CGSB - Canadian Government Specifications Board
CSA - Canadian Standards Association
NLGA - National Lumber Grades Authority
ASTM - American Society for Testing and Materials
- .2 Where these abbreviations and standards are used in this project, latest edition in effect on date of bid call will be considered applicable.

1.12 QUARRY AND EXPLOSIVES

- .1 Make own arrangements with Provincial authorities and owners of private properties, for the quarrying and transportation of rock and all materials and machinery necessary for work over their property, roads or streets as case may be.

1.13 SITE OPERATIONS

- .1 Arrange for sufficient space adjacent to project site for conduct of operations, storage of materials and so on. Exercise care so as not to obstruct or damage public or private property in area. Do not interfere with normal day-to-day operations in progress at site. All arrangements for space and access will be made by Contractor.
- .2 Remove snow and ice as required to maintain safe access in a manner that does not damage existing structures or interfere with the operations of others.

1.14 PROJECT MEETINGS

- .1 Departmental Representative will arrange project meetings and assume responsibility for setting times and recording minutes.

- .2 Project meetings will take place on site of work unless so directed by the Departmental Representative.
- .3 Departmental Representative will assume responsibility for recording minutes of meetings and forwarding copies to all parties present at the meetings.
- .4 Have a responsible member of firm present at all project meetings.

1.15 PROTECTION

- .1 Store all materials and equipment to be incorporated into work to prevent damage by any means.
- .2 Repair or replace all materials or equipment damaged in transit or storage to the satisfaction of Departmental Representative and at no cost to Canada.

1.16 EXISTING SERVICES

- .1 Where work involves breaking into or connecting to existing services, carry out work at times directed by governing authorities, with minimum of disturbance to site operations, pedestrian, vehicular traffic and tenant operations.
- .2 Before commencing work, establish location and extent of service lines in area of work and notify Departmental Representative of findings.
- .3 Submit schedule to and obtain approval from Departmental Representative for any shut-down or closure of active service or facility. This includes disconnection of electrical power and communication services to tenant's operational areas. Adhere to approved schedule and provide notice to affected parties.
- .4 Provide temporary services when directed

by Departmental Representative to maintain critical facility systems.

- .5 Provide adequate bridging over trenches which cross walkways or roads to permit normal traffic.
- .6 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .7 Protect, relocate or maintain existing active services as required. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction over service. Record locations of maintained, re-routed and abandoned service lines.

1.17 DOCUMENTS
REQUIRED

- .1 Maintain at job site, one copy each of the following:
 - .1 Contract Drawings
 - .2 Specifications
 - .3 Addenda
 - .4 Reviewed Shop Drawings
 - .5 List of outstanding shop drawings
 - .6 Change Orders
 - .7 Other modifications to Contract
 - .8 Field Test Reports
 - .9 Copy of Approved Work Schedule
 - .10 Site specific Health and Safety Plan and other safety related documents
 - .11 Other documents as stipulated elsewhere in the Contract Documents.

1.18 PERMITS

- .1 Obtain and pay for all permits, certificates and licenses as required by Municipal, Provincial, Federal and other Authorities.
- .2 Provide appropriate notifications of project to municipal and provincial

inspection authorities.

.3 Obtain compliance certificates as prescribed by legislative and regulatory provisions of municipal, provincial and federal authorities as applicable to the performance of work.

.4 Submit to Departmental Representative, copy of application submissions and approval documents received for above referenced authorities.

.5 Submit to Departmental Representative, copy of quarry permit, if applicable, prior to start of quarry operations.

.6 Comply with all requirements, recommendations and advice by all regulatory authorities unless otherwise agreed in writing by Departmental Representative. Make requests for such deviations to these requirements sufficiently in advance of related work.

1.19 CUTTING,
FITTING AND
PATCHING

.1 Execute cutting, including excavation, fitting and patching required to make work fit properly.

.2 Where new work connects with existing and where existing work is altered, cut, patch and make good to match existing work. This includes patching of openings in existing work resulting from removal of existing services.

.3 Do not cut, bore, or sleeve load-bearing members.

.4 Make cuts with clean, true, smooth edges. Make patches inconspicuous in final assembly.

- 1.20 EXISTING SUB-SURFACE CONDITIONS
- .1 Information pertaining to the existing sub-surface conditions may be available by contacting the Departmental Representative.
 - .2 Contractors are cautioned that any previous investigations that may be available for review, were intended to provide general site information only. Any interpolation and/or assumptions made relative to any previous investigations is the Contractor's responsibility.
- 1.21 LOCATION OF EQUIPMENT
- .1 Location of cleats, poles, ladders, power pedestals and outlets, shown or specified shall be considered as approximate. Actual location shall be as required to suit conditions at time of installation and as is reasonable. Obtain approval of Departmental Representative.
 - .2 Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space and in accordance with manufacturer's recommendations for safety, access and maintenance.
 - .3 Inform Departmental Representative when impending installation conflicts with other new or existing components. Follow directives for actual location.
 - .4 Submit field drawings to indicate relative position of various services and equipment when required by Departmental Representative.
- 1.22 FISH HABITAT
- .1 This work is being conducted in an area where fish habitat may be affected. Perform work to conform with rules and regulations governing fish habitat and in accordance with authorization for work or

undertakings affecting fish habitat.

- .2 Contact the local Department of Fisheries and Oceans detachment at least 48 hours in advance of starting any work on site. Submit confirmation to the Departmental Representative that DFO have been contacted.

1.23 NOTICE TO SHIPPING/MARINERS

- .1 Notify the Marine Communications and Traffic Services' Centre, of Fisheries and Oceans Canada, at (709) 772-2083, ten (10) days prior to commencement and upon completion of the work, in order to allow for the issuance of Notices to Shipping/Mariners.
- .2 During construction any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.

1.24 ACCEPTANCE

- .1 Prior to the issuance of the Certificate of Substantial Performance, in company with Departmental Representative, make a check of all work. Correct all discrepancies before final inspection and acceptance.

1.25 WORKS COORDINATION

- .1 Responsible for coordinating the work of the various trades, where the work of such trades interfaces with each other.
- .2 Convene meetings between trades whose work interfaces and ensure that they are fully aware of the areas and the extent of where interfacing is required. Provide each trade with the plans and specifications of the interfacing trade, as required, to assist them in planning and carrying out their respective work.

- .3 Canada will not be responsible for or held accountable for any extra costs incurred as a result of the failure to carry out coordination work. Disputes between the various trades as a result of their not being informed of the areas and extent of interface work shall be the sole responsibility of the General Contractor and shall be resolved at no extra cost to Canada.

1.26 CONTRACTOR'S
USE OF SITE

- .1 Construction operations, including storage of materials for this contract, not to interfere with the fishing activity and/or operations at this harbour facility.
- .2 Responsible for arranging the storage of materials on or off site, and any materials stored at the site which interfere with any of the day to day activities at or near the site will be moved promptly at the Contractor's expense, upon request by Departmental Representative.
- .3 Contractor will take adequate precautions to protect existing concrete decks and asphalt when operating tracked equipment.
- .4 Exercise care so as not to obstruct or damage public or private property in the area.
- .5 At completion of work, restore area to its original condition. Damage to ground and property will be repaired by Contractor. Remove all construction materials, residue, excess, etc., and leave site in a condition acceptable to Departmental Representative.

1.27 WORK
COMMENCEMENT

- .1 Mobilization to project site is to commence immediately after acceptance of bid and submission of Site Specific Safety Plan and insurance documentation, unless otherwise agreed by Departmental Representative.
- .2 Project work on site is to commence as soon as possible, with a continuous reasonable work force, unless otherwise agreed by Departmental Representative.
- .3 Weather conditions, short construction season, delivery challenges and the location of the work site may require the use of longer working days and additional work force to complete the project within the specified completion time.
- .4 Make every effort to ensure that sufficient material and equipment is delivered to site at the earliest possible date after acceptance of bid and replenished as required.

1.28 FACILITY
SMOKING ENVIRONMENT

- .1 Comply with smoking restrictions.

1.29 INTERPRETATION
OF DOCUMENTS

- .1 Supplementary to the Order of Precedence article of the General Conditions of the Contract, the Division 01 sections take precedence over the technical specification sections in other Divisions of the Specification Manual.

1.30 WORKING ADJACENT
TO ROUTE 92

- 1. A permit to work on the highway right of way will be required for this contract. The Contractor is to contact Mike Singleton (or his representative) at the Provincial department of Transportation and Works St. Joseph's Depot (telephone 521-2230) to obtain an approved permit.

The Contractor will be responsible for abiding by the terms of the permit and paying any permitting fees.

2. The Contractor will be responsible to restore any damage to existing highway components and must ensure that the gravel shoulders along the highway are fully restored upon the completion of the required work.
3. The Contractor shall ensure that all work adjacent to the highway on the highway right of way is in accordance with the requirements of the Department of Transportation and Works "Traffic Control Manual" latest edition. A copy of this manual is available on-line or by contacting the Provincial Department of Transportation and Works.

1.31 TIMING
RESTRICTIONS ON IN-
WATER WORK

1. No in-water work will be permitted before October 15, 2015, or after March 31, 2016.

PART 1 - GENERAL

- 1.1 SECTION INCLUDES
- .1 Inspecting and testing by inspecting firms or testing laboratories designated by Departmental Representative.
- 1.2 RELATED REQUIREMENTS SPECIFIED ELSEWHERE
- .1 Particular requirements for inspection and testing to be carried out by testing laboratory designated by Departmental Representative are specified under various sections.
- 1.3 APPOINTMENT AND PAYMENT
- .1 The Department will appoint and pay for services of testing laboratory except for the following:
- .1 Inspection and testing required by laws, ordinances, rules, regulations or orders of public authorities.
 - .2 Inspection and testing performed exclusively for Contractor's convenience.
 - .3 Mill tests and certificates of compliance.
 - .4 Tests specified to be carried out by Contractor under the supervision of Departmental Representative.
 - .5 Tests requested by Departmental Representative to confirm material specifications when the applicable manufacturer's documentation or test results are unavailable.
 - .6 Additional tests specified in the following paragraph.
- .2 Where tests or inspections by designated testing laboratory reveal Work not in accordance with contract requirements, pay costs for additional tests or inspections as required by Departmental Representative

to verify acceptability of corrected work.

1.4 CONTRACTOR'S
RESPONSIBILITIES

- .1 Provide labour, equipment and facilities to:
 - .1 Provide access to Work to be inspected and tested.
 - .2 Facilitate inspections and tests.
 - .3 Make good Work disturbed by inspection and test.
 - .4 Provide storage on site for laboratory's exclusive use to store equipment and cure test samples.
- .2 Notify Departmental Representative sufficiently in advance of operations to allow for assignment of laboratory personnel and scheduling of test.
- .3 Where materials are specified to be tested, deliver representative samples in required quantity to testing laboratory.
- .4 Pay costs for uncovering and making good Work that is covered before required inspection or testing is completed and approved by Departmental Representative.

PART 2 - PRODUCTS

- 2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED .1 Not Used.

PART 1 - GENERAL

1.1 SECTION
INCLUDES

- .1 Shop drawings and product data.
- .2 Samples.
- .3 Certificates.

1.2 SUBMITTAL
GENERAL REQUIREMENTS

- .1 Submit to Departmental Representative for review submittals listed, including shop drawings, samples, certificates and other data, as specified in other sections of the Specifications.
- .2 Submit with reasonable promptness and in orderly sequence so as to allow for Departmental Representative's review and not cause delay in Work. Failure to submit in ample time will not be considered sufficient reason for an extension of Contract time and no claim for extension by reason of such default will be allowed.
- .3 Do not proceed with work until relevant submissions are reviewed by Departmental Representative.
- .4 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .5 Where items or information is not produced in SI Metric units, provide soft converted values.
- .6 Review submittals prior to submission to Departmental Representative. Ensure during review that necessary requirements have been determined and verified, required field

measurements or data have been taken, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents.

.1 Submittals not stamped, signed, dated and identified as to specific project will be returned unexamined by Departmental Representative and considered rejected.

- .7 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .8 Verify field measurements and affected adjacent work and coordinate.
- .9 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .10 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative's review.
- .11 Submittal format: paper originals, or alternatively clear and fully legible photocopies of originals. Facsimiles are not acceptable, except in special circumstances pre-approved by Departmental Representative. Poorly printed non-legible photocopies or facsimiles will not be accepted and be returned for resubmission.
- .12 Make changes or revision to submissions which Departmental Representative may require, consistent with Contract Documents and resubmit as directed by Departmental Representative. When resubmitting, notify Departmental Representative in writing of any revisions other than those requested.

- .13 Keep one reviewed copy of each submittal document on site for duration of Work.

1.3 SHOP DRAWINGS
AND PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, product data, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Number of Shop Drawings: submit sufficient copies of shop drawings which are required by the General Contractor and sub-contractors plus 2 copies which will be retained by Departmental Representative. Ensure sufficient numbers are submitted to enable one complete set to be included in each of the maintenance manuals specified, if applicable.
- .3 Shop Drawings Content and Format:
 - .1 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where items or equipment attach or connect to other items or equipment, confirm that all interrelated work have been coordinated, regardless of section or trade from which the adjacent work is being supplied and installed.
 - .2 Shop Drawings Format:
 - .1 Opaque white prints or photocopies of original drawings or standard drawings modified to clearly illustrate work specific to project requirements. Maximum sheet size to be 1000 x 707 mm.
 - .2 Product Data from manufacturer's standard catalogue sheets, brochures, literature, performance charts and diagrams, used to illustrate standard manufactured products, to be original full colour brochures, clearly marked

- indicating applicable data and deleting information not applicable to project.
- .3 Non or poorly legible drawings, photocopies or facsimiles will not be accepted and returned not reviewed.
 - .3 Supplement manufacturer's standard drawings and literature with additional information to provide details applicable to project.
 - .4 Delete information not applicable to project on all submittals.
 - .4 Allow 10 calendar days for Departmental Representative's review of each submission.
 - .5 Adjustments or corrections made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, advise Departmental Representative in writing prior to proceeding with Work.
 - .6 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections and comments are made, fabrication and installation may proceed upon receipt of shop drawings. If shop drawings are rejected and noted to be Resubmitted, do not proceed with that portion of work until resubmission and review of corrected shop drawings, through same submission procedures indicated above.
 - .7 Accompany each submission with transmittal letter, containing:
 - .1 Date.
 - .2 Project title and project number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Other pertinent data.
 - .8 Submissions shall include:
 - .1 Date and revision dates.

- .2 Project title and project number.
- .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
- .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
- .5 Cross references to particular details of contract drawings and specifications section number for which shop drawing submission addresses.
- .6 Details of appropriate portions of Work as applicable:
 - .1 Fabrication.
 - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - .3 Setting or erection details.
 - .4 Capacities.
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - .8 Wiring diagrams.
 - .9 Single line and schematic diagrams.
 - .10 Relationship to adjacent work.
- .9 After Departmental Representative's review, distribute copies.
- .10 The review of shop drawings by the Departmental Representative or their delegated representative is for sole purpose of ascertaining conformance with general concept. This review shall not mean that the Departmental Representative approves the detail design inherent in the shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in

shop drawings or of responsibility for meeting all requirements of the construction and Contract Documents. Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of all sub-trades.

1.4 SCHEDULES,
PERMITS AND
CERTIFICATES

- .1 Upon acceptance of bid, submit to Departmental Representative copy of Work Schedule and various other schedules, permits, certification documents and project management plans as specified in other sections of the Specifications.
- .2 Submit copy of permits, notices, compliance Certificates received by Regulatory Agencies having jurisdiction and as applicable to the Work.
- .3 Submission of above documents to be in accordance with Submittal General Requirements procedures specified in this section.

1.1 SECTION
INCLUDES

- .1 Fire Safety Requirements.
- .2 Hot Work Permit.

1.2 RELATED WORK

- .1 Section 01 35 25 - Special Procedures on Lockout Requirements.
- .2 Section 01 35 28 - Health and Safety Requirements.

1.3 REFERENCES

- .1 Fire Protection Standards issued by Fire Protection Services of Human Resources Development Canada as follows:
 - .1 FCC No. 301-June 1982 Standard for Construction Operations (http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/commissioner/301/page00.shtml).
 - .2 FCC No. 302-June 1982 Standard for Welding and Cutting (http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/commissioner/302/page00.shtml).
 - .3 FCC standards, may also be viewed at the Regional Fire Protection Services' office (previously known as the Fire Commissioner of Canada) located at 99 Wyse Road, 8th Floor, Dartmouth, NS, Tel: (902) 426-6053.

1.4 DEFINITIONS

- .1 Hot Work defined as:
 - .1 Welding work.
 - .2 Cutting of materials by use of torch or other open flame devices.
 - .3 Grinding with equipment which produces sparks.

1.5 SUBMITTALS

- .1 Submit copy of Hot Work Procedures and sample of Hot Work permit to Departmental Representative for review, within 14 calendar days after notification of acceptance of bid.
- .2 Submit in accordance with the Submittal General Requirements specified in Section 01 33 00.

1.6 FIRE SAFETY
REQUIREMENTS

- .1 Implement and follow fire safety measures during Work. Comply with following:
 - .1 National Fire Code, 2005
 - .2 Fire Protection Standards FCC 301 and FCC 302.
 - .3 Federal and Provincial Occupational Health and Safety Acts and Regulations as specified in Section 01 35 28.
- .2 In event of conflict between any provisions of above authorities the most stringent provision will apply. Should a dispute arise in determining the most stringent requirement, Departmental Representative will advise on the course of action to be followed.

1.7 HOT WORK
AUTHORIZATION

- .1 Obtain Departmental Representative's written "Authorization to Proceed" before conducting any form of Hot work on site.
- .2 To obtain authorization submit to Departmental Representative:
 - .1 Contractor's typewritten Hot Work Procedures to be followed on site as specified below.
 - .2 Description of the type and frequency of Hot Work required.
 - .3 Sample Hot Work Permit to be used.

- .3 Upon review and confirmation that effective fire safety measures will be implemented during performance of hot work, Departmental Representative will provide authorization to proceed as follows:
 - .1 Issue one written "Authorization to Proceed" covering the entire project for duration of work or;
 - .2 Separate work, or segregate certain parts of work, into individual entities. Each entity requiring a separately written "Authorization to Proceed" from Departmental Representative. Follow Departmental Representative's directives in this regard.
- .4 Requirement for individual authorization based on:
 - .1 Nature or phasing of work;
 - .2 Risk to Facility operations;
 - .3 Quantity of various trades needing to perform hot work on project or;
 - .4 Other situation deemed necessary by Departmental Representative to ensure fire safety on premises.
- .5 Do not perform any Hot Work until receipt of Departmental Representative's written "Authorization to Proceed" for that portion of work.
- .6 In tenant occupied Facility, coordinate performance of Hot Work with Facility Manager through the Departmental Representative. When directed, perform Hot Work only during non-operative hours of Facility. Follow Departmental Representative's directives in this regard.

1.8 HOT WORK
PROCEDURES

- .1 Develop and implement safety procedures and work practices to be followed during the performance of Hot Work.

- .2 Procedures to include:
 - .1 Requirement to perform hazard assessment of site and immediate hot work area for each hot work event in accordance with Hazard Assessment and Safety Plan requirements of Section 01 35 28.
 - .2 Use of a Hot Work Permit system for each hot work event.
 - .3 The step by step process of how to prepare and issue permit.
 - .4 Permit shall be issued by Contractor's site Superintendent, or other authorized person designated by Contractor, granting permission to worker or subcontractor to proceed with hot work.
 - .5 Provision of a designated person to carryout a Fire Safety Watch for a minimum of 60 minutes immediately upon completion of the hot work.
 - .6 Compliance with fire safety codes and standards specified herein and occupational health and safety regulations specified in Section 01 35 28.
- .3 Generic procedures, if used, must be edited and supplemented with pertinent information tailored to reflect specific project conditions. Clearly label as being the Hot Work Procedures applicable to this contract.
- .4 Hot Work Procedures shall clearly establish worker instructions and allocate responsibilities of:
 - .1 Worker(s),
 - .2 Authorized person issuing the Hot Work Permit,
 - .3 Fire Safety Watcher,
 - .4 Subcontractors and Contractor.
- .5 Brief all workers and subcontractors on Hot Work Procedures and Permit system established for project. Stringently enforce compliance.
 - .1 Failure to comply with the established procedures may result in the issuance of a

Non-Compliance Notification at Departmental Representative's discretion with possible disciplinary measures imposed as specified in Section 01 35 28.

1.9 HOT WORK
PERMIT

- .1 Hot Work Permit to include, as a minimum, the following data:
 - .1 Project name and project number.
 - .2 Building name, address and specific room or area where hot work will be performed.
 - .3 Date when permit issued.
 - .4 Description of hot work type to be performed.
 - .5 Special precautions required, including type of fire extinguisher needed.
 - .6 Name and signature of person authorized to issue the permit.
 - .7 Name of worker (clearly printed) to which the permit is being issued.
 - .8 Time Duration that permit is valid (not to exceed 8 hours). Indicate start time and date, and completion time and date.
 - .9 Worker signature with date and time upon hot work termination.
 - .10 Specified time period requiring safety watch.
 - .11 Name and signature of designated Fire Safety Watcher, complete with time and date when safety watch terminated, certifying that surrounding area was under continual surveillance and inspection during the full watch time period specified in Permit and commenced immediately upon completion of Hot Work.
- .2 Permit to be typewritten form. Industry Standard forms shall only be used if all data specified above is included on form.
- .3 Each Hot Work Permit to be completed in full and signed as follows:
 - .1 Authorized person issuing Permit before hot work commences.
 - .2 Worker upon completion of Hot Work.

.3 Fire Safety Watcher upon termination of safety watch.

.4 Returned to Contractor's Site Superintendent for safe keeping.

1.10 DOCUMENTS
ON SITE

.1 Keep Hot Work Permits and Hazard assessment documentation on site for duration of Work.

.2 Upon request, make available to Departmental Representative or to authorized safety representative for inspection.

1.1 SECTION INCLUDES .1 Procedures to isolate and lockout electrical facility or other equipment from energy source.

1.2 RELATED WORK .1 Section 01 35 24 - Fire Safety Requirements.
.2 Section 01 35 28 - Health and Safety Requirements.

1.3 REFERENCES .1 C22.1-06 - Canadian Electrical Code, Part 1, Safety Standard for Electrical Installations.
.2 CAN/CSA C22.3 No. 1-10 - Overhead Systems.
.3 CAN/CSA C22.3 No. 7-10 - Underground Systems.
.4 COSH, Canada Occupational Health and Safety Regulations made under Part II of the Canada Labour Code.

1.4 DEFINITIONS .1 Electrical Facility: means any system, equipment, device, apparatus, wiring, conductor, assembly or part thereof that is used for the generation, transformation, transmission, distribution, storage, control, measurement or utilization of electrical energy, and that has an amperage and voltage that is dangerous to persons.
.2 Guarantee of Isolation: means a guarantee by a competent person in control or in charge that a particular facility or equipment is isolated.
.3 De-energize: in the electrical sense, that a piece of equipment is isolated and grounded,

e.g. if the equipment is not grounded, it cannot be considered de-energized (DEAD).

- .4 Guarded: means that an equipment or facility is covered, shielded, fenced, enclosed, inaccessible by location, or otherwise protected in a manner that, to the extent that is reasonably practicable, will prevent or reduce danger to any person who might touch or go near such item.
- .5 Isolate: means that an electrical facility, mechanical equipment or machinery is separated or disconnected from every source of electrical, mechanical, hydraulic, pneumatic or other kind of energy that is capable of making it dangerous.
- .6 Live/alive: means that an electrical facility produces, contains, stores or is electrically connected to a source of alternating or direct current of an amperage and voltage that is dangerous or contains any hydraulic, pneumatic or other kind of energy that is capable of making the facility dangerous to persons.

1.5 COMPLIANCE
REQUIREMENTS

- .1 Perform lockouts in compliance with:
 - .1 Canadian Electrical Code.
 - .2 Federal and Provincial Occupational Health and Safety Acts and Regulations as specified in Section 01 35 28.
 - .3 Regulations and code of practice as applicable to mechanical equipment or other machinery being de-energized.
 - .4 Procedures specified herein.
- .2 In event of conflict between any provisions of above authorities the most stringent provision will apply. Should a dispute arise in determining the most stringent requirement, Departmental Representative

1.6 SUBMITTALS

will advise on the course of action to be followed.

- .1 Submit copy of proposed Lockout Procedures and sample form of lockout permit or lockout tags for review.
- .2 Submit documentation within 7 calendar days of acceptance of bid. Do not proceed with work until submittal has been reviewed by Departmental Representative.
- .3 Submit above documents in accordance with the submittal requirements specified in Section 01 33 00.
- .4 Resubmit Lockout Procedures with noted revisions as may result from Departmental Representative's review.

1.7 ISOLATION OF
EXISTING SERVICES

- .1 Obtain Departmental Representative's written authorization prior to conducting work on an existing active, energized service or facility required as part of the work and before proceeding with lockout of such services or facility.
- .2 To obtain authorization, submit to Departmental Representative the following documentation:
 - .1 Written Request for Isolation of the service or facility and;
 - .2 Copy of Contractor's Lockout Procedures.
- .3 Make a Request for Isolation for each event, unless directed otherwise by Departmental Representative, and as follows:
 - .1 Fill-out standard forms in current use at the Facility when so directed by Departmental Representative or;
 - .2 Where no form exist at Facility, make request in writing identifying:

- .1 Identification of system or equipment to be isolated, including it's location;
- .2 Time duration, indicating Start time and date, and Completion time and date when isolation will be in effect;
- .3 Voltage of service feed to system or equipment being isolated;
- .4 Name of person making the request.
- .3 Document to be in typewritten format.
- .4 Do not proceed until receipt of written notification from Departmental Representative granting the Isolation Request and authorization to proceed with the isolation of designated equipment or facility. Departmental Representative may designate other individual at the Facility as the person authorized to grant the Isolation Request.
- .5 Conduct safe, orderly shut down of equipment or facilities, de-energize and isolate power and other sources of energy and lockout items in accordance with requirement of clause 1.8 below.
- .6 Plan and schedule shut down of existing services in consultation with the Departmental Representative and the Facility Manager. Minimize impact and downtime of facility operations.
- .7 Determine in advance, as much as possible, in cooperation with the Departmental Representative, the type and frequency of situations which will require a Request for Isolation. Follow Departmental Representative's directives in this regard.
- .8 Conduct hazard assessment as part of the planning process of isolating existing equipment and facilities. Hazard Assessments to conform with requirements of Health and

Safety Section 01 35 28.

1.8 LOCKOUTS

- .1 Isolate and lockout electrical facilities, mechanical equipment and machinery from all potential energy sources prior to starting work on such items.
- .2 Develop and implement lockout procedures to be followed on site as an integral part of the Work.
- .3 Use energy isolation lockout devices specifically designed and appropriate for type of facility or equipment being locked out.
- .4 Use industry standard lockout tags.
- .5 Provide appropriate safety grounding and guards as required.
- .6 Prepare Lockout Procedures in writing. Describe safe work practices, work functions and sequence of activities to be followed on site to safely isolate all potential energy sources and lockout/tagout facilities and equipment.
- .7 Include within procedures a system of worker request and issuance of individual lockout permit by a person, employed by Contractor, designated to be "in-charge" and being responsible for:
 - .1 Controlling issuance of permits or tags to workers.
 - .2 Determining permit duration.
 - .3 Maintaining record of permits and tags issued.
 - .4 Submitting a Request for Isolation to Departmental Representative when required in accordance with Clause 1.7 above.
 - .5 Designating a Safety Watcher, when one

is required based on type of work.

.6 Ensuring equipment or facility has been properly isolated, providing a Guarantee of Isolation to worker(s) prior to proceeding with work.

.7 Collecting and safekeeping lockout tags, returned by workers, as a record of the event.

.8 Clearly establish, describe and allocate, within procedures, the responsibilities of:

.1 Workers.

.2 Designated person controlling issuance of lockout tags/permits.

.3 Safety Watcher.

.4 Subcontractors and General Contractor.

.9 Procedures shall meet the requirements of Codes and Regulations specified in clause 1.5 above.

.10 Generic procedures, if used, must be edited, supplemented with pertinent information and tailored to reflect specific project conditions. Clearly label as being the procedures applicable to this contract.

.1 Incorporate site specific rules and procedures established by Facility Manager and in force at site. Obtain such procedures through Departmental Representative.

.11 Procedures to be in typewritten format.

.12 Submit copy of Lockout Procedures to Departmental Representative, in accordance with submittal requirements of clause 1.6 herein, prior to commencement of work.

1.9 CONFORMANCE

.1 Ensure that lockout procedures, as established for project on site, are stringently followed. Enforce use and compliance by all workers.

- .2 Brief all persons working on electrical facilities, mechanical and other equipment fed by an energy source on requirements of this section.
- .3 Failure to perform lockouts in accordance with regulatory requirements or follow procedures specified herein may result in the issuance of a Non-Compliance Notification at Departmental Representative's discretion with possible disciplinary measures imposed as specified in Section 01 35 28.

1.10 DOCUMENTS
ON SITE

- .1 Post Lockout Procedures on site in common location for viewing by workers.
- .2 Keep copies of Request for Isolation submitted to Departmental Representative and lockout permits or tags issued to workers during the course of work for full project duration.
- .3 Upon request, make such data available to Departmental Representative or to authorized safety representative for inspection.

- 1.1 RELATED WORK
- .1 Section 01 35 24 - Special Procedures on Fire Safety Requirements.
 - .2 Section 01 35 25 - Special Procedures on Lockout Requirements.
- 1.2 SUBMITTALS
- .1 Submit to Departmental Representative copies of the following documents, including updates:
 - .1 Site Specific Health and Safety Plan.
 - .2 Building Permit, compliance certificates and other permits obtained.
 - .3 Reports or directions issued by Federal and Provincial Inspectors and other Authorities having jurisdiction.
 - .4 Accident or Incident Reports.
 - .5 MSDS data sheets.
 - .6 Name of Contractor's representative designated to perform full time health and safety supervision on site.
 - .7 Letter of Good Standing/Certificate of Clearance from the provincial Workers Compensation Board.
 - .2 Upon request by Departmental Representative, submit reports and other documentation as stipulated to be produced and maintained by Federal and Provincial Occupational Health and Safety Regulations and as specified herein.
 - .3 Submit above documents in accordance with the submittal procedures specified in Section 01 33 00.
- 1.3 COMPLIANCE REQUIREMENTS
- .1 Comply with the Occupational Health and Safety Act for the Province of Newfoundland and Labrador, and the Occupational Health and Safety Regulations made pursuant to the Act.

- .2 Comply with Canada Labour Code Part II, and the Canada Occupational Safety and Health Regulations made under Part II of the Canada Labour Code.
- .3 Observe and enforce construction safety measures required by:
 - .1 National Building Code of Canada, Part 8, latest edition.
 - .2 Provincial Worker's Compensation Board.
 - .3 Municipal statutes and ordinances.
- .4 In event of conflict between any provisions of above authorities the most stringent provision will apply. Should a dispute arise in determining the most stringent requirement, Departmental Representative will advise on the course of action to be followed.
- .5 A copy of the Canada Labour Code Part II may be obtained by contacting:

Canadian Government Publishing
Public Works and Government Services Canada
Ottawa, Ontario, K1A 0S9 Tel: (819) 956-4800
(1-800-635-7943) Publication No. L31-85/2000 E
or F).

- .6 Maintain Workers Compensation Coverage for duration of Contract. Submit Letter of Good Standing to Departmental Representative at time of submitting the Project Health and Safety Plan and with each Request for Progress Payment.

1.4 RESPONSIBILITY

- .1 Be responsible for health and safety of persons on site, of property and for protection of persons and public circulating adjacent to work operations to extent that they may be affected by

conduct of the Work.

- .2 Enforce compliance by all workers, sub-contractors and other persons granted access to work site with safety requirements of Contract Documents, applicable Federal, Provincial, and local statutes, regulations, and ordinances, and with site specific Health and Safety Plan.

1.5 SITE CONTROL
AND ACCESS

- .1 Control work site and entry points to construction areas.
 - .1 Delineate and isolate construction areas from other areas of site by use of appropriate means.
 - .2 Post notices and signage at entry points and at other strategic locations identifying entrance onto site to be restricted to authorized persons only.
 - .3 Signage must be professionally made, bilingual in both official languages or display internationally understood graphic symbols.
- .2 Approve and grant access to site only to workers and authorized persons.
 - .1 Immediately stop non-authorized persons from circulating in construction areas and remove from site.
 - .2 Provide site safety orientation to all persons before granting access. Advise of site conditions, hazards and mandatory safety rules to be observed on site.
- .3 Secure site at night time to extent required to protect against unauthorized entry. Provide security guard where protection cannot be achieved by other means.
- .4 Ensure persons granted access to site wear appropriate personal protective equipment

(PPE) suitable to work and site conditions.

.1 Provide such PPE to authorized persons who require access to perform inspections or other approved purposes.

1.6 PROTECTION

.1 Carry out work placing emphasis on health and safety of the Public, Facility personnel, construction workers and protection of the environment.

.2 Erect safety barricades, lights and signage on site to effectively delineate work areas, protect pedestrian and vehicular traffic around and adjacent to work, and to create a safe working environment.

.1 Erect fences, hoarding, protective barriers and temporary lighting as required. See Section 01 56 00 for minimum acceptable barricades.

.3 Should unforeseen or peculiar safety related hazard or condition become evident during performance of work, immediately take measures to rectify the situation and prevent damage or harm. Advise Departmental Representative verbally and in writing.

1.7 PERMITS

.1 Obtain building permit, licenses, compliance certificates and other permits as specified in Section 01 10 10 before and during progress of work. Post on site.

.2 Where particular permit or compliance certificate cannot be obtained at the required stage of work, notify Departmental Representative in writing and obtain Departmental Representative's

approval to proceed prior to carrying out that portion of work.

1.8 HAZARD
ASSESSMENTS

- .1 Conduct site specific health and safety hazard assessment before commencing project and during course of work identifying risks and hazards resulting from site conditions, weather conditions and work operations.
 - .1 Perform on-going assessments addressing new risks and hazards as work progresses including when new subtrade or sub-contractor arrives on site.
 - .2 Also, conduct assessment when the scope of work has been changed by Change Order and when potential hazard or weakness in current health and safety practices are identified by Departmental Representative or by an authorized safety representative.
- .2 Record results in writing and address in Health and Safety Plan.
- .3 Keep copy of all assessments on site.

1.9 PROJECT/SITE
CONDITIONS

- . 1 The following are known or potential project related safety hazards at site:
 - .1 Working in close proximity of water.
 - .2 Use of water crafts and floating platforms.
 - .3 Wet and slippery conditions.
 - .4 Inclement weather.
 - .5 Potential structural weakness of existing structures.
 - .6 Heavy equipment activity in the area.
 - .7 Heavy lifting.
 - .8 Working at heights.

- .9 Cutting tools and other construction power tools.
- .10 Overhead power/utility lines.
- .11 Risk of electric shock.
- .12 Vehicular and pedestrian traffic.
- .13 Confined spaces.

.2 Above list shall not be construed as being complete and inclusive of potential health, and safety hazards encountered during work. Include above items into hazard assessment process.

.3 Obtain from Departmental Representative, copy of MSDS Data sheets for existing hazardous products stored on site or used by Facility personnel.

1.10 HEALTH AND SAFETY MEETINGS

.1 Attend pre-construction health and safety meeting conducted by Departmental Representative. Have following persons in attendance:

- .1 Site Superintendent.
- .2 Contractor's designated Health and Safety Site Supervisor.
- .3 Departmental Representative will advise of date, time and location.

.2 Conduct health and safety meetings and tool box briefings on site. Hold on a regular and pre-scheduled basis during entire work in accordance with requirements and frequency as stipulated in provincial Occupational Health and Safety Regulations.

- .1 Keep workers informed of potential hazards and provide safe work practices and procedures to be followed.
- .2 Take written minutes and post on site.
- .3 Conduct formal meetings on a minimum

monthly basis.

1.11 HEALTH AND
SAFETY PLAN

- .1 Develop written site specific Project Health and Safety Plan, based on hazard assessments, prior to commencement of work.
 - .1 Submit copy to Departmental Representative within 7 calendar days of acceptance of bid.
 - .2 Submit updates as work progresses.
- .2 Health and Safety Plan shall contain three (3) parts with following information:
 - .1 Part 1 - Hazards: List of individual health risks and safety hazards identified by hazard assessment process.
 - .2 Part 2 - Safety Measures: Engineering controls, personal protective equipment and safe work practices used to mitigate hazards and risks listed in Part 1 of Plan.
 - .3 Part 3a: Emergency Response: standard operating procedures, evacuation measures and emergency response in the occurrence of an accident, incident or emergency.
 - .1 Include response to all hazards listed in Part 1 of Plan.
 - .2 Evacuation measures to complement the Facility's existing Emergency Response and Evacuation Plan. Obtain pertinent information from Departmental Representative.
 - .3 List names and telephone numbers of officials to contact including:
 - .1 General Contractor and all Subcontractors.
 - .2 Federal and Provincial Departments as stipulated by laws and regulations of authorities having jurisdiction and local emergency resource organizations, as needed base on

nature of emergency.

.3 Officials from DFO and site Facility Management.

Departmental Representative will provide list.

.4 Part 3b - Site Communications:

.1 Procedures used on site to share work related safety issues between workers, subcontractors, and General Contractor.

.2 List of critical tasks and work activities, to be communicated with the Facility Manager, which has risk of affecting tenant operations, or endangering health and safety of Facility personnel and the general public. Develop list in consultation with the Departmental Representative.

.3 Prepare Health and Safety Plan in a three column format, addressing the three parts specified above, as follows:

Column 1	Column 2	Column 3
Part 1 Identified Hazards	Part 2 Safety Measures	Part 3a/3b Emergency Response & Site Communications

.4 Develop Plan in collaboration with subcontractors. Address work activities of all trades. Revise and update Plan as subcontractors arrive on site.

.5 Implement and enforce compliance with requirements of Plan for full duration of work to final completion and demobilization from site.

.6 As work progresses, review and update Plan. Address additional health risks and safety hazards identified by on-going hazard assessments.

- .7 Post copy of Plan and updates, on site.
- .8 Submission of the Health and Safety Plan and updates, to the Departmental Representative, is for review and information purposes only. Departmental Representative's receipt, review and any comments made of the Plan shall not be construed to imply approval in part, or in hold, of such Plan by Departmental Representative, and shall not be interpreted as a warranty of being complete and accurate, or as a confirmation that all health and safety requirements of the Work, have been addressed, and that it is legislative compliant. Furthermore, Departmental Representative's review of the Plan shall not relieve the Contractor of any of his legal obligations for Occupational Health and Safety provisions specified as part of the Work and those required by provincial legislation or those which would otherwise be applicable to the site of the work.

1.12 SAFETY
SUPERVISION AND
INSPECTIONS

- .1 Designate one person to be present on site at all times, responsible for supervising health and safety of the Work.
 - .1 Person to be competent in Occupational Health and Construction Safety as defined in the Provincial Occupational Health and Safety Act.
- .2 Assign responsibility, obligation and authority to such designated person to stop work as deemed necessary for reasons of health and safety.
- .3 Conduct regularly scheduled informal safety inspections of work site on a minimum bi-weekly basis.

.1 Note deficiencies and remedial action taken in a log book or diary.

.4 Keep inspection reports on site.

1.13 TRAINING

- .1 Ensure that all workers and other persons granted access to site are competently trained and knowledgeable on:
- .1 Safe use of tools and equipment.
 - .2 How to wear and use personal protective equipment (PPE).
 - .3 Safe work practices and procedures to be followed in carrying out work.
 - .4 Site conditions and minimum safety rules to be observed on site, as given at site orientation session.
- .2 Maintain evidence and records of worker training.

1.14 MINIMUM
SITE SAFETY RULES

- .1 Notwithstanding the requirement to abide by federal and provincial health and safety regulations, the following safety rules shall be considered minimum requirements to be obeyed by all persons granted site access:
- .1 Wear personnel protective equipment (PPE) appropriate to function and task on site; the minimum requirements being hard hat, safety footwear and eye protection.
 - .2 Immediately report unsafe activity or condition at site, near-miss accident, injury and damage.
 - .3 Maintain site in tidy condition.
 - .4 Obey warning signs and safety tags.
- .2 Brief workers on site safety rules and on disciplinary measures to be taken by Departmental Representative for violation or non-compliance of such rules. Post

rules on site.

- .3 The following actions or conduct by Contractor, workers and sub-contractors will be considered as non conformance with the health and safety requirements of the contract for which a Non-compliance Notification will be issued to the General Contractor by the Departmental Representative:
 - .1 Failure to follow the minimum site safety rules specified above.
 - .2 Negligence resulting in serious injury or major property damage.
 - .3 Deliberate non-compliance with Federal and Provincial Acts and Regulations.
 - .4 Falsification of information in Workers Compensation Reports, safety reports and other health and safety related documents submitted to Departmental Representative or to Authority having jurisdiction.
 - .5 Possession of firearms on site.
 - .6 Possession of non-prescriptive illegal drugs or alcohol.
 - .7 Action, or lack thereof, resulting in the issuance of Warnings, Fines or Stop Work Orders from a Provincial Authority having jurisdiction.
 - .8 Violation of other specified health and safety rules and requirements as determined by Departmental Representative.
- .4 See elsewhere in this section for details on Non-Compliance Notifications and resulting disciplinary measures.

1.15 ACCIDENT
REPORTING

- .1 Investigate and report the following incidents and accidents:
 - .1 Those as required by Provincial Occupational Safety and Health Act and

Regulations.

.2 Injury requiring medical aid as defined in the Canadian Dictionary of Safety Terms-1987, published by the Canadian Society of Safety Engineers (C.S.S.E) as follows:

.1 Medical Aid Injury: any minor injury for which medical treatment was provided and the cost of which is covered by Workers' Compensation Board of the province in which the injury was incurred.

.3 Property damage in excess of \$5000.00.

.4 Interruption to Facility operations with potential loss to a Federal Department in excess of \$5000.00.

.5 Those which require notification to Workers Compensation Board or other regulatory agencies as stipulated by applicable law or regulations.

.2 Send written report to Departmental Representative for all above cases.

1.16 TOOLS AND
EQUIPMENT SAFETY

.1 Routinely check and maintain tools, equipment and machinery for safe operation.

.2 Conduct checks as part of site safety inspections. When requested, submit proof that checks and maintenance have been carried out.

.3 Tag and immediately remove from site items found faulty or defective.

1.17 HAZARDOUS
PRODUCTS

.1 Comply with requirements of Workplace Hazardous Materials Information System (WHMIS).

- .2 Keep MSDS data sheets for all products delivered to site. Post on site. Submit copy to Departmental Representative upon receipt.

1.18 BLASTING

- .1 Blasting or other use of explosives is not permitted without prior written instructions from Departmental Representative.
- .2 Do blasting operations in accordance with local and provincial codes.

1.19 POWDER
ACTUATED DEVICES

- .1 Use powder actuated fastening devices only after receipt of written permission from Departmental Representative.

1.20 CONFINED
SPACES

- .1 Carry out work in confined spaces in compliance with:
 - .1 Provincial Occupational Safety and Health Regulations; and
 - .2 Canada Occupational Safety and Health Regulations (COSH) made under the Canada Labour Code - Part II.
- .2 Conduct hazard assessment and address in Safety Plan before entering confined space.
- .3 Provide and maintain equipment and PPE as required for the safety and emergency evacuation of persons entering confined spaces.
- .4 Provide training to persons who will be entering and to those persons who will be assisting in the confined space entry process. Training to be specialized

instructions beyond (basic confined space entry information) as required to suit type and conditions of confined space.

- 1.21 POSTING OF DOCUMENTS .1 Post on site safety documentation as stipulated by Authorities having jurisdiction and as specified herein. Place in a common visible location.
- 1.22 SITE RECORDS .1 Maintain on site a copy of all health and safety documentation and reports specified to be produced as part of the work and received from authorities having jurisdiction.
- .2 Upon request, make available to Departmental Representative, or authorized safety representative, for review. Provide copy when directed by Departmental Representative.
- 1.23 NON-COMPLIANCE AND DISCIPLINARY MEASURES .1 Immediately address and correct health and safety violations and non-compliance issues.
- .2 Negligence or failure to follow occupational health and safety provisions specified in the Contract Documents and of those of applicable laws and regulations could result in disciplinary measures taken by the Departmental Representative against the General Contractor.
- 1.24 DIVING OPERATIONS .1 All diving work to comply fully with the requirements of CSA Z275.2-011, "Occupational Safety Code for Diving

Operations", CSA Z275.4-02 (R2008),
"Competency Standards for Diving
Operations" and CAN/CSA Z180.1-00 (R2010),
"Compressed Breathing Air and Systems."

- .2 Dive personnel must meet the minimum competency requirements of the CSA Z275.4-02 (R2008) and all divers must possess a valid Category 1 Diving Certificate or an Unrestricted Surface-supplied Certificate.
- .3 Diving in free-swim mode is not permitted at the work site.
- .4 Divers must have a current (less than one year) validated medical examination certificate(s) from a licensed Diving Physician in Newfoundland and Labrador who is knowledgeable and competent in diving and hyperbaric medicine, for all dives.

-
- 1.1 RELATED WORK .1 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- 1.2 DEFINITIONS .1 Hazardous Material: Product, substance, or organism that is used for its original purpose; and that is either dangerous goods or a material that may cause adverse impact to the environment or adversely affect health of persons, animals, or plant life when released into the environment.
- 1.3 FIRES .1 Fires and burning of rubbish on site not permitted.
- 1.4 DISPOSAL OF WASTES AND HAZARDOUS MATERIALS .1 Do not bury rubbish and waste materials on site. Dispose at approved landfill sites as specified in Section 01 74 21.
- .2 Do not dispose of hazardous waste or volatile materials, such as mineral spirits, paints, thinners, oil or fuel into waterways, storm or sanitary sewers or waste landfill sites.
- .3 Store, handle and dispose of hazardous materials and hazardous waste in accordance with applicable federal and provincial laws, regulations, codes and guidelines.
- .4 Dispose of construction waste materials and demolition debris, resulting from work, at approved landfill sites only. Carryout such disposal in strict accordance with provincial and municipal rules and regulations. Separate out and prevent improper disposal of items banned from landfills.

- .5 Establish methods and undertake construction practices which will minimize waste and optimize use of construction materials. Separate at source all construction waste materials, demolition debris and product packaging and delivery containers into various waste categories in order to maximize recycling abilities of various materials and avoid disposal of debris at landfill site(s) in a "mixed state". Where recycling firms, specializing in recycling of specific materials exist, transport such materials to the recycling facility and avoid disposal at landfill sites.
- .6 Communicate with landfill operator prior to commencement of work, to determine what specific construction, demolition and renovation waste materials have been banned from disposal at the landfill and at transfer stations.

1.5 DRAINAGE

- .1 Provide temporary drainage and pumping as necessary to keep excavations and site free from water.
- .2 Do not pump water containing suspended materials into waterways, sewer or drainage systems.
- .3 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with governing regulations and requirements.
- .4 Pumped water must meet applicable federal, provincial, and municipal standards before it can be discharged to a surface water body. If regulatory guidelines exceedences are noted, the Departmental Representative has the right to issue stop pumping instructions to the Contractor. Contractor will not be

compensated for any delays associated with retrofitting equipment to meet guidelines.

- .5 Provide control devices such as filter fabrics, sediment traps and settling ponds to control drainage and prevent erosion of adjacent lands. Maintain in good order for duration of work.

1.6 PERMITS

- .1 All guidelines and instructions stated on permits must be strictly adhered to.

1.7 WORK ADJACENT TO WATERWAYS

- .1 Do not operate construction equipment in waterways.
- .2 Do not use waterway beds for borrow material.
- .3 Do not dump excavated fill, waste material or debris in waterways.
- .4 At borrow sites, design and construct temporary crossings to minimize erosion to waterways in strict conformance with provincial and federal environmental regulations.
- .5 Do not skid logs or construction materials across waterways.
- .6 Avoid indicated spawning beds when constructing temporary crossings of waterways.
- .7 Do not blast within 100 m of spawning beds.
- .8 Do not refuel any type of equipment within 100 m of a water body. Maintain equipment in good working condition with no fluid leaks, loose hoses or fittings.

1.8 POLLUTION
CONTROL

- .1 Maintain temporary erosion and pollution control features installed under this contract.
- .2 Control emissions from equipment and plant to local authorities emission requirements.
- .3 Prevent sandblasting and other extraneous materials from contaminating air beyond application area, by providing temporary enclosures.
- .4 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads and around entire construction site.
- .5 Maintain inventory of hazardous materials and hazardous waste stored on site. List items by product name, quantity and date when storage began.
- .6 Have emergency spill response equipment and rapid clean-up kit, appropriate to work, at site. Locate adjacent to work and where hazardous materials are stored. Provide personal protective equipment as required for clean-up.
- .7 Report, to Federal and Provincial Department of the Environment, spills of petroleum and other hazardous materials as well as accidents having potential of polluting the environment. Also notify Departmental Representative and submit a written spill report to Departmental Representative within 24 hours of occurrence.
- .8 Provide a floating debris containment boom whenever any of the Contractors methods of work allow for the potential of floating

debris.

1.9 WILDLIFE
PROTECTION

- .1 Should nests of migratory birds in wetlands be encountered during work, immediately notify Departmental Representative for directives to be followed.
 - .1 Do not disturb nest site and neighbouring vegetation until nesting is completed.
 - .2 Minimize work immediately adjacent to such areas until nesting is completed.
 - .3 Protect these areas by following recommendations of Canadian Wildlife Service.

1.1 SECTION
INCLUDES

- .1 Inspection and testing, administrative and enforcement requirements.
- .2 Tests and mix designs.
- .3 Mock-ups.
- .4 Mill tests.
- .5 Equipment and system adjust and balance.

1.2 RELATED
SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 78 00 - Closeout Submittals.

1.3 INSPECTION

- .1 Facilitate Departmental Representative's access to Work. If part of Work is being fabricated at locations other than construction site, make preparations to allow access to such Work whenever it is in progress.
- .2 Give timely notice requesting inspection of Work designated for special tests, inspections or approvals by Departmental Representative or by inspection authorities having jurisdiction.
- .3 If Contractor covers or permits to be covered Work designated for special tests, inspections or approvals before such is made, uncover Work until particular inspections or tests have been fully and satisfactorily completed and until such time as Departmental Representative gives permission to proceed. Pay costs to uncover and make good such Work.
- .4 In accordance with the General Conditions,

Departmental Representative may order any part of Work to be examined if Work is suspected to be not in accordance with Contract Documents.

1.4 INDEPENDENT
INSPECTION AGENCIES

- .1 Departmental Representative may engage and pay for service of Independent Inspection and Testing Agencies for purpose of inspecting and testing portions of Work except for the following which remain part of Contractor's responsibilities:
 - .1 Inspection and testing required by laws, ordinances, rules, regulations or orders of public authorities.
 - .2 Inspection and testing performed exclusively for Contractor's convenience.
 - .3 Testing, adjustment and balancing of conveying systems, mechanical and electrical equipment and systems.
 - .4 Mill tests and certificates of compliance.
 - .5 Tests as specified within various sections designated to be carried out by Contractor under the supervision of Departmental Representative.
 - .6 Additional tests specified in Clause 1.4.2.
- .2 Where tests or inspections by designated Testing Agency reveal work not in accordance with contract requirements, Contractor shall pay costs for additional tests or inspections as Departmental Representative may require to verify acceptability of corrected work.
- .3 Employment of inspection and testing agencies by Departmental Representative does not relax responsibility to perform Work in accordance with Contract Documents.

- 1.5 ACCESS TO WORK
- .1 Furnish labour and facility to provide access to the work being inspected and tested.
 - .2 Co-operate to facilitate such inspections and tests.
 - .3 Make good work disturbed by inspections and tests.
- 1.6 PROCEDURES
- .1 Notify Departmental Representative sufficiently in advance of when work is ready for tests, in order for Departmental Representative to make attendance arrangements with Testing Agency. When directed by Departmental Representative, notify such Agency directly.
 - .2 Submit representative samples of materials specified to be tested. Deliver in required quantities to Testing Agency. Submit with reasonable promptness and in an orderly sequence so as not to cause delay in Work.
 - .3 Provide labour and facilities to obtain and handle samples on site. Provide sufficient space on site for Testing Agency's exclusive use to store equipment and cure test samples.
- 1.7 REJECTED WORK
- .1 Remove and replace defective Work, whether result of poor workmanship, use of defective or damaged products and whether incorporated in Work or not, which has been identified by Departmental Representative as failing to conform to Contract Documents.
 - .2 Make good damages to existing or new work, including work of other Contracts, resulting from removal or replacement of defective work.

1.8 TESTING BY
CONTRACTOR

- .1 Provide all necessary instruments, equipment and qualified personnel to perform tests designated as Contractor's responsibilities herein or elsewhere in the Contract Documents.
- .2 At completion of tests, turn over 2 copies of fully documented test reports to Departmental Representative. Additionally, obtain other copies in sufficient quantities to enable one complete set of test reports to be placed in each of the maintenance manuals specified in Section 01 78 00.
- .3 Submit mill test certificates and other certificates as specified in various sections.
- .4 Submit adjustment and balancing reports for mechanical, electrical and building equipment systems specified in trade sections.
- .5 Furnish test results and mix designs as specified in various sections.

1.9 MOCK-UPS

- .1 Prepare mock-ups for Work specifically requested in various trade sections. Include in each mock-up all related work components representative of final assembly.
- .2 Construct in locations acceptable to Departmental Representative.
- .3 Prepare mock-ups for Departmental Representative's review with reasonable promptness and in an orderly sequence, so as not to cause any delay in Work.
- .4 Failure to prepare mock-ups in ample time is not considered sufficient reason for an extension of Contract Time and no claim for

Wharf Extension Branch, NL 721395	TESTING AND QUALITY CONTROL	Section 01 45 00 Page 5 2015-06-01
---	--------------------------------	--

extension by reason of such default will be allowed.

- .5 If requested, Departmental Representative will assist in preparing a schedule fixing dates for preparation.
- .6 Remove mock-up at conclusion of Work or when directed by Departmental Representative unless approval is given to remain as part of Work.

- 1.1 ACCESS
- .1 Provide and maintain adequate access to project site.
 - .2 Maintain access roads for duration of contract and make good damage resulting from Contractors' use of roads.
- 1.2 CONTRACTOR'S SITE OFFICE
- .1 Be responsible for and provide own site office, if required, including electricity, heat, lights and telephone. Locate site office as directed by Departmental Representative.
- 1.3 DEPARTMENTAL REPRESENTATIVE'S SITE OFFICE
- .1 Provide or construct a separate site office for the use of the Departmental Representative and the Site Representative. The building must be in place prior to commencement of work.
 - .2 Provide heating system to maintain 22°C inside temperature at -20°C outside temperature.
 - .3 The building will be approximately 2400 mm x 3600 mm. It will have a suitable frame covered with a weatherproof siding and lined with plywood or other approved material. The floor will be of 19 mm thick material. It will be provided with suitable window with at least 1 m² of glass and arranged to provide at least 0.5 m² of screened opening. The door will be fitted with a lockset and 2 keys.
 - .4 The office will be equipped with a drafting chair and a 900 mm x 1500 mm table having a hinged, smooth wooden top suitable for drafting.

- .5 Install electrical lighting system to provide minimum 750 lux using surface mounted, shielded commercial fixtures with 10% upward light component.
- .6 Maintain office in clean condition.
- .7 Arrange and pay for telephone and facsimile machine in the Departmental Representative's Office for Site Representative's exclusive use. Long distance calls or faxes placed on this phone by the Departmental Representative or the Site Representative will be paid by the Departmental Representative.
- .8 Contractor may, on approval of Departmental Representative, provide cellular or mobile phone. If approval to use cellular or mobile phone is granted, be responsible for all services, airtime, license and network access fees, and all other fees or charges required to utilize the phone as intended by the manufacturer.

1.4 SANITARY FACILITIES

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition.

1.5 POWER

- .1 Arrange, pay for and maintain temporary electrical power supply in accordance with governing regulations and ordinances.
- .2 Supply and install all temporary facilities for power such as pole lines and underground cables to approval of local power supply authority.

1.6 WATER SUPPLY .1 Arrange, pay for and maintain temporary water supply in accordance with governing regulations and ordinances.

1.7 SCAFFOLDING .1 Design, construct and maintain scaffolding in rigid, secure and safe manner in accordance with CSA797-09.
.2 Erect scaffolding independent of walls. Remove when no longer required.

1.8 CONSTRUCTION SIGN AND NOTICES .1 Contractor or subcontractor advertisement signboards are not permitted on site.
.2 Only notices of safety or instructions are permitted on site.
.3 Safety and Instruction Signs and Notices:
.1 Signs and notices for safety and instruction shall be in both official languages.
.4 Maintenance and Disposal of Site Signs:
.1 Maintain approved signs and notices in good condition for duration of project and dispose of off site on completion of project or earlier if directed by Departmental Representative.

1.9 REMOVAL OF TEMPORARY FACILITIES .1 Remove temporary facilities from site when directed by Departmental Representative.

Wharf Extension Branch, NL 721395	TEMPORARY FACILITIES	Section 01 50 00 Page 4 2015-06-01
---	----------------------	--

PART 1 - GENERAL

- | | | |
|---|----|---|
| <u>1.1 SECTION
INCLUDES</u> | .1 | Barriers. |
| | .2 | Traffic Controls. |
| <u>1.2 INSTALLATION
AND REMOVAL</u> | .1 | Provide temporary controls in order to execute work expeditiously. |
| | .2 | Remove from site all such work after use. |
| <u>1.3 HOARDING</u> | .1 | Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m centres. Provide one lockable truck gate. Maintain fence in good repair. |
| <u>1.4 GUARD RAILS
AND BARRICADES</u> | .1 | Provide secure, rigid guard rails and barricades around open excavations. |
| | .2 | Provide barricades along wharf structure when wheelguard is removed. |
| | .3 | Provide as required by governing authorities. |
| <u>1.5 ACCESS TO SITE</u> | .1 | Provide and maintain access to adjacent harbour facilities. |
| <u>1.6 PUBLIC
TRAFFIC FLOW</u> | .1 | Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to |

perform work and protect the public.

1.7 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.8 PROTECTION FOR
OFF-SITE AND PUBLIC
PROPERTY

- .1 Protect surrounding private and public property from damage during performance of work.
- .2 Be responsible for damage incurred.

1.1 DESCRIPTION

- .1 This section specifies requirements for board, lodgings and related services to be provided by the Contractor for the Site Monitor.
- .2 Due to the location of this site, it is a requirement of this contract that the Contractor provide and pay for all board and lodgings for the Site Monitor's sole use for the duration of the project. Provide for and maintain acceptable living accommodations on site for the Site Monitor's sole use. The minimum requirement would be a self-contained unit with private sleeping accommodation and shower or bath or other arrangement approved by the Departmental Representative.

1.2 BOARD AND
LODGINGS

- .1 For the purpose of this contract board and lodgings shall include but not necessarily be limited to: sleeping accommodation, meals and dining facilities, washroom facilities, laundry facilities, electrical and heating service, linens and bedding, etc. and any reasonable service as directed by the Departmental Representative.
- .2 Board and lodgings must be approved by the Departmental Representative and Contractor will cooperate in providing all services required to maintain an acceptable standard of living during construction period.
- .3 The Contractor shall include all calendar days, including weekends and statutory holidays in determining the cost.

1.3 REQUIREMENTS
OF REGULATORY
AGENCIES

- .1 Comply with any or all applicable Agencies regulation of the Province of Newfoundland and Labrador, relating to the set up, servicing and maintenance of accommodations for the Site Monitor.
- .2 Obtain and pay for any permits which may be required and comply to regulations of same.

1.1 GENERAL

- .1 Use new material and equipment unless otherwise specified.
- .2 Within 7 days of written request by Departmental Representative, submit following information for any materials and products proposed for supply:
 - .1 name and address of manufacturer;
 - .2 trade name, model and catalogue number;
 - .3 performance, descriptive and test data;
 - .4 manufacturer's installation or application instructions;
 - .5 evidence of arrangements to procure.
 - .6 evidence of manufacturer delivery problems or unforeseen delays.
- .3 Provide material and equipment of specified design and quality, performing to published ratings and for which replacement parts are readily available.
- .4 Use products of one manufacturer for equipment or material of same type or classification unless otherwise specified.
- .5 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.2 PRODUCT QUALITY
AND REFERENCED
STANDARDS

- .1 Contractor shall be solely responsible for submitting relevant technical data and independent test reports to confirm whether a product or system proposed for use meets contract requirements and specified standards.
- .2 Final decision as to whether a product or system meets contract requirements rest

solely with the Departmental Representative in accordance with the General Conditions.

1.3 ACCEPTABLE
MATERIALS AND
ALTERNATIVES

- .1 Acceptable Materials: When materials specified include trade names or trade marks or manufacturer's or supplier's name as part of the material description, select and only use one of the names listed for incorporation into the Work.
- .2 Alternative Materials: Submission of alternative materials to trade names or manufacturer's names specified must be done during the bidding period following procedures indicated in the Instructions to Bidders.
- .3 Substitutions: After acceptance of bid, substitution of a specified material will be dealt with as a change to the Work in accordance with the General Conditions of the Contract.

1.4 MANUFACTURERS
INSTRUCTIONS

- .1 Unless otherwise specified, comply with manufacturer's latest printed instructions for materials and installation methods to be used. Do not rely on labels or enclosure provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify Departmental representative in writing of any conflict between these specifications and manufacturers instructions, so that Departmental Representative will designate which document is to be followed.

1.5 AVAILABILITY

- .1 Immediately notify Departmental

Representative in writing of unforeseen or unanticipated material delivery problems by manufacturer. Provide support documentation as per Clause 1.1.2 above.

- 1.6 WORKMANSHIP
- .1 Ensure quality of work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed.
 - .2 Remove unsuitable or incompetent workers from site as stipulated in General Conditions.
 - .3 Ensure cooperation of workers in laying out work. Maintain efficient and continuous supervision on site at all times.
 - .4 Coordinate work between trades and subcontractors.
 - .5 Coordinate placement of openings, sleeves and accessories.
- 1.7 FASTENINGS - GENERAL
- .1 Provide metal fastenings and accessories in same texture, colour and finish as base metal in which they occur. Prevent electrolytic action between dissimilar metals. Use non-corrosive fasteners, anchors and spacers for securing exterior work and in humid areas.
 - .2 Space anchors within limits of load bearing or shear capacity and ensure that they provide positive permanent anchorage. Wood or organic material plugs not acceptable.
 - .3 Keep exposed fastenings to minimum, space evenly and lay out neatly.
 - .4 Fastenings which cause spalling or cracking of material to which anchorage is made, are

not acceptable.

- .5 Do not use explosive actuated fastening devices unless approved by Departmental Representative. See Section 01 35 28 on Health and Safety in this regard.

1.8 FASTENINGS -
EQUIPMENT

- .1 Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.
- .2 Use heavy hexagon heads, semi-finished unless otherwise specified.
- .3 Bolts may not project more than one diameter beyond nuts.
- .4 Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur and, use resilient washers with stainless steel.

1.9 STORAGE,
HANDLING AND
PROTECTION

- .1 Deliver, handle and store materials in manner to prevent deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled materials in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work. Provide additional cover where manufacturer's packaging is insufficient to provide adequate protection.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Store cementitious products clear of earth or concrete floors, and away from walls.

- .5 Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.
- .6 Store sheet materials and lumber on flat, solid supports and keep clear of ground. Slope to shed moisture.
- .7 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .8 Immediately remove damaged or rejected materials from site.
- .9 Touch-up damaged factory finished surfaces to Departmental Representative's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

1.10 CONSTRUCTION
EQUIPMENT AND PLANT

- .1 On request, prove to the satisfaction of Departmental Representative that the construction equipment and plant are adequate to manufacture, transport, place and finish work to quality and production rates specified. If inadequate, replace or provide additional equipment or plant as directed.
- .2 Maintain construction equipment and plant in good operating order. Prevent oil and other contaminant leaks. Should any contaminant leak onto ground or into the water, take immediate and appropriate measures to contain, cleanup and dispose in an environmentally responsible manner.

Wharf Extension Branch, NL 721395	COMMON PRODUCT REQUIREMENTS	Section 01 61 00 Page 6 2015-06-01
---	--------------------------------	--

PART 1 - GENERAL

- 1.1 GENERAL
- .1 Conduct cleaning and disposal operations to comply with local ordinances and anti-pollution laws.
 - .2 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
 - .3 Prevent accumulation of wastes which create hazardous conditions.
 - .4 Provide adequate ventilation during use of volatile or noxious substances.
- 1.2 MATERIALS
- .1 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
- 1.3 CLEANING DURING CONSTRUCTION
- .1 Maintain project grounds and public properties in a tidy condition, free from accumulations of waste material and debris. Clean areas on a daily basis.
 - .2 Provide on-site garbage containers for collection of waste materials and debris.
 - .3 Remove waste materials and debris from site on a daily basis.
- 1.4 FINAL CLEANING
- .1 In preparation for acceptance of the Work perform final cleaning.

Wharf Extension Branch, NL 721395	CLEANING	Section 01 74 11 Page 2 2015-06-01
---	----------	--

- .2 Inspect finishes, fitments and equipment.
Ensure specified workmanship and operation.
- .3 Broom clean exterior paved and concrete
surfaces; rake clean other surfaces of
grounds.

1.1 RELATED
SECTIONS

- .1 Section 01 35 43 - Environment Procedures.
- .2 Section 02 41 16 - Sitework, Demolition and Removal.
- .3 Section 03 30 00 - Cast-in-Place Concrete.
- .4 Section 06 05 73 - Wood Treatment.
- .5 Section 31 53 13 - Timber Cribwork.
- .6 Section 31 53 16 - Structural Timber.

1.2 WASTE
MANAGEMENT PLAN

- .1 Prior to commencement of work, prepare waste Management Workplan.
- .2 Workplan to include:
 - .1 Waste audit.
 - .2 Waste reduction practices.
 - .3 Material source separation process.
 - .4 Procedures for sending recyclables to recycling facilities.
 - .5 Procedures for sending non-salvageable items and waste to approved waste processing facility or landfill site.
 - .6 Training and supervising workforce on waste management at site.
- .3 Workplan to incorporate waste management requirements specified herein and in other sections of the Specifications.
- .4 Develop Workplan in collaboration with all subcontractors to ensure all waste management issues and opportunities are addressed.
- .5 Submit copy of Workplan to Departmental Representative for review and approval.
 - .1 Make revisions to Plan as directed by Departmental Representative.

- .6 Implement and manage all aspects of Waste Management Workplan for duration of work.
- .7 Revise Plan as work progresses addressing new opportunities for diversion of waste from landfill.

1.3 WASTE AUDIT

- .1 At project start-up, conduct waste audit of:
 - .1 Site conditions identifying salvageable and non-salvageable items and waste resulting from demolition and removal work.
 - .2 Projected waste resulting from product packaging and from material leftover after installation work.
- .2 Develop written list. Record type, composition and quantity of various salvageable items and waste anticipated, reasons for waste generation and operational factors which contribute to waste.

1.4 WASTE REDUCTION

- .1 Based on waste audit, develop waste reduction program.
- .2 Structure program to prioritize actions, with waste reduction as first priority, followed by salvage and recycling effort, then disposal as solid waste.
- .3 Identify materials and equipment to be:
 - .1 Protected and turned over to Departmental Representative when indicated.
 - .2 Salvaged for resale by Contractor.
 - .3 Sent to recycling facility.
 - .4 Sent to waste processing/landfill site for their recycling effort.
 - .5 Disposed of in approved landfill site.
- .4 Reduce construction waste during installation work. Undertake practices which

will minimize waste and optimize full use of new materials on site, such as:

.1 Use of a central cutting area to allow for easy access to off-cuts;

.2 Use of off-cuts for blocking and bridging elsewhere.

.3 Use of effective and strategically placed facilities on site for storage and staging of left-over or partially cut materials to allow for easy incorporation into work whenever possible avoiding unnecessary waste.

.5 Develop other strategies and innovative procedures to reduce waste such as minimizing the extent of packaging used for delivery of materials to site, etc.

1.5 MATERIAL SOURCE
SEPARATION PROCESS

.1 Develop and implement material source separation process at commencement of work as part of mobilization and waste management at site.

.2 Provide on-site facilities to collect, handle and store anticipated quantities of reusable, salvageable and recyclable materials.

.1 Use suitable containers for individual collection of items based on intended purpose.

.2 Locate to facilitate deposit but without hindering daily operations of existing building tenants.

.3 Clearly mark containers and stockpiles as to purpose and use.

.3 Perform demolition and removal of existing structure components and equipment following a systematic deconstruction process.

.1 Separate materials and equipment at source, carefully dismantling, labelling and stockpiling alike items for the following purposes:

- .1 Reinstallation into the work where indicated.
- .2 Salvaging reusable items not needed in project which Contractor may sell to other parties. Sale of such items not permitted on site.
- .3 Sending as many items as possible to locally available recycling facility.
- .4 Segregating remaining waste and debris into various individual waste categories for disposal in a "non-mixed state" as recommended by waste processing/landfill sites.

- .4 Isolate product packaging and delivery containers from general waste stream. Send to recycling facility or return to supplier/manufacturer.
- .5 Send leftover material resulting from installation work for recycling whenever possible.
- .6 Establish methods whereby hazardous and toxic waste materials, and their containers, encountered or used in the course work are properly isolated, stored on site and disposed in accordance with applicable laws and regulations from authorities having jurisdiction.
- .7 Isolate and store existing materials and equipment identified for re-incorporation into the Work. Protect against damage.

1.6 WORKER TRAINING
AND SUPERVISION

- .1 Provide adequate training to workforce, through meetings and demonstrations, to emphasize purpose and worker responsibilities in carrying out the Waste Management Plan.

- .2 Waste Management Coordinator: designate full-time person on site, experienced in waste management and having knowledge of the purpose and content of Waste Management Plan to:
 - .1 Oversee and supervise waste management during work.
 - .2 Provide instructions and directions to all workers and subcontractors on waste reduction, source separation and disposal practices.
- .3 Post a copy of Plan in a prominent location on site for review by workers.

1.7 CERTIFICATION
OF MATERIAL
DIVERSION

- .1 Submit to Departmental Representative, copies of certified weigh bills from authorized waste processing sites and sale receipts from recycling/reuse facilities confirming receipt of building materials and quantity of waste diverted from landfill.
- .2 Submit data at pre-determined project milestones as determined by Departmental Representative.
- .3 Compare actual quantities diverted from landfill with projections made during waste audit.

1.8 DISPOSAL
REQUIREMENTS

- .1 Burying or burning of rubbish and waste materials is prohibited.
- .2 Disposal of waste, volatile materials, mineral spirits, oil, paint, paint thinner or unused preservative material into waterways, storm, or sanitary sewers is prohibited.
- .3 Do not dispose of preservative treated wood

through incineration.

- .4 Do not dispose of preservative treated wood with other materials destined for recycling or reuse.
- .5 Dispose of treated wood, end pieces, wood scraps and sawdust at a sanitary landfill.
- .6 Dispose of waste only at approved waste processing facility or landfill sites approved by authority having jurisdiction.
- .7 Contact the authority having jurisdiction prior to commencement of work, to determine what, if any, demolition and construction waste materials have been banned from disposal in landfills and at transfer stations. Take appropriate action to isolate such banned materials at site of work and dispose in strict accordance with provincial and municipal regulations.
- .8 Transport waste intended for landfill in separated condition, following rules and recommendations of Landfill Operator in support of their effort to divert, recycle and reduce amount of solid waste placed in landfill.
- .9 Collect, bundle and transport salvaged materials to be recycled in separated categories and condition as directed by recycling facility. Ship materials only to approved recycling facilities.
- .10 Sale of salvaged items by Contractor to other parties not permitted on site.

1.1 SECTION
INCLUDES

- .1 Project Record Documents as follows:
 - .1 As-built drawings;
 - .2 As-built specifications;
 - .3 Reviewed shop drawings.

1.2 PROJECT RECORD
DOCUMENTS

- .1 Departmental Representative will provide two white print sets of contract drawings and two copies of Specifications Manual specifically for "as-built" purposes.
- .2 Maintain at site one set of the contract drawings and specifications to record actual as-built site conditions.
- .3 Maintain up-to-date, real time as-built drawings and specifications in good condition and make available for inspection by the Departmental Representative at any time during construction.
- .4 As-Built Drawings:
 - .1 Record changes in red ink on the prints. Mark only on one set of prints and at completion of project and prior to final inspection, neatly transfer notations to second set (also by use of red ink). Submit both sets to Departmental Representative. All drawings of both sets shall be stamped "As-Built Drawings" and be signed and dated by Contractor.
 - .2 Show all modifications, substitutions and deviations from what is shown on the contract drawings or in specifications.
 - .3 Record following information:
 - .1 Horizontal and vertical location of various elements in relation to Geodetic Datum.
 - .2 Field changes of dimension and detail.
 - .3 All design elevations, sections, and details dimensioned and marked-up to consistently report finished installation conditions.

.4 Any details produced in the course of the contract by the Departmental Representative to supplement or to change existing design drawings must also be marked-up and dimensioned to reflect final as-built conditions and appended to the as-built drawing document.

.5 All change orders issued over the course of the contract must be documented on the finished as-built documents, accurately and consistently depicting the changed condition as it applies to all affected drawing details.

.5 As-built Specifications: legibly mark in red each item to record actual construction, including:

.1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly items substituted from that specified.

.2 Changes made by Addenda and Change Orders.

.3 Mark up both copies of specifications; stamp "as-built", sign and date similarly to drawings as per above clause.

.6 Maintain As-built documents current as the contract progresses. Departmental Representative will conduct reviews and inspections of the documents on a regular basis. Frequency of reviews will be subject to Departmental Representative's discretion. Failure to maintain as-builts current and complete to satisfaction of the Departmental Representative shall be subject to financial penalties in the form of progress payment reductions and holdback assessments.

1.3 REVIEWED
SHOP DRAWINGS

.1 Compile 2 full sets of all reviewed shop drawings.

CLOSEOUT SUBMITTALS

Section 01 78 00

Wharf Extension
Branch, NL
721395

Page 3

2015-06-01

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Demolition, removal, and disposal of timber wheelguard, wheelguard blocking, fenders and associated hardware at the south face of the existing wharf to accommodate the new construction.
 - .2 Demolition, removal, and disposal of an existing untreated round timber crib structure, as required to accommodate the new wharf footprint, as noted on the drawings.
 - .3 Removal of existing rip rap, and re-instatement in the new work, as noted on the drawings.

1.2 GENERAL
REQUIREMENTS

- .1 A Notice to Shipping is to be issued prior to commencement and upon completion of work.
- .2 During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
- .3 Upon completion of the project, a written Notice to Mariners must be issued.

1.3 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.

- .2 Place a floating boom around entire demolition site to prevent loss of any materials.
- .3 Remove all floating debris from water on a routine and timely basis.

PART 2 - PRODUCTS

NOT APPLICABLE

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.2 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place.

3.3 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and disposed of to satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal

site is approved and willing to accommodate any materials disposed of from work site.

- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.
- .3 Contractor responsible for obtaining approval from Service NL, for the disposal of all demolished debris, including dredged spoils (which are to be disposed of at an approved waste site).

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.

Wharf Extension Branch, NL 721395	CONCRETE FORMING AND ACCESSORIES	Section 03 10 00 Page 1 2015-06-01
---	-------------------------------------	--

PART 1 - GENERAL

1.1 RELATED
SECTIONS

- .1 Section 03 20 00 - Concrete Reinforcing.
- .2 Section 03 30 00 - Cast-in-Place Concrete.
- .3 Section 07 92 10 - Joint Sealing.

1.2 REFERENCES

- .1 Canadian Standards Association (CSA)
 - .1 CAN/CSA-A23.1-09, Concrete Materials and Methods of Concrete Construction.
 - .2 CAN/CSA-O86-09, Engineering Design in Wood.
 - .3 CSA O121-08, Douglas Fir Plywood.
 - .4 CSA O151-09, Canadian Softwood Plywood.
 - .5 CSA O153-M1980 (R2008), Poplar Plywood.
 - .6 CAN3-O188.0-M78, Standard Test Methods for Mat-Formed Wood Particleboards and Waferboard.
 - .7 CSA O437 Series-93 (R2006), Standards for OSB and Waferboard.
 - .8 CSA S269.1-1975 (R2003), Falsework for Construction Purposes.
 - .9 CAN/CSA-S269.3-M92 (R2008), Concrete Formwork.

1.3 SHOP DRAWINGS

- .1 Submit shop drawings for formwork and falsework in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Indicate method and schedule of construction, shoring, stripping and re-shoring procedures, materials, arrangement of joints, special architectural exposed finishes, ties, liners, and locations of temporary embedded parts. Comply with CSA

S269.1, for falsework drawings Comply with CAN/CSA-S269.3 for formwork drawings.

- .3 Indicate formwork design data, such as permissible rate of concrete placement, and temperature of concrete, in forms.
- .4 Indicate sequence of erection and removal of formwork/falsework as directed by Departmental Representative.
- .5 Each shop drawing submission shall bear stamp and signature of qualified Professional Engineer registered or licensed in Province of Newfoundland and Labrador, Canada.

1.4 WASTE
MANAGEMENT AND
DISPOSAL

- .1 Separate and recycle waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal and the Waste Reduction Workplan.
- .2 Place materials defined as hazardous or toxic waste in designated containers.
- .3 Ensure emptied containers are sealed and stored safely for disposal away from children.
- .4 Use sealers, form release and stripping agents that are non-toxic, biodegradable and have zero or low VOC's.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Formwork materials:
 - .1 Use formwork materials to CAN/CSA-A23.1.

- .2 Form ties:
 - .1 Removable or snap-off metal ties, fixed or adjustable length, free of devices leaving holes larger than 25 mm diameter in concrete surface.
- .3 Form release agent: non-toxic, chemically active release agents containing compounds that react with free lime present in concrete to provide water insoluble soaps, preventing set of film of concrete in contact with form.
- .4 Falsework materials: to CSA-S269.1.
 - .1 Materials required to bear grade marks, or be accompanied with certificates, test reports or other proof of conformity.
- .5 Premoulded joint fillers:
 - .1 Bituminous impregnated fibreboard to ASTM D1751.
- .6 Bond Breaker:
 - .1 Impermeable tube formed of polyvinylchloride, rubber or similar material to the approval of the Departmental Representative. Internal diameter equal to dowels.
- .7 Sealant: to Section 07 92 10 - Joint Sealing.

PART 3 - EXECUTION

3.1 FABRICATION AND ERECTION

- .1 Verify lines, levels and centres before proceeding with formwork/falsework and ensure dimensions agree with drawings.
- .2 Obtain Departmental Representative's approval for use of earth forms framing openings not indicated on drawings.

- .3 Hand trim sides and bottoms and remove loose earth from earth forms before placing concrete.
- .4 Fabricate and erect falsework in accordance with CSA S269.1.
- .5 Fabricate and erect formwork in accordance with CAN/CSA-S269.3 to produce finished concrete conforming to shape, dimensions, locations and levels indicated within tolerances required by CAN/CSA-A23.1.
- .6 Align form joints and make watertight. Keep form joints to minimum.
- .7 Use 25 mm chamfer strips on external corners and/or 25 mm fillets at interior corners, joints, unless specified otherwise.
- .8 Form chases, slots, openings, drips, recesses, expansion and control joints as indicated.
- .9 Build in anchors, sleeves, and other inserts required to accommodate Work specified in other sections. Assure that all anchors and inserts will not protrude beyond surfaces designated to receive applied finishes, including painting.
- .10 Clean formwork in accordance with CAN/CSA-A23.1, before placing concrete.

3.2 REMOVAL AND
RESHORING

- .1 Leave formwork in place for following minimum periods of time after placing concrete.
 - .1 5 days for slabs, decks and other structural members, or 3 days when replaced immediately with adequate shoring to standard specified for falsework.

- .2 Remove formwork when concrete has reached 75% of its design strength or minimum period noted above, whichever comes later, and replace immediately with adequate reshoring.
- .3 Provide all necessary reshoring of members where early removal of forms may be required or where members may be subjected to additional loads during construction as required.
- .4 Space reshoring in each principal direction at not more than 3000 mm apart.
- .5 Re-use formwork and falsework subject to requirements of CAN/CSA-A23.1.

3.3 JOINT FILLERS

- .1 Locate and form expansion joints as indicated. Install joint filler in all joints.
- .2 Use 13 mm thick joint filler to separate new concrete from existing structure, and extend joint filler from bottom of slab to within 25 mm of finished slab surface unless indicated otherwise.

3.4 JOINT SEALANT

- .1 Fill expansion and control joints with sealer as per manufacturer instructions.

PART 1 - GENERAL

1.1 RELATED
SECTIONS

- .1 Section 03 10 00 - Concrete Forming and Accessories.
- .2 Section 03 30 00 - Cast-in-Place Concrete.
- .3 Section 35 59 29 - Mooring Devices.

1.2 REFERENCES

- . 1 American Concrete Institute (ACI)
 - .1 ACI 315R-04, Manual of Engineering and Placing Drawings for Reinforced Concrete Structure.
- .2 American National Standards Institute/American Concrete Institute (ANSI/ACI)
 - .1 ANSI/ACI 315-99, Details and Detailing of Concrete Reinforcement.
- .3 American Society for Testing and Materials International (ASTM)
 - .1 ASTM A185/A185M-07, Standard Specification for Steel Welded Wire Reinforcement, Plain, for Concrete.
 - .2 ASTM A497/A497M-07, Standard Specification for Steel Welded Wire Reinforcement, Deformed, for Concrete.
 - .3 ASTM-A123/A123M-09, Standard Specification for Zinc (Hot Dip Galvanized) Coatings on Iron and Steel Products.
- .4 Canadian Standards Association (CSA)
 - .1 CAN/CSA-A23.1-09, Concrete Materials and Methods of Concrete Construction.
 - .2 CSA-A23.3-04(R2010), Design of Concrete Structures.
 - .3 CAN/CSA-G30.18-09, Carbon Steel Bars

for Concrete Reinforcement.

.4 CSA-G40.20-04/G40.21-04(R2009),
General Requirements for Rolled or Welded
Structural Quality Steel/Structural Quality
Steel.

.5 CSA W186-M1990 (R2007), Welding of
Reinforcing Bars in Reinforced Concrete
Construction.

1.3 SHOP DRAWINGS

.1 Submit shop drawings including placing of
reinforcement in accordance with Section
01 33 00 - Submittal Procedures.

.2 Indicate on shop drawings, bar bending
details, lists, quantities of reinforcement,
sizes, spacings, locations of reinforcement
and mechanical splices if approved by
Departmental Representative, with
identifying code marks to permit correct
placement without reference to structural
drawings. Indicate sizes, spacings and
locations of chairs, spacers and hangers.
Prepare reinforcement drawings in accordance
with Reinforcing Steel Manual of Standard
Practice - by Reinforcing Steel Institute of
Canada. ANSI/ACI 315 and ACI 315R, Manual of
Engineering and Placing Drawings for
Reinforced Concrete Structure.

1.4 WASTE MANAGEMENT AND DISPOSAL

.1 Separate and recycle waste materials in
accordance with Section 01 74 21 -
Construction/Demolition Waste Management and
Disposal and the Waste Reduction Workplan.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Substitute different size bars only if permitted in writing by Departmental Representative.
- .2 Reinforcing steel: billet steel, grade 400, deformed bars to CAN/CSA-G30.18, unless indicated otherwise.
- .3 Reinforcing steel: weldable low alloy steel deformed bars to CAN/CSA-30.18.
- .4 Cold-drawn annealed steel wire ties: to ASTM A-82/A-82M.
- .5 Welded steel wire fabric: to CSA G30.5. Provide in flat sheets only.
- .6 Chairs, bolsters, bar supports, spacers: to CAN/CSA-A23.1.
- .7 Mechanical splices: subject to approval of Departmental Representative.

2.2 FABRICATION

- .1 Fabricate reinforcing steel in accordance with CAN/CSA-A23.1, ANSI/ACI 315, and Reinforcing Steel Manual of Standard Practice by the Reinforcing Steel Institute of Canada. ACI 315R, Manual of Engineering and Placing Drawings for Reinforced Concrete Structures unless indicated otherwise.
- .2 Obtain Departmental Representative's approval for locations of reinforcement splices other than those shown on placing drawings.
- .3 Upon approval of Departmental Representative, weld reinforcement in

accordance with CSA W186.

- .4 Ship bundles of bar reinforcement, clearly identified in accordance with bar bending details and lists.

2.3 SOURCE QUALITY CONTROL

- .1 Provide Departmental Representative with certified copy of mill test report of reinforcing steel, showing physical and chemical analysis, minimum 2 weeks prior to commencing reinforcing work.
- .2 Upon request inform Departmental Representative of proposed source of material to be supplied.

PART 3 - EXECUTION

3.1 FIELD BENDING

- .1 Do not field bend or field weld reinforcement except where indicated or authorized by Departmental Representative.
- .2 When field bending is authorized, bend without heat, applying a slow and steady pressure.
- .3 Replace bars which develop cracks or splits.

3.2 PLACING REINFORCEMENT

- .1 Place reinforcing steel as indicated on reviewed placing drawings and in accordance with CAN/CSA-A23.1.
- .2 Use approved type chairs to locate the reinforcing steel at the proper grade.

- .3 Tie reinforcement where spacing in each direction is:
 - .1 Less than 300 mm: tie at alternate intersections.
 - .2 300 mm or more: tie at each intersection.
- .4 Prior to placing concrete, obtain Departmental Representative's approval of reinforcing material and placement.
- .5 Ensure cover to reinforcement is maintained during concrete pour.

3.3 CLEANING

- .1 Clean reinforcing before placing concrete to CAN/CSA-A23.1.

PART 1 - GENERAL

- 1.1 DESCRIPTION .1 This section specifies requirements for supply, placing, finishing, protecting and curing cast-in-place concrete for mooring cleat blocks, and wharf deck.
- 1.2 RELATED SECTIONS .1 Section 03 10 00 - Concrete Forming and Accessories.
.2 Section 03 20 00 - Concrete Reinforcing.
.3 Section 35 59 29 - Mooring Devices.
- 1.3 REFERENCES .1 American Society for Testing and Materials (ASTM)
.1 ASTM C109/C109M-08, Standard Test Method for Compressive Strength of Hydraulic Cement Mortars (Using 2 in. or 50 mm Cube Specimens).
.2 ASTM C260/260M-10a, Standard Specification for Air-Entraining Admixtures for Concrete.
.3 ASTM C494/C494M-10a, Standard Specification for Chemical Admixtures for Concrete.
.2 Canadian General Standards Board (CGSB)
.1 CAN/CGSB-51.34-M86, Vapour Barrier, Polyethylene Sheet for Use in Building Construction.
.3 Canadian Standards Association (CSA)
.1 CAN/CSA-A23.1-09, Concrete Materials and Methods of Concrete Construction.
.2 CAN/CSA-A23.2-09, Methods of Test for

Concrete.

.3 CSA-A283-06, Qualification Code for Concrete Testing Laboratories.

.4 CAN/CSA-A3000-08, Cementitious Materials Compendium (consists of A3001, A3002, A3003, A3004 and A3005).

.1 CSA-A3001-08, Cementitious Materials for Use in Concrete.

1.4 CERTIFICATES

- .1 Submit certificates in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Minimum 2 weeks prior to starting concrete work submit to Departmental Representative manufacturer's test data and certification by qualified independent inspection and testing laboratory that following materials will meet specified requirements:
 - .1 Portland cement.
 - .2 Blended hydraulic cement.
 - .3 Supplementary cementing materials.
 - .4 Grout.
 - .5 Admixtures.
 - .6 Aggregates.
 - .7 Water.
 - .8 Joint filler.
 - .9 Joint Sealant.
- .3 Provide certification that mix proportions selected will produce concrete of quality, yield and strength as specified in concrete mixes, and will comply with CAN/CSA-A23.1.
- .4 Provide certification that plant, equipment, and materials to be used in concrete comply with requirements of CAN/CSA-A23.1.

1.5 STORAGE OF MATERIALS

- .1 Store materials to prevent contamination or deterioration.

- .2 Provide adequate storage facilities for materials to ensure a continuous supply of these materials during batching operations.
- .3 Store cement in weathertight facility.

1.6 QUALITY ASSURANCE

- .1 Minimum 2 weeks prior to starting concrete work, submit proposed quality control procedures to Departmental Representative for the following items:
 - .1 Cold weather concrete.
 - .2 Curing.
 - .3 Finishes.
 - .4 Formwork removal.
 - .5 Joints.

1.7 WASTE MANAGEMENT AND DISPOSAL

- .1 Use trigger operated spray nozzles for water hoses.
- .2 Designate a cleaning area for tools to limit water use and runoff.
- .3 Carefully coordinate the specified concrete work with weather conditions.
- .4 Ensure emptied containers are sealed and stored safely for disposal away from children.
- .5 Prevent plasticizers, water-reducing agents and air-entraining agents from entering drinking water supplies or streams. Using appropriate safety precautions, collect liquid or solidify liquid with an inert, noncombustible material and remove for disposal. Dispose of all waste in accordance with applicable local, provincial and national

regulations.

- .6 Choose least harmful, appropriate cleaning method which will perform adequately.

1.8 MEASUREMENT
FOR PAYMENT

- .1 250mm Structural Deck: Supply and installation of reinforced concrete deck for the new wharf to be measured in square metres (m²) calculated from actual field measurements, excluding area occupied by mooring cleat pedestals and coping. Contractor to provide all plant, equipment, material, and labour including concrete, reinforcing steel, and control joints.
- .2 Cleat Pedestals: No measurement for payment to be made under this section. Include costs incidental to unit price for Type "B1" mooring cleats.
- .3 No separate payment will be made for any other ingredient or feature of concrete work, and all factors, including cold weather placement, steel angle, reinforcing steel, anchor bolts, joint filler for control joints, cement, plant and labour will be considered as being included in the unit price for item.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Cement to CAN/CSA-A3001, Type GU.
- .2 Supplementary cementing materials: to CAN/CSA-A3001.
- .3 Cementitious hydraulic slag: to CAN/CSA-A3001.

- .4 Water: to CAN/CSA-A23.1.
- .5 Aggregates: to CAN/CSA-A23.1. Coarse aggregates to be normal density.
- .6 Air entraining admixture: to ASTM C260.
- .7 Chemical admixtures: to ASTM C494/C494M. Departmental Representative to approve accelerating or set retarding admixtures during cold and hot weather placing.
- .8 Concrete retarders: to ASTM C494/C494M. Do not allow moisture of any kind to come in contact with the retarder film.
- .9 Curing compound: curing compounds are not to be used.
- .10 Premoulded joint fillers:
 - .1 Sponge rubber: to ASTM D1752, Type I, flexible grade.

2.2 MIXES

- .1 Proportion concrete in accordance with CAN/CSA-A23.1, Clause 4.3.
- .2 Proportion concrete to comply with Alternate 1, Table 2 in CAN/CSA-A23.1 and following requirements:
 - .1 Cement:
 - .1 Type GU Portland cement.
 - .2 Minimum compressive strength: 35 MPa at 28 days.
 - .3 Class of exposure: C1.
 - .4 Minimum cement content: 385 kg/m³ of concrete.
 - .5 20 mm nominal size coarse aggregate.
 - .6 Air content 5% to 8%.
 - .7 Density of air-dry concrete in range of 2240 kg/m³ to 2400 kg/m³.

- .8 Slump at time and point of discharge
50 mm to 100 mm.
- .3 When the Contractor wishes to purchase
concrete from a ready mix concrete
supplier, submit a letter from the
supplier certifying the following:
 - .1 That plant and equipment is certified
and all materials to be used in the
concrete comply with the requirements of
CAN/CSA-A23.1.
 - .2 That the mix proportions selected
will produce concrete of the specified
quality and yield. Indicate mix
proportions and sources of all materials.
 - .3 That the strengths will comply with
the strengths specified herein.
- .4 When the Contractor wishes to mix concrete
on site, identify the source of aggregates
and submit samples of fine and coarse
aggregates to a testing laboratory for
testing and trial mixes in order to
determine a suitable mix design. The
testing laboratory, at Contractor's cost,
will test the trial mix for slump, air
content, density and strength. The results
of these tests will be submitted to the
Departmental Representative to be reviewed
for compliance with the specification.
This review must be completed before
permission to place concrete is given.
 - .1 The sand, gravel, water and air
entraining agent should be mixed prior to
the addition of cement and water reducer.
- .5 Weigh aggregates, cement, water and
admixture when batching. No alternative
methods of measuring will be permitted.
- .6 Do not use calcium chloride.

PART 3 - EXECUTION

3.1 PREPARATION

- .1 Obtain Departmental Representative's approval before placing concrete. Provide 24 hours notice prior to placing of concrete.
- .2 Pumping of concrete is permitted only after approval of equipment and mix.
- .3 Ensure reinforcement and inserts are not disturbed during concrete placement.
- .4 Prior to placing of concrete obtain Departmental Representative's approval of proposed method for protection of concrete during placing and curing in adverse weather.
- .5 Maintain accurate records of poured concrete items to indicate date, location of pour, quality, air temperature and test samples taken.
- .6 Do not place load upon new concrete until authorized by Departmental Representative.

3.2 CONSTRUCTION

- .1 Comply with additional requirements of CAN/CSA-A23.1, Clause 4.1.1.5, for concrete exposed to seawater environments.
- .2 Minimum concrete cover over reinforcing steel bars to be 75 mm.
- .3 Place concrete in hot weather to CAN/CSA-A23.1.
- .4 Place concrete in cold weather to CAN/CSA-A23.1.
- .5 Keep concrete surfaces moist continually during protection stage.

- .6 Place, consolidate, finish, cure and protect concrete to CAN/CSA-A23.1.
- .7 Do not commence placing concrete until Departmental Representative has inspected and approved forms, foundations, reinforcing steel, joints, conveying, spreading, consolidation and finishing equipment and curing and protective methods.

3.3 FORMWORK

- .1 Install and strip formwork to CAN/CSA-A23.1 and Section 03 10 00.

3.4 INSERTS

- .1 Position and secure anchor bolts in formwork to maintain line and grades.

3.5 CONTROL JOINTS

- .1 Construct control joints in locations shown on drawings or directed by Departmental Representative.
- .2 All joints will be centred over a support. Joints will be made in a perfectly straight line.
- .3 Cut control joint when concrete has hardened.
- .4 Fill saw cut with joint sealer as specified.

3.6 PLACING CONCRETE

- .1 Place and consolidate concrete to CAN/CSA-A23.1.
- .2 Do not place concrete on or against frozen

material.

- .3 Place concrete continuously from joint to joint.
- .4 Place concrete in a uniform heading, normal to the centreline. Limit rate of placing to that which can be finished before beginning of initial set.

3.7 STRIKE OFF
AND CONSOLIDATION

- .1 High speed internal poker vibrators shall be used to consolidate the concrete during placing. Final compaction of the surfaces shall be done by beam-type vibratory air screed as approved by Departmental Representative. A surcharge of approximately 65 mm of concrete will be maintained at the screed face during consolidation.
- .2 Strikeoff and consolidation must be completed before excess water bleeds to the surface.
- .3 Ensure that the concrete deck conforms to the elevations and slopes as shown on the drawings so that satisfactory drainage will result.

3.8 FINISHING

- .1 Only ACI certified or other pre-approved concrete finishers are to be utilized in finishing all concrete works. All work is to be finished to CAN/CSA-A23.1, and as specified below.
- .2 The surface will be brought to the specified level by means of darbying or bull floating which will be carried out immediately following screeding and must be completed before any bleed water is

- present on the surface. Surface tolerance to be 8 mm under a 3 metre straight edge.
- .3 Provide slope as shown on the drawings to permit proper drainage of the concrete deck.
 - .4 Finish slabs to elevations indicated on drawings.
 - .5 Strike off the surface with a straight edge.
 - .6 Hand tamp low slump concrete with jitterbug.
 - .7 Darby or bull float the surface to smooth and level the concrete.
 - .8 Allow bleed water or sheen to disappear.
 - .9 Float the surface by means of power and/or hand float where the concrete has hardened enough for a man to leave only slight footprints on the surface.
 - .10 Do not bring water and fines to the surface by over floating. Where extra floating is required the floating operation shall be repeated after the time interval necessary for any sheen to disappear and for concrete to set further.
 - .11 Steel trowel the concrete surfaces by means of power and/or hand trowel. Do not leave any hard, smooth, polished or burnished surface area.
 - .12 Do not bring water and fines to the surface by over trowelling.
 - .13 After slight interval necessary for concrete to further harden, repeat the trowelling operation.

- .14 Lightly broom surface with a soft bristle broom obtaining a fine and even textured finish with a non-slip finish. All brush strokes to be parallel across paving.
- .15 The surface shall be true and accurate to a maximum tolerance of 1 mm in 500 mm.

3.9 PROTECTION
AND CURING

- .1 Cure to CAN/CSA-A23.1.
- .2 Cure concrete by protecting it against loss of moisture, rapid temperature change and mechanical injury for at least 7 days after placement. After finishing operations have been completed, the entire surface of the newly placed concrete shall be covered by whatever curing medium is applicable to local conditions and approved by the Departmental Representative. The edges of concrete slabs exposed by removal of forms shall be protected with continuous curing treatment equal to the method selected for curing the slab and curb surfaces. Cure to CAN/CSA-A23.1. Have the equipment needed for adequate curing at hand and ready to install before actual concrete placement begins.
- .3 When air temperature is at or below 5°C or when there is a probability of its falling to that limit within 24 hours of placing (as forecast by the nearest official meteorological office) cold weather protection as per CAN/CSA-A23.1 will be provided and the following:
 - .1 Housing - Protect concrete by a windproof shelter of canvas or other material to allow free circulation of inside air around fresh touch formwork and provide sufficient space for removal of

formwork for finishing. Supply approved heating equipment capable of keeping inside air at a constant temperature sufficiently high to maintain concrete at following curing temperatures.

.1 For initial 3 days at a temperature of not less than 15°C nor more than 27°C at surface.

.2 Maintain concrete at 10°C for an extra 4 days plus the initial 3 days.

.3 In addition to the protective housing, the concrete must be cured as outlined in Clause 3.9.2 above.

3.10 TESTING

- .1 Departmental Representative will appoint a concrete testing company to test all work under this section of specification as per CAN/CSA-A23.1.
- .2 Cost of compressive strength tests shall be paid for by the Departmental Representative.
- .3 Testing company shall issue reports to Departmental Representative on quality of test cylinders.
- .4 Notify Departmental Representative at least 7 days prior to start of placing concrete. Provide for testing purposes an adequate quantity of approved test cylinders.
- .5 At least 1 set of 3 cylinders each shall be taken from 25 m³ or fraction thereof of each day's pour, whichever is less. 1 cylinder shall be tested at 7 days and other 2 tested at 28 days.
- .6 Crate cylinders and deliver to the testing laboratory within 48 hours after casting in accordance with CAN/CSA-A23.1.

Contractor will pay for crating and delivery of cylinders to the laboratory.

- .7 If strength tests of test cylinder for any portion of the work falls below the specified compressive strength at 28 days, the Departmental Representative reserves the right to determine the acceptability of the concrete by performing additional field testing as outlined in CAN/CSA-A23.1.
- .8 If concrete does not conform to drawings or specifications, take measures as directed to correct the deficiency. All costs of correctional measures will be at the expense of the Contractor.

PART 1 - GENERAL

1.1 RELATED
SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .3 Section 03 30 00 - Cast-in-Place Concrete.

1.2 REFERENCES

- .1 American Society for Testing and Materials International, (ASTM)
 - .1 ASTM A 53/A53M-10, Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Seamless.
 - .2 ASTM A 269-10, Standard Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service.
 - .3 ASTM A307-10, Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
 - .4 ASTM A123/A123M-09, Standard Specification for Zinc (Hot Dip Galvanized) Coatings on Iron and Steel Products.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.40-97, Anti-corrosive Structural Steel Alkyd Primer.
 - .2 CAN/CGSB-1.181-99, Ready-Mixed, Organic Zinc-Rich Coating.
- .3 Canadian Standards Association (CSA International)
 - .1 CSA-G40.20/G40.21-04 (R2009), General Requirements for Rolled or Welded

Structural Quality Steel/Structural Quality Steel.

.2 CAN/CSA-S16.1-09, Design of Steel Structures.

.3 CSA W48-06, Filler Metals and Allied Materials for Metal Arc Welding (Developed in co-operation with the Canadian Welding Bureau).

.4 CSA W59-03 (R2008), Welded Steel Construction (Metal Arc Welding).

.4 The Environmental Choice Program

.1 CCD-047a-98, Paints, Surface Coatings.

.2 CCD-048-98, Surface Coatings - Recycled Water-borne.

1.3 SUBMITTALS

.1 Product Data:

.1 Submit manufacturer's printed product literature, specifications and data sheet in accordance with Section 01 33 00 - Submittal Procedures.

.2 Submit two copies of WHMIS MSDS - Material Safety Data Sheets in accordance with Section 01 33 00 - Submittal Procedures. Indicate VOC's:

.1 For finishes, coatings, primers and paints.

.2 Shop Drawings

.1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.

.2 Indicate materials, core thicknesses, finishes, connections, joints, method of anchorage, number of anchors, supports, reinforcement, details, and accessories.

1.4 QUALITY ASSURANCE

.1 Test Reports: Certified test reports showing compliance with specified

performance characteristics and physical properties.

- .2 Certificates: Product certificates signed by manufacturer certifying materials comply with specified performance characteristics and criteria and physical requirements.

1.5 DELIVERY,
STORAGE, AND
HANDLING

- .1 Packing, Shipping, Handling and Unloading:
- .2 Deliver, store, handle and protect materials in accordance with Section 01 61 00 - Common Product Requirements.
- .3 Storage and Protection:
 - .1 Cover exposed stainless steel surfaces with pressure sensitive heavy protection paper or apply strippable plastic coating, before shipping to job site.
 - .2 Leave protective covering in place until final cleaning of building. Provide instructions for removal of protective covering.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Steel sections and plates: to CAN/CSA-G40.20/G40.21, Grade 300W.
- .2 Welding materials: to CSA W59.
- .3 Welding electrodes: to CSA W48 Series.
- .4 Bolts and anchor bolts: to ASTM A 307.

2.2 FABRICATION

- .1 Fabricate work square, true, straight and accurate to required size, with joints closely fitted and properly secured.
- .2 Use self-tapping shake-proof flat headed screws on items requiring assembly by screws or as indicated.
- .3 Where possible, fit and shop assemble work, ready for erection.
- .4 Ensure exposed welds are continuous for length of each joint. File or grind exposed welds smooth and flush.

2.3 FINISHES

- .1 Galvanizing: hot dipped galvanizing with zinc coating to ASTM-A123/A123M.
- .2 Shop coat primer: to CAN/CGSB-1.40.
- .3 Zinc primer: zinc rich, ready mix to CAN/CGSB-1.181.

2.4 SHOP PAINTING

- .1 Apply one shop coat of primer to metal items, with exception of galvanized or concrete encased items.
- .2 Use primer unadulterated, as prepared by manufacturer. Paint on dry surfaces, free from rust, scale, grease. Do not paint when temperature is lower than 7 degrees C.
- .3 Clean surfaces to be field welded; do not paint.

PART 3 - EXECUTION

3.1 ERECTION

- .1 Do welding work in accordance with CSA W59 unless specified otherwise.
- .2 Erect metalwork square, plumb, straight, and true, accurately fitted, with tight joints and intersections.
- .3 Provide suitable means of anchorage acceptable to Departmental Representative such as dowels, anchor clips, bar anchors, expansion bolts and shields, and toggles.
- .4 Exposed fastening devices to match finish and be compatible with material through which they pass.
- .5 Make field connections with bolts to CAN/CSA-S16.1, or weld.
- .6 Touch-up rivets, field welds, bolts and burnt or scratched surfaces after completion of erection with primer.
- .7 Touch-up galvanized surfaces with zinc rich primer where burned by field welding.

3.2 CLEANING

- .1 Perform cleaning after installation to remove construction and accumulated environmental dirt.
- .2 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

3.3 STEEL ANGLE

- .1 Install steel angle on back of concrete deck as shown on the drawings. No separate payment will be made for the steel angle.

PART 1 - GENERAL

1.1 REFERENCES

- .1 American Wood-Preservers' Association (AWPA)
 - .1 AWPA M2-01, Standard Inspection of Treated Wood Products.
 - .2 AWPA M4-06, Standard for the Care of Preservative-Treated Wood Products.
- .2 Canadian Standards Association (CSA)
 - .1 CSA O80 Series-97 (R2007), Wood Preservation.
 - .2 CSA O80.201-97, Standard for Hydrocarbon Solvents for Preservatives. This Standard covers hydrocarbon solvents for preparing solutions of preservatives. This is not stand alone specification
 - .3 CSA O322-02, Procedure for Certification of Pressure-Treated Wood Materials for Use in Preserved Wood Foundations.

1.2 QUALITY
ASSURANCE

- .1 Testing of products treated with preservative by pressure impregnation will be carried out by the manufacturer's testing laboratory to AWPA M2, and revisions specified in CSA O80 Series, Supplementary Requirements to AWPA M2.
- .2 Inspection and testing of timber materials will be carried out by the manufacturer.

1.3 CERTIFICATES
AND ASSAY
RETENTION RESULTS

- .1 Submit certificates and assay retention results in accordance with Section 01 33 00 - Submittal Procedures.
- .2 For products treated with preservative by

pressure impregnation submit following information certified by authorized signing officer of treatment plant:

- .1 Information listed in AWPA M2 and revisions specified in CSA O80 Series, Supplementary Requirement to AWPA M2 applicable to specified treatment.
- .2 Moisture content after drying following treatment with water-borne preservative.
- .3 Assay retentions results representing each treated batch of supplied timber.
- .4 Acceptable types of paint, stain, and clear finishes that may be used over treated materials to be finished after treatment.

1.4 WASTE
MANAGEMENT AND
DISPOSAL

- .1 Do not dispose of preservative treated wood through incineration.
- .2 Do not dispose of preservative treated wood with other materials destined for recycling or reuse.
- .3 Dispose of treated wood, end pieces, wood scraps and sawdust at sanitary landfill approved by Departmental Representative.
- .4 Dispose of unused wood preservative material at official hazardous material collections site approved by Departmental Representative.
- .5 Do not dispose of unused preservative material into sewer system, into streams, lakes, onto ground or in other location where they will pose health or environmental hazard.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Preservative: to CSA-080 Series.
- .2 Solvent: to CSA-080.201.

2.2 PRESERVATIVE TREATMENTS

- .1 Treat to CSA 080, commodity standard 080.18, Table 1 and its referenced standards, with the following minimum assay retentions:

<u>Species</u>	<u>CCA kg/m3</u>	<u>ACA kg/m3</u>
Dimension Timber		
-Coast Douglas Fir	24	24
-Western/Eastern Hemlock	24	24
-Hemlock, Douglas Fir (Wheelguard, Wheelguard Blocking)	10	10
-Birch or Maple	Treat to Refusal	

Note: Birch or maple must be air dried for six (6) months in weather protected environment or kiln dried.

PART 3 - EXECUTION

3.1 FIELD TREATMENT

- .1 Handle pressure treated material in a manner that will avoid damage which may expose untreated material. Rejection of any damaged material may result and replacement will be at the Contractor's expense.

- .2 Fill all bored bolt holes with preservative immediately after boring. Use a pressurized container with hose to apply preservative, or some alternate method acceptable to the Departmental Representative.
- .3 Fill all unused bored holes and spike holes with tight fitting treated wooden plugs.

3.2 CUTTING

- .1 Field cuts, if authorized, are to receive three (3) liberal coats of the applicable preservative applied to dry wood on each application.

3.3 FIELD QUALITY

- .1 Timber which contain rot, splits exposing untreated wood, excessive wane, or timbers which cannot be fastened in the work so as to be structurally sound are unacceptable.
- .2 The Departmental Representative reserves the right to carry out field testing of treated timber for penetration and retention of preservative. Timber not meeting the requirements of the specification may be rejected for use under the contract.

PART 1 - GENERAL

1.1 SECTION
INCLUDES

- .1 Materials, preparation and application for caulking and sealants.

1.2 RELATED
SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 45 00 - Testing and Quality Control.
- .3 Section 01 61 00 - Common Product Requirements.
- .4 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .5 Section 03 10 00 - Concrete Forming and Accessories.
- .6 Section 03 30 00 - Cast-in-Place Concrete.

1.3 REFERENCES

- .1 Canadian General Standards Board (CGSB)
- .2 CAN/CGSB-19.24-M90, Multi-component, Chemical Curing Sealing Compound.
- .3 Department of Justice Canada (Jus)
 - .1 Canadian Environmental Protection Act, 1999 (CEPA).
- .4 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .5 Transport Canada (TC)

.1 Transportation of Dangerous Goods Act, 1992 (TDGA).

1.4 SUBMITTALS

- .1 Submit product data in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Manufacturer's product to describe.
 - .1 Caulking compound.
 - .2 Primers.
 - .3 Sealing compound, each type, including compatibility when different sealants are in contact with each other.
- .3 Submit manufacturer's instructions in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Instructions to include installation instructions for each product used.

1.5 DELIVERY,
STORAGE, AND
HANDLING

- .1 Deliver, handle, store and protect materials in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver and store materials in original wrappings and containers with manufacturer's seals and labels, intact. Protect from freezing, moisture, water and contact with ground or floor.

1.6 WASTE
MANAGEMENT AND
DISPOSAL

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.

- .3 Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard, packaging material, in appropriate on-site bins, for recycling in accordance with Waste Management Plan.
- .4 Place materials defined as hazardous or toxic in designated containers.
- .5 Handle and dispose of hazardous materials in accordance with the CEPA, TDGA, Regional and Municipal regulations.
- .6 Unused sealant material must not be disposed of into sewer system, into streams, lakes, onto ground or in other location where it will pose health or environmental hazard.
- .7 Divert unused joint sealing material from landfill to official hazardous material collections site approved by Departmental Representative.
- .8 Empty plastic joint sealer containers are not recyclable. Do not dispose of empty containers with plastic materials destined for recycling.
- .9 Fold up metal banding, flatten, and place in designated area for recycling.

1.7 PROJECT
CONDITIONS

- .1 Environmental Limitations:
 - .1 Do not proceed with installation of joint sealants under following conditions:
 - .1 When ambient and substrate temperature conditions are outside limits permitted by joint sealant manufacturer or are below 4.4 degrees C.
 - .2 When joint substrates are wet.
 - .2 Joint-Width Conditions:

.1 Do not proceed with installation of joint sealants where joint widths are less than those allowed by joint sealant manufacturer for applications indicated.

.3 Joint-Substrate Conditions:

.1 Do not proceed with installation of joint sealants until contaminants capable of interfering with adhesion are removed from joint substrates.

1.8 ENVIRONMENTAL
REQUIREMENTS

.1 Comply with requirements of Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials; and regarding labeling and provision of Material Safety Data Sheets (MSDS) acceptable to Labour Canada.

.2 Conform to manufacturer's recommended temperatures, relative humidity, and substrate moisture content for application and curing of sealants including special conditions governing use.

PART 2 - PRODUCTS

2.1 SEALANT
MATERIALS

.1 Where sealants are qualified with primers use only these primers.

2.2 SEALANT
MATERIAL
DESIGNATIONS

.1 Polysulfide Two Part.

.2 Self-Leveling to CAN/CGSB-19.24, Type 1, Class B, colour to match concrete.

.3 Polysulfide Two Part.

- .1 Non-Sag to CAN/CGSB-19.24, Type 2, Class B, colour to match concrete.
- .4 Preformed Compressible and Non-Compressible back-up materials.
 - .1 Polyethylene, Urethane, Neoprene or Vinyl Foam.
 - .1 Extruded closed cell foam backer rod.
 - .2 Size: oversize 30 to 50%.
 - .2 Neoprene or Butyl Rubber.
 - .1 Round solid rod, Shore A hardness 70.
 - .3 High Density Foam.
 - .1 Extruded closed cell polyvinyl chloride (PVC), extruded polyethylene, closed cell, Shore A hardness 20, tensile strength 140 to 200 kPa, extruded polyolefin foam, 32 kg/m³ density, or neoprene foam backer, size as recommended by manufacturer.
 - .4 Bond Breaker Tape.
 - .1 Polyethylene bond breaker tape which will not bond to sealant.

2.3 JOINT CLEANER

- .1 Non-corrosive and non-staining type, compatible with joint forming materials and sealant recommended by sealant manufacturer.
- .2 Primer: as recommended by manufacturer.

PART 3 - EXECUTION

3.1 PROTECTION

- .1 Protect installed Work of other trades from staining or contamination.

3.2 SURFACE
PREPARATION

- .1 Examine joint sizes and conditions to establish correct depth to width relationship for installation of backup materials and sealants.
- .2 Clean bonding joint surfaces of harmful matter substances including dust, rust, oil grease, and other matter which may impair Work.
- .3 Do not apply sealants to joint surfaces treated with sealer, curing compound, water repellent, or other coatings unless tests have been performed to ensure compatibility of materials. Remove coatings as required.
- .4 Ensure joint surfaces are dry and frost free.
- .5 Prepare surfaces in accordance with manufacturer's directions.

3.3 PRIMING

- .1 Where necessary to prevent staining, mask adjacent surfaces prior to priming and caulking.
- .2 Prime sides of joints in accordance with sealant manufacturer's instructions immediately prior to caulking.

3.4 BACKUP MATERIAL

- .1 Apply bond breaker tape where required to manufacturer's instructions.
- .2 Install joint filler to achieve correct joint depth and shape, with approximately 30% compression.

3.5 MIXING

- .1 Mix materials in strict accordance with sealant manufacturer's instructions.

3.6 APPLICATION

- .1 Sealant.
 - .1 Apply sealant in accordance with manufacturer's written instructions.
 - .2 Mask edges of joint where irregular surface or sensitive joint border exists to provide neat joint.
 - .3 Apply sealant in continuous beads.
 - .4 Apply sealant using gun with proper size nozzle.
 - .5 Use sufficient pressure to fill voids and joints solid.
 - .6 Form surface of sealant with full bead, smooth, free from ridges, wrinkles, sags, air pockets, embedded impurities.
 - .7 Tool exposed surfaces before skinning begins to give slightly concave shape.
 - .8 Remove excess compound promptly as work progresses and upon completion.
- .2 Curing.
 - .1 Cure sealants in accordance with sealant manufacturer's instructions.
 - .2 Do not cover up sealants until proper curing has taken place.
- .3 Cleanup.
 - .1 Clean adjacent surfaces immediately and leave Work neat and clean.
 - .2 Remove excess and droppings, using recommended cleaners as work progresses.
 - .3 Remove masking tape after initial set of sealant.

PART 1 - GENERAL

1.1 LOCATION OF
CONDUIT

.1 Drawings show all conduits in their approximate locations only.

1.2 APPROVALS,
CODES AND PERMITS

.1 All work shall be done in accordance with latest edition of the Canadian Electrical Code C22.1-2015.

.2 Contractor shall present the drawings to the Electrical Inspection Authority for approval and obtain a permit before starting work.

.3 Notify the Departmental Representative of any changes required before proceeding.

PART 2 - PRODUCTS

2.1 CONDUIT

.1 Rigid PVC conduit: to CSA C22.2 No. 211.2. To be used below grade unless noted otherwise.

2.2 CONDUIT
FASTENINGS

.1 One hole PVC straps to secure surface conduits 50 mm and smaller. Two hole PVC straps for conduits larger than 50 mm.

.2 Beam clamps to secure conduits to exposed steel work.

.3 Channel type supports for two or more conduits at 1 m oc.

.4 Threaded rods, 6 mm dia., to support suspended channels.

2.3 CONDUIT FITTINGS

.1 Fittings for raceways: to CSA C22.2 No. 18-M1987.

.2 Factory 90° bends are required for 25 mm and larger conduits.

.3 Fittings manufactured for use with conduit specified, approved for encasement in slab.

2.4 FISH CORD

.1 Polypropylene.

PART 3 - EXECUTION

3.1 INSTALLATION

.1 Install conduit as shown on drawings.

.2 Place conduit between mats of steel and secure in position with tye wire.

.3 Ensure system is intact and clear after concrete is poured. Remove and replace any blocked conduit.

.4 Install pull rope in empty conduit before pouring concrete.

.5 Swab conduits when system is complete.

Wharf Extension Branch, NL 721395	POLE	Section 26 52 60 Page 1 2015-06-01
---	------	--

PART 1 - GENERAL

1.1 REFERENCES

- .1 Canadian Standards Association (CSA):
 - 1. CAN/CSA-015-90, Wood Utility Poles and Reinforcing Stubs.
 - 2. American National Standards Institute (ANSI).

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Wood preservation: to CAN/CSA080 Series.

2.2 POLES

- .1 Wood utility poles: to CAN/CSA-015, wood species, Class 2, 12.2 meter poles, CCA or ACA pressure treated to 080-M1983. Installation as detailed on drawings.
 - 1. 12.2 m long poles for lighting fixtures.
 - 2. Minimum circumference at top - 635 mm.
 - 3. Minimum circumference at 1.8 m from butt - 978 mm.

PART 3 - EXECUTION

3.1 INSTALLATION

- .1 Install wooden poles as indicated on drawings.

PART 1 - GENERAL

- 1.1 DESCRIPTION .1 This section specifies supply, placement and compaction of rock and gravel fill as required to bring the grade to the underside of the granular base courses as noted on the drawings or as directed by Departmental Representative. Rock/gravel fill will not be measured separately for payment, as these costs are to be included in the lump sum arrangement.

PART 2 - PRODUCTS

- 2.1 ROCK FILL .1 Rock fill will be of hard, durable, evenly graded blasted stone having a maximum diameter of 300 mm in major portion of fill and a maximum diameter of 150 mm in upper 600 mm of rock fill. Fill material will contain not more than 6 percent by weight passing the 25 mm sieve. Rock fill to be evenly graded within the limits specified.
- .2 Use of shale rock or slate will not be permitted.

- 2.2 GRAVEL FILL .1 Gravel fill will consist of hard, durable, particles of stone mixed with suitable binding material. It shall be free from flat, elongated particles and shall be well graded. When tested by means of laboratory sieves it shall fulfill requirements as follows:

<u>Sieve Size</u>	<u>% by Weight Passing</u>
56 mm	100
16 mm	45-80
4.75 mm	25-55
1.25 mm	10-35
0.300 mm	5-15
0.075 mm	3-8

PART 3 - EXECUTION

3.1 PLACING ROCK FILL

- .1 Only rock fill material approved by Departmental Representative will be placed. Material will be placed uniformly across full cross-section in layers not exceeding 300 mm loose depth.
- .2 Use suitable earth moving and surface grading equipment to place and spread rock fill in continuous and uniform horizontal layers.
- .3 Compact rock fill after each 300 mm lift.
- .4 Place rock fill to 350 mm below bottom of finished grade.

3.2 PLACING GRAVEL FILL

- .1 Top 300 mm of fill will consist of gravel fill as specified in Clause 2.2.1 of this section.
- .2 Place gravel fill in two (2) equal lifts to minimum 95% standard proctor density.

PART 1 - GENERAL

- 1.1 SECTION INCLUDES
- .1 Materials and installation of polymeric geotextiles, purpose of which is to:
 - .1 Separate and prevent mixing of granular materials of different grading.
 - .2 Act as hydraulic filters permitting passage of water while retaining soil strength of granular structure.
- 1.2 RELATED WORK
- .1 Section 01 33 00 - Submittal Procedures.
 - .2 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .3 Section 31 53 13 - Timber Cribwork.
- 1.3 REFERENCES
- .1 American Society for Testing and Materials (ASTM)
 - .1 ASTM D4491-99a(2004)e1, Standard Test Methods for Water Permeability of Geotextiles by Permittivity.
 - .2 ASTM D4595-05, Standard Test Method for Tensile Properties of Geotextiles by the Wide-Width Strip Method.
 - .3 ASTM D4716-04, Standard Test Method for Determining the (In-Plane) Flow Rate Per Unit Width and Hydraulic Transmissivity of a Geosynthetic Using a Constant Head.
 - .4 ASTM D4751-04, Standard Test Method for Determining Apparent Opening Size of a Geotextile.
 - .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-4.2-M88, Textile Test Methods.
 - .2 CAN/CGSB-148.1, Methods of Testing

Geotextiles and Geomembranes.

- .1 No.2-M85, Mass per Unit Area.
- .2 No.3-M85, Thickness of Geotextiles.
- .3 No.7.3-92, Grab Tensile Test for Geotextiles.
- .4 No.6.1-93, Bursting Strength of Geotextiles Under No Compressive Load.

- .3 Canadian Standards Association (CSA)
 - .1 CAN/CSA-G40.20-04/G40.21-04, General Requirements for Rolled or Welded Structural Quality Steel.
 - .2 CAN/CSA-G164-M92(R2003), Hot Dip Galvanizing of Irregularly Shaped Articles.

- 1.4 SAMPLES
 - .1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Submit to Departmental Representative the following samples at least 2 weeks prior to commencing work.
 - .1 Minimum length of 1 m of roll width of geotextile.

- 1.5 MILL CERTIFICATES
 - .1 Submit to Departmental Representative a copy of mill test data and certificate at least 2 weeks prior to start of work.

- 1.6 DELIVERY AND STORAGE
 - .1 During delivery and storage, protect geotextiles from direct sunlight, ultraviolet rays, excessive heat, mud, dirt, dust, debris and rodents.

- 1.7 WASTE MANAGEMENT AND DISPOSAL
 - .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste

Management And Disposal.

- .2 Remove from site and dispose of all packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard, and packaging material, in appropriate on-site bins, for recycling in accordance with Waste Management Plan.
- .4 Fold up metal banding, flatten and place in designated area for recycling.

PART 2 - PRODUCTS

2.1 MATERIAL

- .1 Geotextile: woven or non-woven synthetic fibre fabric, supplied in rolls.
 - .1 Width: 3.5 m minimum.
 - .2 Length: 50 m minimum.
 - .3 Composed of: minimum 85% by mass of polyester with inhibitors added to base plastic to resist deterioration by ultra-violet and heat exposure.
- .2 Physical properties:
 - .1 Thickness: to CAN/CGSB-148.1, No.3, minimum 2.5 mm.
 - .2 Mass per unit area: to CAN/CGSB-148.1, No. 2, minimum 400 g/m².
 - .3 Tensile strength and elongation (in any principal direction): to ASTM D4595.
 - .1 Tensile strength: minimum 1200 N, wet condition.
 - .2 Elongation at break: 50 to 100 percent.
 - .3 Seam strength: equal to or greater than tensile strength of fabric.

Wharf Extension Branch, NL 721395	GEOTEXTILES	Section 31 32 21 Page 4 2015-06-01
---	-------------	--

- .4 Mullen burst strength: to CAN/CGSB-4.2, method 11.1, minimum 3100 kPa.
- .3 Hydraulic properties:
 - .1 Apparent opening size (AOS): to ASTM D4751, 50 to 150 micrometres.
 - .2 Permittivity: to ASTM D4491, 0.25 cm per second.
- .4 Securing pins and washers: to CAN/CSA-G40.21, Grade 300W, hot-dipped galvanized with minimum zinc coating of 600 g/m² to CAN/CSA G164.

PART 3 - EXECUTION

3.1 INSTALLATION

- .1 Place one (1) layer of geotextile material from base elevation of crib to top of crib and retain in position with securing pins and washers.
- .2 Place geotextile material by unrolling onto graded surface in orientation, manner and locations indicated and retain in position with securing pins and washers.
- .3 Place geotextile material on sloping surfaces in one continuous length from toe of slope to upper extent of geotextile.
- .4 Place geotextile material smooth and free of tension stress, folds, wrinkles and creases.
- .5 Overlap each successive strip of geotextile 600 mm over previously laid strip.
- .6 Join successive strips of geotextile by sewing.

- .7 Pin successive strips of geotextile with securing pins at mid point of lap to satisfaction of Departmental Representative.
- .8 Protect installed geotextile material from displacement, damage or deterioration before, during and after placement of material layers.
- .9 After installation, cover with overlying layer within 4 hours of placement.
- .10 Replace damaged or deteriorated geotextile to approval of Departmental Representative.
- .11 For full cribs, extend geotextile over top of cribwork, in portion of cribwork not containing a concrete deck.

3.2 CLEANING

- .1 Remove construction debris from Project site and dispose of debris in an environmentally responsible and legal manner.

3.3 PROTECTION

- .1 Vehicular traffic not permitted directly on geotextile.

PART 1 - GENERAL

- 1.1 RELATED WORK .1 Section 31 53 13 - Timber Cribwork.
- 1.2 MEASUREMENT FOR PAYMENT .1 Rock Mattress: as specified including base layer, bearing layer, the cost of all plant, labour, equipment and materials required to complete the work, will be measured in cubic metres place measure (CMPM) of material placed in work within the limits indicated. The volume of material will be determined in place from measurements taken prior to and at completion of the work.
- .2 Excavation/dredging of material will be required prior to rock mattress placement and these costs are to be included as incidental (reference the drawings in this regard showing pay limits).
- .3 Provide a sounding survey to the Departmental Representative, taken in the presence of the inspector, before and following placement of rock mattress. No separate payment will be made for the sounding survey.
- 1.3 REFERENCES .1 American Society for Testing and Materials (ASTM)
- .1 ASTM C88-05, Standard Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate.
- .2 ASTM C127-07, Standard Test Method for Specific Gravity and Absorption of Coarse Aggregate.

.3 ASTM C535-03e1, Standard Test Method for Resistance to Degradation of Large-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Mattress material to following requirements:
- .1 Crushed quarry stone consisting of hard durable particles free from silt, clay lumps, organic matter, frozen material and other deleterious materials, and free from splits, seams or defects likely to impair its soundness during handling or under action of water.
 - .2 Relative density (formally specific gravity): to ASTM C127 (AASHTO T85), not less than 2.65.
 - .3 Base layer will be uniformly graded quarry run rock ranging in weight from 45 to 400 kg. A minimum of 50% of the total base layer will contain stones with individual weights of 200 kg. No more than 5% by weight to be rocks weighing less than 10 kg.
 - .4 Bearing layer will be uniformly graded quarry run rock ranging in weight from 2 to 7 kg with average rock dimensions off 100 and 150 mm respectively. A minimum of 50% of the total bearing layer will contain stones with individual weight of 5 kg.

PART 3 - EXECUTION

3.1 PREPARATION

- .1 Rock mattress is to be placed only after

existing harbour bottom materials have been excavated/dredged and hard bottom has been achieved. Achieving hard bottom will be the responsibility of the Contractor.

- .2 Sound area in presence of the inspector before placing mattress material, and record elevation of bottom on which mattress to be placed.

3.2 PLACEMENT

- .1 Ensure that no frozen material is used in placing.
- .2 Do not place mattress material until bottom area has been approved by Departmental Representative.
- .3 Place mattress materials to elevations and dimensions as indicated.
- .4 Prevent segregation in placing of material sizes. Do not drop material through water.
- .5 Do not place material during weather judged unsuitable by Departmental Representative.
- .6 Place material immediately prior to planned placement of timber cribs.
- .7 Level top surface of mattress to specified grade. Use sweep beam suspended from barge as screed to level surface of each mattress layer. Other methods of leveling may be employed subject to approval of Departmental Representative.
- .8 In areas where the depth of the rock mattress to be placed is less than the 600 mm required for the full thickness of the bearing layer, only place the required thickness of bearing layer to reach the

required crib seat elevation.

3.3 ROCK MATERIAL
WASHED OUT OF WORK

- .1 Should during the progress of the work, any rock material be washed out of the work, or through neglect of carelessness of the Contractor or workmen or from any other cause, be dumped into the water near the work or anywhere within the harbour or channel, so as to interfere, in the opinion of the Departmental Representative, with actual depths of water and/or impede navigation, it will be removed by the Contractor when ordered to do so by the Departmental Representative. Any material washed out of the work or displaced beyond the contract limits will be replaced by the Contractor at no cost to Canada.

3.4 TOLERANCES

- .1 Surface of bearing layer to be parallel with elevation as indicated with mean elevation of surface within 50 mm of elevations as indicated.
- .2 Surface of base layer to be parallel with elevation as indicated with mean elevation of surface within 100 mm of elevations as indicated.
- .3 Establish mean elevation from spot elevations taken at 2 m intervals. Do not allow spot elevation to differ more than 50 mm from mean.

3.5 TESTING

- .1 Submit rock materials samples for testing to testing laboratory approved by the Departmental Representative prior to commencement of quarry production. Allow sufficient lead time to perform and report

tests before start of production.

- .2 Contractor will be responsible for procurement of samples for testing and arrange and pay for shipment of samples to testing laboratory.
- .3 Departmental Representative will pay for costs associated with laboratory testing. The cost of retesting due to samples failing to meet the requirements of the contract will be borne by the Contractor.
- .4 Only materials satisfactorily tested and approved by the Departmental Representative will be quarried and placed in the work.

Wharf Extension Branch, NL 721395	RIP-RAP	Section 31 37 10 Page 1 2015-06-01
---	---------	--

PART 1 - GENERAL

- 1.1 DESCRIPTION .1 This section specifies requirements for supply and placing stone rip-rap for erosion protection at locations and to dimensions indicated or designated by Departmental Representative. Rip rap will not be measured separately for payment, and is to be included in the lump sum arrangement. The intent is to re-shape the existing bank on the south side of Crib #4 and install 2 rows of 1 tonne rip rap, as shown on the drawings (existing rip rap may be salvaged for re-use at the discretion of the Departmental Representative).

PART 2 - PRODUCTS

- 2.1 RIP-RAP .1 Hard, dense with relative density (formally specific gravity) not less than 2.65, durable quarry stone, free from seams, cracks or other structural defects, to meet following size distribution for use intended.
- .2 Rip-rap stone to be well graded, sizes as indicated on drawings.
- .3 Supply rock spalls to fill open joints.
- .4 Field stones of appropriate sizes are acceptable for hand placed rip-rap.

PART 3 - EXECUTION

- 3.1 PLACING .1 Place rip-rap as directed to thickness and details indicated or as designated by Departmental Representative.

- .2 Where rip-rap is to be placed on slopes, excavate trench at toe of slope to dimensions as indicated.
- .3 All side slopes to match the existing bank profile, adjacent to the area of work.
- .4 Fine grade area to be rip-rapped to uniform, even surface. Fill depressions with suitable material and compact to provide firm bed.
- .5 Place stones in manner approved by Departmental Representative to secure surface and create a stable mass. Place larger stones at bottom of slopes.
- .6 Hand placing:
 - .1 Use larger stones for lower courses and as headers for subsequent courses.
 - .2 Stagger vertical joints and fill voids with rock spalls or cobbles.
 - .3 Finish surface evenly, free of large openings and neat in appearance.

PART 1 - GENERAL

- 1.1 DESCRIPTION .1 This section specifies requirements for supply and installation of treated timber and necessary fastenings for fabrication, placing, and ballasting of timber cribwork.
- 1.2 RELATED SECTIONS .1 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Section 06 05 73 - Wood Treatment.
- 1.3 MEASUREMENT FOR PAYMENT .1 Treated Timber Cribwork: to be measured in cubic metres (m³) of completed work which include ballast stone, gravel, treated timber, end of wharf blocking, fire separators, fire sealant, fastenings, and all plant, labour, materials and equipment to perform work.
- .2 Measure timber cribwork in cubic metres determined by product. Use following dimensions measured in place:
- .1 Height: average of measurements taken at each vertical from bottom of lowest timber to top side of uppermost course of timber.
- .2 Width: average of measurements between outside faces of exterior longitudinal timbers, each width measured on top ties of each row of cross ties.
- .3 Length: measured horizontally along centre-line of crib between outside faces of exterior cross ties.

- .3 Measurements of the vertical lengths, widths and lengths of cribwork, will be taken in the presence of both the Contractor and the Departmental Representative and will be verified and signed by both parties on the site to avoid any disputes. There will be no overpayment for cribwork, as the intent is to pay the Contractor only for the actual volume of cribwork placed in the work (the Departmental Representative will make the final decision on actual volumes of cribwork placed in the work).

1.4 SAFETY
REQUIREMENTS

- .1 Worker protection:
 - .1 Workers must wear gloves, respirators, dust masks, long sleeved clothing, eye protection, protective clothing when handling, drilling, sawing, cutting or sanding preservative treated wood and applying preservative materials.
 - .2 Workers must not eat, drink or smoke while applying preservative material.
 - .3 Clean up spills of preservative materials immediately with absorbent material. Safely discard of absorbent material to sanitary landfill.

1.5 REFERENCES

- .1 American Society for Testing and Materials (ASTM International)
 - .1 ASTM A307-07b, Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile.
 - .2 ASTM C136-06, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
- .2 American Wood-Preserver's Association (AWPA)
 - .1 AWPA M4-06, Standard for the Care of

Preservation - Treated Wood Products.

- .3 Canadian Standards Association (CSA International)
 - .1 CSA B111-1974(R2003), Wire Nails, Spikes and Staples.
 - .2 CAN/CSA-G40.21-04, General Requirements for Rolled or Welded Structural Quality Steel/Structural Steel.
 - .3 CAN/CSA G164-M92(R2003), Hot Dip Galvanizing of Irregularly Shaped Articles.
 - .4 CAN/CSA-O80 Series-97 (R2007), Wood Preservation.
- .4 Canadian Wood Council
 - .1 Wood Design Manual.
- .5 National Lumber Grades Authority (NLGA)
 - .1 Standard Grading Rules for Canadian Lumber 2000 edition.

1.6 SUBMITTALS

- .1 Ballast:
 - .1 Submit proposed placing method to Departmental Representative for approval, prior to placing of ballast.

1.7 WASTE MANAGEMENT

- .1 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .2 Dispose of all corrugated cardboard and polystyrene plastic packaging material in appropriate on-site bin for recycling.
- .3 Place materials defined as hazardous or toxic in designated containers.
- .4 Ensure emptied containers are sealed and stored safely.

- .5 Do not dispose of preservative treated wood through incineration.
- .6 Do not dispose of preservative treated wood with other materials destined for recycling or reuse.
- .7 Dispose of treated wood, end pieces, wood scraps and sawdust at a sanitary landfill.
- .8 Dispose of unused preservative material at an official hazardous material collections site. Do not dispose of unused preservative material into sewer system, streams, lakes, on ground or in any other location where they will pose a health or environmental hazard.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Timber: Use timber graded and stamped in accordance with applicable grading rules and standards of associations or agencies approved to grade lumber by Canadian Lumber Standards Accreditation Board of CSA.
- .2 Species: Douglas Fir, Pacific Coast Hemlock and Eastern Hemlock.
- .3 Grade: No. 1 Structural.
- .4 Grading authority: NLGA.
- .5 Preservative treatment: To CSA O80 for coastal waters and Section 06 05 73. Supply timbers in lengths required. Cut and field treat timbers only as may be necessary to suit site conditions. Contractor will have on site sufficient

lengths and thickness of treated timber to permit leveling of cribs after ballasting operations.

- .6 Miscellaneous steel: Medium structural steel conforming to CSA Specification G40.21 "Structural Quality Steels".
 - .1 Hot dip galvanized: to CAN/CSA-G164. Minimum weight of zinc coating as stated in Table 1 of this Standard. Fabricator to adhere to recommendations in Appendix A and B of Standard.
 - .2 Wire nails, spikes, staples: to CSA-B111.
 - .3 Bolts, nuts, washers: to ASTM A307.
 - .4 Drift Bolts: to G40.21 from round stock, button head and diamond or wedge point.
 - .5 Washers:
 - .1 Round Plate Washers: for 19 mm diameter machine bolts, 79 mm diameter by 7.9 mm thick, with hole diameter of 21 mm. Washers to G40.21.
 - .2 Square washers not permitted to be used.
 - .6 All hardware galvanized.
- .7 Ballast for filling cribs to following requirements:
 - .1 Stone, consisting of hard durable particles free from clay lumps, organic material and other deleterious materials.
 - .2 Dry density in place: minimum 2600 kg per cubic metre.
 - .3 Ballast stone to be well graded with maximum sizes not exceeding 400 mm on any side and minimum size of not less than 250 mm on any side.
- .8 Gravel: Evenly graded pit run or crushed stone, maximum size, 50 mm, with not more than 8% passing the 0.075 mm sieve.

PART 3 - EXECUTION

3.1 PREPARATION

- .1 Place rock mattress on hard bottom, as indicated on drawings. Achieving hard bottom will be the responsibility of the Contractor.
- .2 Before construction, stockpile sufficient ballast to completely fill cribs. Provide suitable plant and equipment to keep crib in proper position and alignment during sinking operations.
- .3 Cribs out of alignment or not correctly located to be refloated and replaced in correct position.

3.2 NEW CRIB
CONSTRUCTION

- .1 Construct new timber cribwork to 400 mm above LNT prior to sinking in final position in work.
- .2 Levelling Pieces:
 - .1 Place treated timber levelling pieces beneath bottom timbers to conform to shape of base area.
 - .2 Place levelling pieces horizontally.
 - .3 Secure succeeding pieces at intersections of bottom timbers and vertical posts, and other levelling pieces with machine bolts.
- .3 Bottom timbers:
 - .1 Place bottom timbers lengthwise, and crosswise to form bottom three courses of cribs.
 - .2 Crosswise bottom timbers to be of one piece.
 - .3 Lengthwise bottom timbers to be of one piece.
 - .4 Secure three courses of bottom

timbers together with machine bolts at every intersection with each other and with vertical posts.

- .4 Ballast floor:
 - .1 Place ballast floor on pockets on bottom or middle course of bottom timbers.
 - .2 Secure each ballast floor timber to bottom timbers with drift bolts securing adjacent ballast floor timbers to same bottom timber.

- .5 Longitudinals:
 - .1 Longitudinals one length for individual cribs below LNT.
 - .2 Longitudinals minimum 6100 mm long above LNT.
 - .3 Where cribs are married together, longitudinals of sufficient length to span a minimum of a half a bay of one crib and one and a half bays of the adjacent crib.
 - .4 Butt join exterior and interior longitudinals a minimum distance of 600 mm from crosstie with joint in centre of a 1200 mm long joiner block.
 - .5 Secure block to lower timber with drift bolt at centre and secure longitudinals and splice at ends to block with drift bolts.
 - .6 Stagger joints in longitudinal timbers. Do not join in same bay or on same vertical post.
 - .7 Secure longitudinals to intersection of cross ties with drift bolt and to intersection of vertical posts with machine bolt every third course of longitudinals, along with the top course.
 - .8 Countersink machine bolts on exterior face above LNT.

- .6 Cross ties: one length across cribs.
 - .1 Secure cross ties to intersection of longitudinals with drift bolt and to intersection of vertical posts with

- machine bolt every third course of cross tie, along with the top course.
- .2 One row of crossties and verticals may be eliminated from one crib where cribs marry together above +400 mm LNT.
- .7 Vertical posts: one length from bottom of cribwork to top of cribwork. Locate one vertical post at corner of each crib and at intersection of crossties with longitudinals.
- .8 Blocking: install treated timber filler blocking as indicated on drawings.
- .1 Cut blocking exact length to completely fill spaces and such that the total thickness of crossties and longitudinals carrying the bearing weight of the deck be a minimum of 600 mm if cribwork ends on a crosstie.
- .2 If cribwork ends on a longitudinal one additional tier of blocking is required.
- .3 Blocking of same size and material as crossties or longitudinals and fastened with 2 drift bolts into timber immediately below it.
- .9 Levelling: treated timber required for levelling of cribwork after ballasting, must be full width continuous over entire length to be levelled.
- .10 Bolt Sizing and Holing:
- .1 Drift Bolts: length of drift bolts equal to thickness of timbers fastened less 50 mm, unless otherwise specified. Bore holes for drift bolts 2 mm smaller diameter than bolt and for full length of bolt.
- .2 Machine Bolts: length of machine bolts equal to thickness of timbers fastened plus thickness of washers plus 40 m. Where bolts are countersunk, the

length, as noted above, less depth of countersink. Thread machine bolts for 64 mm. Bore holes for machine bolts to same diameter as bolts.

3.3 HANDLING
TREATED TIMBER

- .1 Handle treated material without damaging original treatment.
 - .1 Replace treated timber with major damage to original treatment, as instructed by Departmental Representative.
- .2 Field treatment: to CAN/CSA-080. Apply and saturate cuts, minor surface damage, abrasions, and nail and spike holes with preservative.
- .3 Ripping of treated timber not permitted without prior approval of Departmental Representative.

3.4 BALLAST

- .1 Place ballast to avoid damage to timber cribwork.
- .2 Place ballast so that differential height of fill between adjacent cells, at any time, will be less than 1 m.
- .3 Pockets of cribs ballasted within 100 mm of top of crib timbers.

3.5 GRAVEL

- .1 Install a 100 mm layer of gravel over the top of ballast to form a base for the reinforced concrete deck.
- .2 Hand place final items of ballast stone to fill voids and depressions to hold gravel in place.

- .3 Install gravel to grade required and compact in preparation for concrete deck work.
- .4 Clean any loose gravel off timber surface prior to placement of deck.

3.6 TOLERANCES

- .1 1 in 300 in overall dimensions.
- .2 Locate cribs within 100 mm of location as indicated. Horizontal misalignment within 100 mm along the outside faces.
- .3 Space between ballasted cribs within 200 mm. No payment for this space will be made above or below LNT.

3.7 PROTECTION

- .1 Protect work from damage resulting from work on other sections and from damage resulting from environmental conditions.
- .2 Repair or replace portion or entire crib at no additional cost if damaged by work.

Wharf Extension Branch, NL 721395	STRUCTURAL TIMBER	Section 31 53 16 Page 1 2015-06-01
---	-------------------	--

PART 1 - GENERAL

- 1.1 DESCRIPTION .1 This section specifies requirements for supply and installation of structural timber as follows:
- .1 Supply and installation of treated dimension timber wheelguard, wheelguard blocking, coping, fire separators, and associated painting.
 - .2 Supply and installation of untreated dimension hardwood timber fenders, and associated painting.
 - .3 Supply and installation of untreated timber hardwood ladders, ladder handgrips, and associated hardware.
- 1.2 RELATED WORK .1 Section 02 41 16 - Sitework, Demolition and Removal.
- .2 Section 03 30 00 - Cast-in-Place Concrete.
 - .3 Section 06 05 73 - Wood Treatment.
 - .4 Section 31 53 13 - Timber Cribwork.
- 1.3 REFERENCES .1 American Society for Testing and Materials (ASTM International)
- .1 ASTM A307-07b, Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile.
 - .2 American Wood-Preserver's Association (AWPA)
 - .1 AWPA M4-06, Standard for the Care of Preservation - Treated Wood Products.
 - .3 Canadian Standards Association (CSA

International)

.1 CSA B111-1974(R2003), Wire Nails, Spikes and Staples.

.2 CAN/CSA-G40.21-04, General Requirements for Rolled or Welded Structural Quality Steel/Structural Steel.

.3 CAN/CSA G164-M92(R2003), Hot Dip Galvanizing of Irregularly Shaped Articles.

.4 CAN/CSA-O80 Series-97 (R2007), Wood Preservation.

.4 Canadian Wood Council

.1 Wood Design Manual.

.5 National Lumber Grades Authority (NLGA)

.1 Standard Grading Rules for Canadian Lumber 2000 edition.

1.4 DIMENSIONS

.1 Check existing site dimensions and report discrepancies to Departmental Representative before commencing work.

1.5 PROTECTION

.1 Avoid dropping, bruising or breaking of wood fibres.

.2 Avoid breaking surfaces of treated timber.

.3 Do not damage surfaces of treated timber by boring holes or driving nails or spikes into them to support temporary material or staging.

.4 Treat cuts, breaks or abrasions on surfaces of treated timber with 3 brush coats of preservative to CSA 080.

.5 Treat bolt holes, cutoffs and field cuts in accordance with CSA 080.

1.6 DELIVERY
AND STORAGE

- .1 Store timber horizontally, evenly supported and open piled permit circulation when stored for prolonged period.
- .2 When handling long timber, provide support at sufficient number of points, properly located to prevent damage due to excessive bending.
- .3 Handle treated timber with hemp, manila or sisal rope slings or other approved means of support that will not damage surface.
- .4 Do not use sharp pointed tools to handle treated timber. Any timber so handled will be rejected and be replaced at Contractor's expense.

1.7 MEASUREMENT
FOR PAYMENT

- .1 Structural Timber:
 - .1 Treated Dimension Timber: The supply and installation of treated dimension timber for wheelguard, wheelguard blocking and coping will be measured by the cubic metre (m³) of timber secured in place, including all timber, fastenings, plant, material, equipment, labour, wheelguard bolt hole levelling sealant, painting of wheelguard and wheelguard blocking.
 - .2 Untreated Dimension Timber: The supply and installation of untreated dimension hardwood timber for hardwood fenders, and ladders as specified will be measured by the cubic metre (m³) of timber secured in place including all timber, fastenings, plant, material, equipment, and labour, ladder rungs, wheelguard hand grips, and painting of complete ladder uprights.

Wharf Extension Branch, NL 721395	STRUCTURAL TIMBER	Section 31 53 16 Page 4 2015-06-01
---	-------------------	--

.3 The supply and installation of solid timber blocking fire separators as noted on the drawings will not be measured separately for payment. Include fire separator costs in lump sum arrangement.

.2 Payment for all dimension timber will be made on volume calculated from nominal sizes as indicated on drawing and specified, eg. 200 mm x 200 mm.

PART 2 - PRODUCTS

2.1 TIMBER MATERIALS

.1 Timber: Use timber graded and stamped in accordance with applicable grading rules and standards of associations or agencies approved to grade lumber by Canadian Lumber Standards Administration Board of CSA.

.2 Species

.1 Wheelguard, wheelguard blocks and coping: Hemlock or Douglas Fir (CCA or ACA treated).

.2 Hardwood fenders and ladder uprights: Birch or Maple (untreated).

.3 Grade: No. 1 Structural Grade

.4 Grading Authority: NLGA

.5 Preservative Treatment: Treat to CSA 080, for coastal waters and Section 06 05 73. Timbers will be treated in the lengths required. Unnecessary field cutting will not be permitted.

.6 Primer: Alkyd undercoat, exterior oil wood primer, similar to Pittsburgh 6-9.

.7 Paint: Alkyd/Oil Resin paint similar to Pittsburgh Paints "Safety Yellow" Product ID

7-808. Paint to conform to
CAN/CGSB-1.61-2004.

2.2 MISCELLANEOUS
STEEL AND
FASTENINGS

- .1 Miscellaneous Steel: All steel and fastenings to be CSA G40.21, Grade 300 W, galvanized.
- .2 Nails and Spikes: to CSA B111.
- .3 Machine Bolts and Nuts: to ASTM A307. All machine bolts and nuts to be galvanized.
- .4 Drift Bolts: to G40.21 from round stock button head and diamond or wedge point. All drift bolts to be galvanized.
- .5 Washers:
 - .1 Round Plate Washers: for 16 mm machine bolts will be 76 mm diameter by 6.4 mm thick, for 19 mm machine bolts will be 79 mm diameter by 7.9 mm thick and have a hole diameter of 18 mm and 21 mm diameter respectively. Washers to conform to G40.21. All washers to be galvanized.
 - .2 Plain Washers: to CSA B19.1, Class 2. All washers to be galvanized.
 - .3 Square washers are not permitted.
- .6 Galvanizing: will conform to CSA G164 "Hot Dip Galvanizing of Irregularly Shaped Articles." Unless otherwise specified, minimum weight of zinc coating will be as stated in Table 1 of this standard. Fabricator is to adhere to recommendations of Appendix A and Appendix B of standard.
- .7 Ladder Rungs and Hand Grips: to CSA G40.21, galvanized.
- .8 Welding in accordance with CSA Standards. The welders will be qualified to the appropriate classification as stated in CSA W47.1 "Certification of Companies for Fusion

Welding of Steel Structures." Conform welding to all appropriate requirements and recommendations of CSA Standard W59 "Welded Steel Construction" (metal arc welding).

PART 3 - EXECUTION

3.1 PREPARATION

- .1 Install structural timbers to details shown on drawings or as specified.

3.2 WHEELGUARD AND WHEELGUARD BLOCKING

- .1 Wheelguard timbers to be 200 mm x 200 mm, and will be in minimum lengths of 6100 mm or as specially required with butt joints made over wheelguard blocking. Wheelguard timbers to be chamfered on top, 25 mm on each horizontal and vertical surface.
- .2 Wheelguard blocks will be installed at 1500 mm on centre as support for wheelguard.
- .3 Wheelguard will be secured through wheelguard blocking, coping and two (2) crib timbers below with two (2) 25 mm diameter drift bolts as shown on detail drawings. Bolts to be countersunk and filled with leveling sealant following installation.
- .4 The installation of wheelguard and wheelguard blocking as per detail.

3.3 COPING

- .1 Install 200 mm x 250 mm treated timber coping in minimum length of 7620 mm around perimeter of wharf as directed.
- .2 Secure coping to timber below with 19 mm diameter drift bolts spaced at 1500 mm on centre. Use machine bolts through coping into new deck as detailed on the drawings.

3.4 FENDERS

- .1 Horizontal Fenders:
 - .1 Install hardwood timber fenders in minimum length of 4880 mm along top perimeter of wharf. Stagger joints in coping from joints in horizontal fender.
 - .2 Top horizontal fender to be chamfered 25 mm on top seaward face.
 - .3 Secure horizontal fender to coping with 16 mm diameter lag screws, minimum of four (4) each lag screws per fender, spaced at 1500 mm on centre. Secure bottom horizontal fender to a crib timber in a similar manner. All lag screws to be countersunk on the exterior face.
- .2 Vertical Fenders:
 - .1 Install hardwood timber fenders spaced at 300 mm on centre along face of wharf except for exterior corners where fenders will be closed face for 1500 mm as directed.
 - .2 Secure each fender with three (3) each 16 mm diameter lag screws evenly spaced from LNT to underside of horizontal fender. All drift bolts to be countersunk.
 - .3 All fenders to extend from underside of horizontal fender to 300 mm below LNT.
 - .4 Do not notch or cut fenders to provide straight wharf face. Continuous blocking will be installed behind fenders to provide straight face.

3.5 LADDERS

- .1 Install ladders on face of wharf in locations shown on drawings or designated by Engineer.
- .2 Ladder uprights to be 150 mm x 200 mm and installed from 900 mm below LNT to wheelguard elevation. Uprights to be bevelled at 45° on top and complete ladder upright to be painted.
- .3 Construction details and steel handgrips as

per detail.

- .4 Secure each upright with four (4) each evenly spaced 19 mm diameter galvanized lag screws. All lag screws to be countersunk.

3.6 PAINTING

- .1 Paint four (4) sides and exposed ends of wheelguard, exposed sides of wheelguard blocking, and complete ladder uprights as directed by the Departmental Representative.
- .2 Use one (1) coat of exterior oil wood primer and two (2) coats of alkyd/oil resin paint as specified. Paint materials for each coat to be product of a single manufacturer as specified. Ensure previous coat of primer or paint is dry before second coat is applied.

3.7 BOLT SIZING

- .1 Drift Bolts: Drift bolts used in the work will have a length equal to thickness of timbers being fastened less 50 mm unless otherwise specified. Holes for drift bolts will be bored 2 mm smaller diameter than size of steel used and for full length of bolts.
- .2 Machine Bolts: Machine bolts used in work will have a length equal to thickness of timbers being fastened plus thickness of washers plus 40 mm. Where bolts are countersunk, the length will be as above less depth of countersinking. Machine bolts will be threaded for 64 mm. Holes will be drilled same diameter as bolt.
- .3 Lag Screws: All lag screws used in the work will have a length equal to thickness of timbers being fastened less 50 mm and depth of countersinking. Holes for lag screws to be drilled same diameter as shank portion of screw and to inside thread diameter for threaded portion of screw and for full length.

All lag screws will be countersunk, screwed, not driven in place, and will have one (1) standard washer under the head.

- .4 Countersink lag screws in hardwood fenders and ladders to the extent that the minimum distance from face of timber to head of bolt is 12 mm.
- .5 Bolting of timbers without properly drilled bolt holes will not be accepted.

3.8 FIRE SEPARATORS .1 Fire separators to be as detailed on the drawings.

3.9 END OF WHARF BLOCKING .1 End of wharf blocking detail to be as shown on the drawings.

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies the requirements for the supplying, producing and placing crushed gravel for quarried stone as a granular base course to lines, grades and typical cross sections indicated, or as directed by Departmental Representative.

1.2 REFERENCES

- .1 ASTM C117-04, Standard Test method for material finer than 0.075 mm sieve in mineral aggregates by washing.
- .2 ASTM C131-06. Standard Test method for resistance to degradation of small size coarse aggregate by abrasion and impact in the Los Angeles machine.
- .3 ASTM C136-06, Standard Test Method for sieve analysis of fine and coarse aggregates.
- .4 CAN/CGSB-8.2-M88, Sieves testing, woven wire, metric.

1.3 DELIVERY, STORAGE
AND HANDLING

- .1 Deliver and stockpile aggregates as directed by Departmental Representative.

1.4 MEASUREMENT FOR
PAYMENT

- .1 Class "A" Granular Base: The supply and installation of Class "A" granular base for the uplands area will be measured in cubic metres of materials supplied and installed in the work.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Granular base fill (Class "A") will consist of clean, hard, durable crushed gravel or stone, free from shale, clay, friable materials, organic matter and other deleterious substances and graded within the following limits when tested to ASTM C136 and ASTM C117 and giving a smooth curve without sharp breaks when plotted on a semi-chart.

ASTM Sieve Designation	% Passing
19.0 mm	100
9.51 mm	50 - 80
4.76 mm	35 - 60
1.20 mm	15 - 35
300 um	7 - 20
75 um	3 - 6 (Pit Source)
	3 - 8 (Rock Source)

- .2 Physical Requirements for Class "A":
- .1 Liquid Limit ASTM D4318: Maximum 25
 - .2 Plasticity Index ASTM D4318: Maximum 0
 - .3 Los Angeles Abrasion ASTM C131-81
Maximum % loss by weight: 35
 - .4 Crushed Fragments: 50%. The percent of crushed particles will be determined by examining the fraction retained on the 4.76mm sieve and dividing the weight of the crushed particles by the total weight retained on the 4.76 mm sieve.
 - .5 CBR: ASSHTO T193-72 Min 100 when compacted to 100% of AASHTO T180-74 Method D.
- .3 Materials from deposits acceptable as to the quality of the particles, but deficient in sizes to provide the required gradation, may be accepted if the contractor furnishes and satisfactorily incorporates into the

product supplementary sizes from other sources to produce the required grading. If the deficiencies occur in Class "A" materials, corrections may be attempted by crushing to a smaller maximum particle size. In that event, the Departmental Representative will furnish special grading limits on the actual maximum particle size.

- .4 Material shall be considered unsuitable even though particle sizes are within the specified gradation limits if particle shape or any other characteristic precludes satisfactory compaction or fails to provide a roadway suitable for traffic. If, in the opinion of the Departmental Representative, an improved particle shape can be achieved by using a different crushing unit for that proposed by the contractor, then the Contractor shall supply and use a crushing unit of the type directed by the Departmental Representative.
- .5 Class "A" shall be processed by crushing and, when necessary, to eliminate surplus fines passing the 4.76 mm sieve, shall be screened and washed.

PART 3 - EXECUTION

3.1 INSTALLATION

- .1 Place granular base after sub-base surface is inspected and approved by Departmental Representative.
- .2 Placing:
 - .1 Construct granular base to depth and grade in area indicated.
 - .2 Ensure no frozen material is placed.
 - .3 Place material only on clean unfrozen surface, free from snow and ice.

- .4 The contractor shall place all granular bases in such a manner as to prevent contamination by other materials and to prevent segregation. If, in the opinion of the Departmental Representative, the methods and techniques used by the Contractor cannot overcome contamination or segregation, then the Departmental Representative may direct a modification in these methods which may require the use of an approved spreader box or other acceptable device.
- .5 All granular bases shall be placed in uniform layers such that the thickness of the compacted layer does not exceed 50 mm.
- .6 Prior to closing down operations for each working day, all granular materials shall be bladed and compacted to the specified density.
- .7 The materials shall be sprayed with water when and as directed by the Departmental Representative, either to aid compaction or reduce dust nuisance or both. When water is added to aid compaction, it shall be applied immediately ahead of the compacting unit.
- .8 Each layer of granular base shall be bladed shaped and compacted as necessary to produce the required profile and cross-section. The finished surface shall not deviate at any place on a 3 m straight edge by more than 10mm for Class "A". The upper layer shall be maintained to these tolerances and to the specified density until compaction of the contract. This may require keeping the moisture content at the appropriate value during periods of dry weather in addition to regarding and re-compacting as frequently as may be deemed necessary by the Departmental Representative.
- .3 Shape each layer to smooth contour and compact to specified density before

succeeding layer is placed.

- .4 Compaction Equipment:
 - .1 Compaction equipment to be capable of obtaining required material densities.
- .5 Compacting:
 - .1 All Class "A" materials shall be compacted to not less than 100% of the maximum Standard Proctor Dry Density ASTM D698-07e1 Method D.
 - .2 Compaction operations shall be carried out as closely as possible behind the placing and spreading operation. At the end of each working day, all materials placed shall have been compacted to the specified density.
 - .3 Each layer of material shall be graded and compacted as specified before the next layer is placed.
 - .4 Where necessary to obtain the required compaction, the contractor shall apply sufficient water by means of an approved distributor.

3.2 INSPECTION AND TESTING

- .1 Testing of materials and compaction will be carried out by testing laboratory designated by the Departmental Representative.
- .2 Contractor will pay costs for inspection and testing.
- .3 Sieve Analysis: proposed granular material will be tested to confirm suitability for intended use and conformity with specifications.
- .4 Frequency of Tests: to be determined by the Departmental Representative.

Wharf Extension Branch, NL 721395	GRANULAR BASE COURSES	Section 32 11 23 Page 6 2015-06-01
---	-----------------------	--

3.3 SITE TOLERANCES .1 Finished base surface to be within plus or minus 10 mm of established grade and cross section but not uniformly high or low.

3.4 PROTECTION .1 Maintain finished base in condition conforming to this section until succeeding material is applied or until acceptance by Departmental Representative.

PART 1 - GENERAL

- 1.1 RELATED SECTIONS .1 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- 1.2 DEFINITIONS .1 Dredging: excavating, transporting and disposing of underwater materials.
- .2 Class A material: solid rock requiring drilling and blasting to loosen, and boulders or rock fragments of individual volumes 4 m³ or more.
- .3 Class B material: loose or shale rock, silt, sand, quick sand, mud, shingle, gravel, clay, sand, gumbo, boulders, hardpan and debris of individual volumes less than 4 m³.
- .4 Obstructions: material other than Class A, having individual volumes of 4 m³ or more.
- .5 CPM: cubic metres place measurement. SQM: area in square metres projected horizontal. CMSM: cubic meters scow measurement.
- .6 Debris: pieces of wood, wire rope, scrap steel, pieces of concrete and other waste materials.
- .7 Grade: plane above which material is to be dredged.
- .8 Estimated quantity:
.1 Volume of material calculated to be above grade and within specified side slopes unless otherwise specified.
.2 Areas in square metres of material calculated horizontally to exist above grade and within dredge limits, unless otherwise specified.

- .9 Side slope: inclined surface or plane from subgrade at side limit of dredging area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical.
- .10 Chart Datum: permanently established plane from which soundings or tide heights are referenced, usually Lowest Normal Tide (LNT).
- .11 Coordinates:
 - .1 U.T.M.: universal transverse mercator projection.
 - .2 M.T.M.: modified transverse mercator projection.
 - .3 U.T.M. or M.T.M. Coordinates: plane rectangular coordinates used in grid system in which grid network is applied to U.T.M. or M.T.M. projection. Horizontal control information as indicated.
- .12 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action.
- .13 Matrix Block: each dredge area is presented as number of 1.2 x 3.0 m long blocks. Dependent on position of sounding, block may have 0 to 4 soundings contained within it.
- .14 Least of Minimum Plan: hydrographic survey plan in which least sounding in grouping of matrix blocks is plotted.
- .15 Instantaneous Mode: mode of operation of hydrographic survey equipment where only sounding observed at predetermined distance interval is retained in memory.
- .16 Average of Instantaneous Plan: hydrographic

survey plan in which average sounding in appropriate grouping of matrix blocks is plotted.

- .17 Lowest Normal Tide (LNT): plane so low that tide will seldom fall below it.
- .18 Cleared Area: area of dredging accepted as achieving the required grade and verified by a Departmental Representative survey.

1.3 SUBMITTALS

- .1 Submit to Departmental Representative for approval, four weeks before blasting, details of proposed blasting operations showing types and quantities of explosives, loading charges and patterns, type of blasting caps, blasting techniques, blast protection measures, time of blasting and other pertinent details. Submit subsequent changes to Departmental Representative before proceeding.
- .2 Submit to Departmental Representative complete photographic and descriptive record of buildings, roads and structures in general area of Project Work, before blasting is started. Describe buildings both inside and out. Record existing cracks in walls or structural components.

1.4 REGULATORY REQUIREMENTS

- .1 There are strict environmental procedures that must be followed during the Work.
- .2 Comply with municipal, provincial and national codes and regulations relating to project.
- .3 Mark floating equipment with lights in accordance with the provisions of the Canada Shipping Act Collision Regulations and Notices to Mariners.

1.5 SCHEDULING

- .1 Submit to Departmental Representative, within 2 weeks after acceptance of bid, schedule of work including time periods during which each operation involved in Work will be undertaken. At time of submission of schedule, meet with Departmental Representative to review schedule.
- .2 Adhere to schedule and take immediate action to correct any slippage by effectively altering existing dredging operations or mobilizing other equipment. Notify Departmental Representative of corrective action to be taken.

1.6 LOCATION

- .1 Work comprises dredging of areas as indicated on drawings.

1.7 INTERFERENCE TO NAVIGATION

- .1 Be familiar with vessel movements and fishery activities in area affected by dredging operations. Plan and execute Work in manner that will not interfere with fishing operations, marine operations and construction activities at wharf site.
- .2 Departmental Representative will not be responsible for loss of time, equipment, material or any other cost related to interference with moored vessels in harbour or due to other Contractor's operations.
- .3 Keep the Marine Communications and Traffic Services' Centre, Fisheries and Oceans Canada, informed of dredging operations in order that necessary Notices to Mariners will be issued.

1.8 DATUM, WATER
GAUGES AND TARGETS

- .1 Elevations used in this specification and contract drawings are in metres referred to Canadian Hydrographic Services Survey datum.
- .2 Areas to be dredged are to be referenced to vertical bench marks for each location of dredging as indicated.

1.9 FLOATING PLANT

- .1 Dredges or other floating plants to be employed on this Work, to be of Canadian registry, make or manufacture, or, must receive certificate of qualification from Industry Canada, Aerospace, Defence and Marine Branch and this certificate to accompany bid submission.
- .2 Requests for certification in format of form PWGSC-TPSGC 2843 (06/2007) attached to the Bid and Acceptance Form to be directed to Mr. Emile Rochon, Aerospace, Defence and Marine Branch, Industry Canada, CD Howe Building - Room 733C, 235 Queen Street, Ottawa, Ontario, K1A 0H5, and to be received there not less than 14 days prior to bid closing.

1.10 INSPECTION OF
SITE

- .1 Contractor to visit site of Work and become thoroughly familiar with extent and nature of Work and conditions affecting Work before bidding.

1.11 SITE
INFORMATION

- .1 Results of prior geotechnical investigations may be available by contacting the Departmental Representative.
- .2 Results of most recent soundings are included on the drawings. This data will be used for all calculations for quantity purposes. If the contractor wishes to perform own survey, a written notice must be submitted to the Departmental Representative (at least 7 days

notice) so the Departmental Representative can verify the sounding survey before the commencement of any work.

- .3 Results of prior geotechnical investigations that may be available for review, are made available for bidding purposes only. It should be noted that this information may differ from site conditions. Take this into consideration when submitting bid.
- .4 Borehole descriptions provided in previous reports are provided to give description of overburden and bedrock only.
- .5 Take necessary steps to become fully familiar with potential inclement weather and sea conditions in this area.

1.13 SURVEY
REQUIREMENTS

- .1 Provide, at own expense, survey vessel, equipment and crew to set up and maintain control for location of dredge limits and to sound areas immediately after dredging to verify that grade depth has been attained. Areas are to be sounded to provide sounding printout display of at least 2 x 2 m UTM grid to approval of Departmental Representative.

1.14 SURVEYS AND
ACCEPTANCE OF WORK

- .1 As soon as practical after acceptance of bid, Departmental Representative will complete pre-dredge survey of all dredge area locations. Contractor has 7 days to accept sounding survey in contract. If any differences are found, Departmental Representative will complete new pre-dredge survey of all dredge area locations within 7 days of the request. Survey will be by electronic survey equipment sounding in instantaneous mode. Survey plan at 1:250 scale plotting average of instantaneous

depths obtained in this survey will define actual pre-dredge seabed areas.

- .2 No area will be dredged prior to Departmental Representative and Contractor's mutual acceptance of pre-dredge survey for that area.
- .3 Post-dredge survey will be undertaken by Departmental Representative upon completion of dredging. Survey will confirm if dredging is completed as specified and whether area can be considered cleared area. Survey will be by electronic sweep equipment. Survey plan at 1:250 plotting least of minimum depths obtained in this survey will identify areas requiring reworking to obtain following elevations using least of minimum mode.
- .4 Contractor to redredge as necessary to remove all material within dredge areas which is found to be above grade using the least of minimum mode elevations as specified herein.
- .5 One additional survey will be undertaken at Departmental Representative's cost, for those areas not meeting acceptance criteria for dredging. All additional surveys required to clear areas will be undertaken by the Departmental Representative at Contractor's cost.

1.15 MEASUREMENT
FOR PAYMENT

- .1 Only material excavated above grade plane and within side slopes indicated or specified will be measured.
- .2 Excavation/dredging prior to rock mattress placement will not be measured separately for payment. Include these costs as incidental

to rock mattress. Reference the pay limits on the drawings.

- .3 Harbour Dredging: will be measured in cubic metres, determined from existing seabed elevation established from the current sounding survey down to grade depth elevation, within pay limits shown on drawings. Quantities will be determined by a sounding survey performed by the Departmental Representative Survey Crew after dredging survey is completed by using electronic sounding and DPGS positioning equipment. The Departmental Representative will verify that the Contractor has performed dredging to the specified grade depth. No payment will be made for over-dredging. Departmental Representative will conduct an interim and final survey. The Contractor will formally request at least seven (7) days in advance that the final after-dredging survey be performed upon completion of dredging. The survey will be dependent on the weather. If the survey and inspection shows that all material has not been removed, the Contractor is to re-dredge to obtain grade depth. The Contractor will perform a sounding survey, using a method approved by the Departmental Representative to verify that the specified dredge depth has been obtained. The Departmental Representative will then perform a third survey for final verification of dredge depth. This third sounding survey and any subsequent surveys will be at the cost of the Contractor.
- .4 No separate payment will be made for Contractor's survey vessel, equipment and crew or diving services.
- .5 Payment will include disposal of dredge material, using water tight boxes, at locations specified or as directed by the Departmental Representative.

- .6 There will be no additional payment for delays and/or downtime for vessel traffic, fishery operations, marine operations, during periods when no dredging is permitted. Contractor should contact the Harbour Authority to determine schedules of operations.
- .7 There will be no additional payment for downtime and for delays caused by vessel traffic.
- .8 Removal of infilling material will not be measured for payment.
- .9 No separate payment will be made for sweeping.

PART 2 - PRODUCTS

2.1 DREDGING EQUIPMENT

- .1 Contractor to determine required equipment necessary to dredge material specified and to dispose of dredged material at approved locations.

PART 3 - EXECUTION

3.1 GENERAL

- .1 Mark floating equipment with lights in accordance with the provisions of the Canada Shipping Act Collision Regulations and maintain radio watch on board.
- .2 Place and maintain buoys, markers and lights

required to define work and disposal areas.

- .3 Lay out Work from control points and baselines established by Departmental Representative. Be responsible for accuracy of Work relative to established bench marks and baseline. Provide and maintain electronic position fixing and distance measuring equipment, laser transits and such other equipment as normally required for accurate dredging control.
- .4 Establish and maintain tide boards in order that proper depth of dredging can be determined. Locate tide boards so as to be clearly visible.
- .5 Remove materials above specified grade depths, within limits indicated. Material removed from below grade depth or outside specified pay limits is not part of Work.
- .6 Remove shoaling which occurs as result of Work at no expense to Canada.
- .7 Remove material cast-over on surrounding area and dispose of it as dredged material.
- .8 Remove infilling in dredge areas which occurs prior to acceptance by Departmental Representative.

3.2 CLASS 'B'
REMOVAL

- .1 All material to be dredged is considered to be Class "B".

3.3 DISPOSAL OF
DREDGED MATERIAL

- .1 Dispose of dredged material by depositing in disposal areas in manner approved by Departmental Representative, using water tight truck boxes.

- 3.4 DREDGING IN VICINITY OF STRUCTURES
- .1 Take precautions not to undermine existing structures during dredging. Carry costs for temporary measures to prevent undermining of structures to remain in the lump sum arrangement.
- 3.5 SWEEPING
- .1 Sweep dredged areas on completion of dredging to confirm that grade depth has been achieved.
- .2 Sweeping equipment to consist of heavy steel beam suspended from scow at required grade depth or other approved method. Beam to be capable of adjustment and calibration and approved by Departmental Representative.
- .3 If, as result of incomplete Work, additional verification of depths by sounding or sweeping becomes necessary, additional costs involved shall be paid by Contractor.
- 3.6 RE-DREDGING
- .1 Re-dredge unsatisfactory Work and verify depths with additional sounding or sweeping to approval of Departmental Representative.
- 3.7 CO-OPERATION AND ASSISTANCE TO DEPARTMENTAL REPRESENTATIVE
- .1 Co-operate with Departmental Representative on inspection of Work and provide assistance requested.
- .2 On request of Departmental Representative, furnish use of such boats, equipment, labour and materials forming ordinary and usual part of dredging plant as may be reasonably necessary to inspect and supervise Work.

PART 1 - GENERAL

- 1.1 DESCRIPTION .1 This section specifies the requirements for supply and installation of mooring devices as follows:
- .1 Supply and installation of Type "B1" mooring cleats.
- 1.2 RELATED WORK .1 Section 02 41 16 - Sitework, Demolition, and Removal.
- .2 Section 03 10 00 - Concrete Forming and Accessories.
- .3 Section 03 20 00 - Concrete Reinforcing.
- .4 Section 03 30 00 - Cast-in-Place Concrete.
- 1.3 MEASUREMENT FOR PAYMENT .1 Mooring Cleats - Type "B1": The supply and installation of Type "B1" mooring cleats, including reinforced concrete pedestal, will be measured by the unit secured in place. Contractor to provide all concrete, reinforcing steel, anchor bolts, nuts, washers, grout, fastenings, paint, plant, equipment, and labour.

PART 2 - PRODUCTS

- 2.1 MATERIALS .1 Mooring Devices:
- .1 Mooring Cleats Type "B1": galvanized cast iron cleats, 36.2 kg weight as dimensioned on the attached drawing.

.2 Anchor Bolts and Nuts: to ASTM A307, galvanized.

.3 Non-Shrink Grout: pre-mixed compound of non-metallic aggregate and plasticizing agents, capable of developing minimum compressive strength of 50 MPa at 28 days.

.4 Galvanizing: to CSA G164, minimum zinc coating 610 g/m².

.5 Welding: to CSA W59.

.6 Sealer: to Section 07 92 10.

.7 Concrete: to Section 03 30 00.

.8 Concrete Reinforcement: to CSA G30.12M, Grade 400.

2.2 SHOP DRAWINGS .1 Submit fabricator's shop drawings on cleats in accordance with Section 01 33 00 - Submittal Procedures.

PART 3 - EXECUTION

3.1 INSTALLATION .1 Mooring Cleats - Type "B1":
.1 Install concrete cleat block for Type "B1" cleats as per attached drawings.
.2 Install concrete cleat blocks monolithically with deck.
.3 Secure cleats with 25 mm diameter anchor bolts of lengths required complete with associated nuts and washers.
.4 After cleat installation is complete, bolt holes in cleats to be filled with approved waterproofing compound.

3.2 GROUT .1 Set all mooring cleats at locations and elevations indicated or as directed by the Departmental Representative. Grout under base of cleat using a non-shrink, non-metallic type of grout after tightening

Wharf Extension Branch, NL 721395	MOORING DEVICES	Section 35 59 29 Page 3 2015-06-01
---	-----------------	--

of anchor bolts or positioning wedges. Grout must be approved by Departmental Representative. Fill anchor bolt holes with approved sealer. Ensure that temperatures of foundation, air, base and grout are within range specified by grout manufacturers.

- .2 Do not grout until approval given by Departmental Representative.