

PART 1 - GENERAL

- | | | |
|------------------------------------|----|--|
| <u>1.1 DESCRIPTION</u> | .1 | This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed. |
| <u>1.2 GENERAL REQUIREMENTS</u> | .1 | A Notice to Shipping is to be issued prior to commencement and upon completion of work. |
| | .2 | During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations. |
| | .3 | Upon completion of the project, a written Notice to Mariners must be issued. |
| <u>1.3 PROTECTION</u> | .1 | Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada. |
| | .2 | Place a floating boom around entire demolition site to prevent loss of any materials. |
| | .3 | Remove all floating debris from water on a routine and timely basis. |
| <u>1.4 MEASUREMENT FOR PAYMENT</u> | .1 | All cost associated for items in this section is to be measured in fixed price items including all plant, labour, materials required to complete this work as indicated on drawings. |
-

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.2 REMOVAL

- .1 Demolition and removal of existing horizontal/vertical fenders, ladder and wheel guard c/w blocking from existing marginal wharf indicated on drawings.
 - .2 Removal of existing scour protection rip rap at the outside face of the existing marginal wharf and transferred to a designated site and stockpiled.
 - .3 Removal of existing pipe wheel guard and relocate as shown on drawings.
 - .4 Sawcut and bust out existing concrete deck to install new electrical conduit as shown on drawings.
 - .5 Sawcut existing asphalt parking area, remove and dispose at an approved dumpsite as shown on accompanying drawings.
 - .6 Remove in their entirety all materials and objects specified for removal.
 - .7 Do not disturb adjacent work designated to remain in place.
-

3.3 DISPOSAL OF
MATERIAL

- .1 All demolished materials, except materials designated to be reused or turned over to owner, will become property of contractor and will be removed from site and disposed of to satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.
- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.