

PART 1 - GENERAL

1.1 SUMMARY

- .1 Section Includes:
 - .1 General requirements for building Energy Monitoring and Control System (EMCS) that are common to NMS EMCS Sections.
- .2 Related Requirements
 - .1 Section 21 05 01 - Common Work Results for Mechanical.

1.2 REFERENCES

- .1 American National Standards Institute (ANSI)/The Instrumentation, Systems and Automation Society (ISA).
 - .1 ANSI/ISA 5.5-1985, Graphic Symbols for Process Displays.
- .2 American National Standards Institute (ANSI)/ Institute of Electrical and Electronics Engineers (IEEE).
 - .1 ANSI/IEEE 260.1-1993, American National Standard Letter Symbols Units of Measurement (SI Units, Customary Inch-Pound Units, and Certain Other Units).
- .3 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE).
 - .1 ASHRAE STD 135-R2001, BACNET - Data Communication Protocol for Building Automation and Control Network.
- .4 Canadian Standards Association (CSA International).
 - .1 CAN/CSA-Z234.1-89(R1995), Canadian Metric Practice Guide.
- .5 Consumer Electronics Association (CEA).
 - .1 CEA-709.1-B-2002, Control Network Protocol Specification.
- .6 Department of Justice Canada (Jus).
 - .1 Canadian Environmental Assessment Act (CEAA), 1995, c. 37.
 - .2 Canadian Environmental Protection Act (CEPA), 1999, c. 33.
- .7 Health Canada/Workplace Hazardous Materials Information System (WHMIS).
 - .1 Material Safety Data Sheets (MSDS).
- .8 Transport Canada (TC).
 - .1 Transportation of Dangerous Goods Act (TDGA), 1992, c. 34.

1.3 ACRONYMS AND ABBREVIATIONS

- .1 Acronyms used in EMCS:
 - .1 AEL - Average Effectiveness Level.
 - .2 AI - Analog Input.
 - .3 AIT - Agreement on International Trade.
 - .4 AO - Analog Output.
 - .5 BACnet - Building Automation and Control Network.
 - .6 BC(s) - Building Controller(s).
 - .7 BECC - Building Environmental Control Center.
 - .8 CAD - Computer Aided Design.
-

- .9 CDL - Control Description Logic.
- .10 CDS - Control Design Schematic.
- .11 COSV - Change of State or Value.
- .12 CPU - Central Processing Unit.
- .13 DI - Digital Input.
- .14 DO - Digital Output.
- .15 DP - Differential Pressure.
- .16 ECU - Equipment Control Unit.
- .17 EMCS - Energy Monitoring and Control System.
- .18 HVAC - Heating, Ventilation, Air Conditioning.
- .19 IDE - Interface Device Equipment.
- .20 I/O - Input/Output.
- .21 ISA - Industry Standard Architecture.
- .22 LAN - Local Area Network.
- .23 LCU - Local Control Unit.
- .24 MCU - Master Control Unit.
- .25 NAFTA - North American Free Trade Agreement.
- .26 NC - Normally Closed.
- .27 NO - Normally Open.
- .28 OS - Operating System.
- .29 O&M - Operation and Maintenance.
- .30 OWS - Operator Work Station.
- .31 PC - Personal Computer.
- .32 PCI - Peripheral Control Interface.
- .33 PCMCIA - Personal Computer Micro-Card Interface Adapter.
- .34 PID - Proportional, Integral and Derivative.
- .35 RAM - Random Access Memory.
- .36 SP - Static Pressure.
- .37 ROM - Read Only Memory.
- .38 TCU - Terminal Control Unit.
- .39 USB - Universal Serial Bus.
- .40 UPS - Uninterruptible Power Supply.
- .41 VAV - Variable Air Volume.

1.4 DEFINITIONS

- .1 Point: may be logical or physical.
 - .1 Logical points: values calculated by system such as setpoints, totals, counts, derived corrections and may include, but not limited to result of and statements in CDL's.
 - .2 Physical points: inputs or outputs which have hardware wired to controllers which are measuring physical properties, or providing status conditions of contacts or relays which provide interaction with related equipment (stop, start) and valve or damper actuators.
- .2 Point Name: composed of two parts, point identifier and point expansion.
 - .1 Point identifier: comprised of three descriptors, "area" descriptor, "system" descriptor and "point" descriptor, for which database to provide 25 character field for each point identifier. "System" is system that point is located on.
 - .1 Area descriptor: building or part of building where point is located.
 - .2 System descriptor: system that point is located on.
 - .3 Point descriptor: physical or logical point description. For point identifier "area", "system" and "point" will be shortforms or acronyms. Database must provide 25character field for each point identifier.

- .2 Point expansion : comprised of three fields, one for each descriptor. Expanded form of shortform or acronym used in "area", "system" and "point" descriptors is placed into appropriate point expansion field. Database must provide 32 character field for each point expansion.
- .3 Bilingual systems to include additional point identifier expansion fields of equal capacity for each point name for second language.
 - .1 System to support use of numbers and readable characters including blanks, periods or underscores to enhance user readability for each of the above strings.
- .3 Point Object Type: points fall into following object types:
 - .1 AI (analog input).
 - .2 AO (analog output).
 - .3 DI (digital input).
 - .4 DO (digital output).
 - .5 Pulse inputs.
- .4 Symbols and engineering unit abbreviations utilized in displays: to ANSI/ISA S5.5.
 - .1 Printouts: to ANSI/IEEE 260.1.

1.5 SYSTEM DESCRIPTION

- .1 Work covered by sections referred to above consists of fully operational EMCS, including, but not limited to, following:
 - .1 DDC VAV box actuator and temperature sensors to match existing.
 - .2 Data communications equipment necessary to effect EMCS data transmission system.
 - .3 Field control devices.
 - .4 Software/Hardware complete with full documentation.
 - .5 Acceptance tests, technical support during commissioning, full documentation.
 - .6 Wiring interface co-ordination of equipment supplied by others.
 - .7 Miscellaneous work as specified in these sections and as indicated.
- .2 Design Requirements:
 - .1 Design and provide conduit and wiring linking elements of system.
 - .2 Supply sufficient programmable controllers of types to meet project requirements. Quantity and points contents as reviewed by Departmental Representative prior to installation.
 - .3 Location of controllers as reviewed by Departmental Representative prior to installation.
- .3 Existing systems: Existing base building controls service contractor for R.H. Coats building is Regulvar.
- .4 All workmanship and materials to match existing base building standard.

1.6 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Quality Control:
 - .1 Provide equipment and material from manufacturer's regular production, CSA certified, manufactured to standard quoted plus additional specified requirements.
 - .2 Where CSA certified equipment is not available submit such equipment to inspection authorities for special inspection and approval before delivery to site.
-

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Material Delivery Schedule: provide Departmental Representative with schedule within 2 weeks after award of Contract.
- .2 Waste Management and Disposal:
 - .1 Separate waste materials for reuse and recycling.
 - .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .3 Collect and separate for disposal paper plastic polystyrene corrugated cardboard packaging material in appropriate on-site bins for recycling.
 - .4 Separate for reuse and recycling and place in designated containers Steel Metal Plastic waste in accordance with Waste Management Plan.
 - .5 Place materials defined as hazardous or toxic in designated containers.

1.8 EXISTING- CONTROL COMPONENTS

- .1 Utilize existing control wiring and piping as indicated.
 - .2 Re-use field control devices that are usable in their original configuration provided that they conform to applicable codes, standards specifications.
 - .1 Do not modify original design of existing devices without written permission from Departmental Representative.
 - .2 Provide for new, properly designed device where re-usability of components is uncertain.
 - .3 Inspect and test existing devices intended for re-use within 30 days of award of contract, and prior to installation of new devices.
 - .1 Furnish test report within 40 days of award of contract listing each component to be re-used and indicating whether it is in good order or requires repair by Departmental Representative.
 - .2 Failure to produce test report will constitute acceptance of existing devices by contractor.
 - .4 Non-functioning items:
 - .1 Provide with report specification sheets or written functional requirements to support findings.
 - .2 Departmental Representative will repair or replace existing items judged defective yet deemed necessary for EMCS.
 - .5 Submit written request for permission to disconnect controls and to obtain equipment downtime before proceeding with Work.
 - .6 Assume responsibility for controls to be incorporated into EMCS after written receipt of approval from Departmental Representative.
 - .1 Be responsible for items repaired or replaced by Departmental Representative.
 - .2 Be responsible for repair costs due to negligence or abuse of equipment.
 - .3 Responsibility for existing devices terminates upon final acceptance of EMCS by Departmental Representative.
 - .7 Remove existing controls not re-used or not required. Place in approved storage for disposition as directed.
-

PART 2 - PRODUCTS**2.1 EQUIPMENT**

- .1 Control Network Protocol and Data Communication Protocol: to CEA 709.1 ASHRAE STD 135.
- .2 Complete list of equipment and materials to be used on project and forming part of bid tender documents by adding manufacturer's name, model number and details of materials, and submit for approval.
 - .1 All materials to match existing base building standards.

PART 3 - EXECUTION**3.1 MANUFACTURER'S RECOMMENDATIONS**

- .1 Installation: to manufacturer's recommendations.