

PART 1 - GENERAL

1.1 SUMMARY

- .1 Section Includes:
 - .1 Seismic restraint systems for statically supported and vibration isolated equipment and systems; including all mechanical equipment, both vibration isolated and statically supported.
- .2 Related Requirements
 - .1 Section 21 13 13 - Wet Pipe Sprinkler Systems.

1.2 REFERENCES

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .2 National Research Council Canada (NRCC)
 - .1 NRCC NBCC-2010, National Building Code of Canada 2010.

1.3 DEFINITIONS

- .1 Priority Two (P2) Buildings: buildings in which life safety is of paramount concern. It is not necessary that P2 buildings remain operative during or after earthquake activity.
- .2 SRS: acronym for Seismic Restraint System.

1.4 DESCRIPTION

- .1 SRS fully integrated into, and compatible with:
 - .1 Noise and vibration controls specified elsewhere.
 - .2 Structural, mechanical, electrical design of project.
- .2 Systems, equipment not required to be operational during and after seismic event.
- .3 During seismic event, SRS to prevent systems and equipment from causing personal injury and from moving from normal position.
- .4 Designed by Professional Engineer specializing in design of SRS and registered in Province of Ontario.

1.5 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Shop drawings: submit drawings stamped and signed by professional engineer registered or licensed in Province of Ontario, Canada.
 - .3 Submit design data including:
 - .1 Full details of design criteria.
-

- .2 Design calculations (including restraint loads resulting from seismic forces in accordance with National Building Code, detailed work sheets, tables).
 - .3 Separate shop drawings for each SRS and devices for each system, equipment.
 - .4 Identification of location of devices.
 - .5 Schedules of types of SRS equipment and devices.
 - .6 Details of fasteners and attachments to structure, anchorage loadings, attachment methods.
 - .7 Installation procedures and instructions.
 - .8 Design calculations including restraint loads to NBC and Supplement.
 - .9 Detailed work sheets, tables Simplified, Detailed work sheets, tables. Simplified, conservative assumptions may be acceptable.
- .4 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
- .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.
 - .1 Departmental Representative will make available 1 copy of systems supplier's installation instructions.
- .5 Closeout Submittals:
- .1 Provide maintenance data including monitoring requirements for incorporation into manuals specified in Section 01 78 00 - Closeout Submittals.

1.6 QUALITY ASSURANCE

- .1 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.7 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
 - .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
-

PART 2 - PRODUCTS

2.1 SRS MANUFACTURER

- .1 SRS from one manufacturer regularly engaged in SRS production.

2.2 GENERAL

- .1 SRS to provide gentle and steady cushioning action and avoid high impact loads.
- .2 SRS to restrain seismic forces in every direction.
- .3 Fasteners and attachment points to resist same load as seismic restraints.
- .4 SRS of Piping systems compatible with:
 - .1 Expansion, anchoring and guiding requirements.
 - .2 Equipment vibration isolation and equipment SRS.
- .5 SRS utilizing cast iron, threaded pipe, other brittle materials not permitted.
- .6 Attachments to RC structure:
 - .1 Use high strength mechanical expansion anchors.
 - .2 Drilled or power driven anchors not permitted.
- .7 Wet pipe sprinkler systems: refer to Section 21 13 13 - Wet Pipe Sprinkler Systems.
- .8 Seismic control measures not to interfere with integrity of firestopping.

2.3 SRS FOR STATIC EQUIPMENT, SYSTEMS

- .1 Floor-mounted equipment, systems:
 - .1 Anchor equipment to equipment supports.
 - .2 Anchor equipment supports to structure.
 - .3 Use size of bolts scheduled in approved shop drawings.
- .2 Suspended equipment, systems:
 - .1 Use one or combination of following methods:
 - .1 Install tight to structure.
 - .2 Cross-brace in every direction.
 - .3 Brace back to structure.
 - .4 Slack cable restraint system.
 - .2 SCS to prevent sway in horizontal plane, "rocking" in vertical plane, sliding and buckling in axial direction.
 - .3 Hanger rods to withstand compressive loading and buckling.

2.4 SRS FOR VIBRATION ISOLATED EQUIPMENT

- .1 Floor mounted equipment, systems:
 - .1 Use one or combination of following methods:
 - .1 Vibration isolators with built-in snubbers.
 - .2 Vibration isolators and separate snubbers.
 - .3 Built-up snubber system approved by Departmental Representative, consisting of structural elements and elastomeric layer.
 - .2 SRS to resist complete isolator unloading.
 - .3 SRS not to jeopardize noise and vibration isolation systems. Provide 4-8 mm clearance between seismic restraint snubbers and equipment during normal operation of equipment and systems.
 - .4 Cushioning action: gentle and steady by utilizing elastomeric material or other means in order to avoid high impact loads.
- .2 Suspended equipment, systems:
 - .1 Use one or combination of following methods:
 - .1 Slack cable restraint system.
 - .2 Brace back to structure via vibration isolators and snubbers.

2.5 SLACK CABLE RESTRAINT SYSTEM (SCS)

- .1 Use elastomer materials or similar to avoid high impact loads and provide gentle and steady cushioning action.
- .2 SCS to prevent sway in horizontal plane, "rocking" in vertical plane, sliding and buckling in axial direction.
- .3 Hanger rods to withstand compressive loading and buckling.

PART 3 - EXECUTION

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Attachment points and fasteners:
 - .1 To withstand same maximum load that seismic restraint is to resist and in every direction.
- .2 Slack Cable Systems (SCS):
 - .1 Connect to suspended equipment so that axial projection of wire passes through centre of gravity of equipment.
 - .2 Use appropriate grommets, shackles, other hardware to ensure alignment of restraints and to avoid bending of cables at connection points.
 - .3 Piping systems: provide transverse SCS at 10 m spacing maximum, longitudinal SCS at 20 m maximum or as limited by anchor/slack cable performance.
 - .4 Small pipes may be rigidly secured to larger pipes for restraint purposes, but not reverse.
 - .5 Orient restraint wires on ceiling hung equipment at approximately 90 degrees to each other (in plan), tie back to structure at maximum of 45 degrees to structure.

- .6 Adjust restraint cables so that they are not visibly slack but permit vibration isolation system to function normally.
- .7 Tighten cable to reduce slack to 40 mm under thumb pressure. Cable not to support weight during normal operation.
- .3 Install SRS at least 25 mm from equipment, systems, services.
- .4 Miscellaneous equipment not vibration-isolated:
 - .1 Bolt through house-keeping pad to structure.
- .5 Co-ordinate connections with other disciplines.
- .6 Vertical tanks:
 - .1 Anchor through house-keeping pad to structure.
 - .2 Provide steel bands above centre of gravity.
- .7 Horizontal tanks:
 - .1 Provide at least two straps with anchor bolts fastened to structure.

3.3 FIELD QUALITY CONTROL

- .1 Manufacturer's Field Services:
 - .1 Arrange with manufacturer's representative to review work of this Section and submit written reports to verify compliance with Contract Documents.
 - .2 Manufacturer's Field Services: consisting of product use recommendations and periodic site visits to review installation, scheduled as follows:
 - .1 After delivery and storage of Products.
 - .2 After preparatory work is complete but before installation commences.
 - .3 Twice during the installation, at 25% and 60% completion stages.
 - .4 Upon completion of installation.
 - .3 Submit manufacturer's reports to Departmental Representative within 3 days of manufacturer representative's review.
- .2 Inspection and Certification:
 - .1 SRS: inspected and certified by Seismic Engineer upon completion of installation.
 - .2 Provide written report to Departmental Representative with certificate of compliance.

3.4 CLEANING

- .1 Proceed in accordance with Section 01 00 10 - General Instructions.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

PART 1 - GENERAL

1.1 SUMMARY

- .1 TAB is used throughout this Section to describe the process, methods and requirements of testing, adjusting and balancing for HVAC.
- .2 TAB means to test, adjust and balance to perform in accordance with requirements of Contract Documents and to do other work as specified in this section.

1.2 QUALIFICATIONS OF TAB PERSONNEL

- .1 Submit names of personnel to perform TAB to Departmental Representative within 15 days of award of contract.
- .2 Provide documentation confirming qualifications, successful experience.
- .3 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
 - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1-2002.
 - .2 National Environmental Balancing Bureau (NEBB) TABES, Procedural Standards for Testing, Adjusting, Balancing of Environmental Systems-1998.
 - .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing-2002.
- .4 Recommendations and suggested practices contained in the TAB Standard: mandatory.
- .5 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
- .6 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
- .7 Where instrument manufacturer calibration recommendations are more stringent than those listed in TAB Standard, use manufacturer's recommendations.
- .8 TAB Standard quality assurance provisions such as performance guarantees form part of this contract.
 - .1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.
 - .2 Where new procedures, and requirements, are applicable to Contract requirements have been published or adopted by body responsible for TAB Standard used (AABC, NEBB, or TABB), requirements and recommendations contained in these procedures and requirements are mandatory.

1.3 PURPOSE OF TAB

- .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads
 - .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.
-

- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.

1.4 CO-ORDINATION

- .1 Schedule time required for TAB (including repairs, re-testing) into project construction and completion schedule to ensure completion before acceptance of project.
- .2 Do TAB of each system independently and subsequently, where interlocked with other systems, in unison with those systems.

1.5 PRE-TAB REVIEW

- .1 Review contract documents before project construction is started and confirm in writing to Departmental Representative adequacy of provisions for TAB and other aspects of design and installation pertinent to success of TAB.
- .2 Review specified standards and report to Departmental Representative in writing proposed procedures which vary from standard.
- .3 During construction, co-ordinate location and installation of TAB devices, equipment, accessories, measurement ports and fittings.

1.6 START-UP

- .1 Follow start-up procedures as recommended by equipment manufacturer unless specified otherwise.
- .2 Follow special start-up procedures specified elsewhere in Division 23.

1.7 OPERATION OF SYSTEMS DURING TAB

- .1 Operate systems for length of time required for TAB and as required by Departmental Representative for verification of TAB reports.

1.8 START OF TAB

- .1 Notify Departmental Representative 7 days prior to start of TAB.
 - .2 Start TAB when building is essentially completed, including:
 - .3 Installation of ceilings, doors, windows, other construction affecting TAB.
 - .4 Application of weatherstripping, sealing, and caulking.
 - .5 Pressure, leakage, other tests specified elsewhere Division 23.
 - .6 Provisions for TAB installed and operational.
-

- .7 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
 - .1 Proper thermal overload protection in place for electrical equipment.
 - .2 Air systems:
 - .1 Filters in place, clean.
 - .2 Duct systems clean.
 - .3 Ducts, air shafts, ceiling plenums are airtight to within specified tolerances.
 - .4 Correct fan rotation.
 - .5 Fire, smoke, volume control dampers installed and open.
 - .6 Coil fins combed, clean.
 - .7 Access doors, installed, closed.
 - .8 Outlets installed, volume control dampers open.

1.9 APPLICATION TOLERANCES

- .1 Do TAB to following tolerances of design values:
 - .1 Other HVAC systems: plus 5%, minus 5%.

1.10 ACCURACY TOLERANCES

- .1 Measured values accurate to within plus or minus 2% of actual values.

1.11 INSTRUMENTS

- .1 Prior to TAB, submit to Departmental Representative list of instruments used together with serial numbers.
- .2 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.
- .3 Calibrate within 3 months of TAB. Provide certificate of calibration to Departmental Representative.

1.12 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.

1.13 PRELIMINARY TAB REPORT

- .1 Submit for checking and approval of Departmental Representative, prior to submission of formal TAB report, sample of rough TAB sheets. Include:
 - .1 Details of instruments used.
 - .2 Details of TAB procedures employed.
 - .3 Calculations procedures.
 - .4 Summaries.
-

1.14 TAB REPORT

- .1 Format in accordance with referenced standard.
- .2 TAB report to show results in SI units and to include:
 - .1 Project record drawings.
 - .2 System schematics.
- .3 Submit 6 copies of TAB Report to Departmental Representative for verification and approval, in English in D-ring binders, complete with index tabs.

1.15 VERIFICATION

- .1 Reported results subject to verification by Departmental Representative.
- .2 Provide personnel and instrumentation to verify up to 30% of reported results.
- .3 Number and location of verified results as directed by Departmental Representative.
- .4 Pay costs to repeat TAB as required to satisfaction of Departmental Representative.

1.16 SETTINGS

- .1 After TAB is completed to satisfaction of Departmental Representative, replace drive guards, close access doors, lock devices in set positions, ensure sensors are at required settings.
- .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.

1.17 COMPLETION OF TAB

- .1 TAB considered complete when final TAB Report received and approved by Departmental Representative.

1.18 AIR SYSTEMS

- .1 Standard: TAB to most stringent of this section or TAB standards of AABC, NEBB, SMACNA & ASHRAE.
 - .2 Do TAB of systems, equipment, components, controls specified Division 23.
 - .3 Qualifications: personnel performing TAB current member in good standing of AABC or NEBB.
 - .4 Quality assurance: perform TAB under direction of supervisor qualified to standards of AABC or NEBB.
 - .5 Measurements: to include as appropriate for systems, equipment, components, controls: air velocity, static pressure, flow rate, pressure drop (or loss), temperatures (dry bulb, wet bulb, dewpoint), duct cross-sectional area, RPM, electrical power, voltage, noise, vibration.
-

- .6 Locations of equipment measurements: to include as appropriate:
 - .1 Inlet and outlet of dampers, filter, coil, humidifier, fan, other equipment causing changes in conditions.
 - .2 At controllers, controlled device.
- .7 Locations of systems measurements to include as appropriate: main ducts, main branch, sub-branch, run-out (or grille, register or diffuser).

PART 2 - PRODUCTS

2.1 NOT USED

- .1 Not used.

PART 3 - EXECUTION

3.1 NOT USED

- .1 Not used.

PART 1 - GENERAL

1.1 REFERENCES

- .1 Definitions:
 - .1 For purposes of this section:
 - .1 "CONCEALED" - insulated mechanical services and equipment in suspended ceilings and non-accessible chases and furred-in spaces.
 - .2 "EXPOSED" - means "not concealed" as previously defined.
 - .3 Insulation systems - insulation material, fasteners, jackets, and other accessories.
 - .2 TIAC Codes:
 - .1 CRD: Code Round Ductwork,
 - .2 CRF: Code Rectangular Finish.
- .2 Reference Standards:
 - .1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
 - .1 ASHRAE/IESNA 90.1-2010, Energy Standard for Buildings Except Low-Rise Residential Buildings.
 - .2 ASTM International Inc.
 - .1 ASTM C335/C335M-10e1, Standard Test Method for Steady State Heat Transfer Properties of Pipe Insulation.
 - .2 ASTM C553-13, Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications.
 - .3 ASTM C612-14, Standard Specification for Mineral Fiber Block and Board Thermal Insulation.
 - .3 Canadian General Standards Board (CGSB)
 - .1 CGSB 51-GP-52Ma, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.
 - .4 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (2005).
 - .5 Underwriters Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-10, Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for duct insulation, and include product characteristics, performance criteria, physical size, finish and limitations.
 - .1 Description of equipment giving manufacturer's name, type, model, year and capacity.
 - .2 Details of operation, servicing and maintenance.
 - .3 Recommended spare parts list.
- .3 Shop Drawings:
 - .1 Provide drawings stamped and signed by professional engineer registered or licensed in Province of Ontario, Canada.
- .4 Samples:
 - .1 Submit for approval: complete assembly of each type of insulation system, insulation, coating, and adhesive proposed.
 - .2 Mount sample on 12 mm plywood board.

- .3 Affix typewritten label beneath sample indicating service.
- .5 Manufacturers' Instructions:
 - .1 Provide manufacture's written duct insulation jointing recommendations. and special handling criteria, installation sequence, cleaning procedures.

1.3 QUALITY ASSURANCE

- .1 Qualifications:
 - .1 Installer: specialist in performing work of this section, qualified to standards member of TIAC.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address and ULC markings.
- .3 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding and packaging materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

PART 2 - PRODUCTS

2.1 FIRE AND SMOKE RATING

- .1 To CAN/ULC-S102:
 - .1 Maximum flame spread rating: 25.
 - .2 Maximum smoke developed rating: 50.

2.2 INSULATION

- .1 Mineral fibre: as specified includes glass fibre, rock wool, slag wool.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at 24 degrees C mean temperature when tested in accordance with ASTM C335.
- .3 TIAC Code C-1: Rigid mineral fibre board to ASTM C612, with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in PART 3 of this Section).
- .4 TIAC Code C-2: Mineral fibre blanket to ASTM C553 faced with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in PART 3 of this section).
 - .1 Mineral fibre: to ASTM C553.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Maximum "k" factor: to ASTM C553.

2.3 ACCESSORIES

- .1 Vapour retarder lap adhesive:
 - .1 Water based, fire retardant type, compatible with insulation.
- .2 Tape: self-adhesive, aluminum, plain reinforced, 50 mm wide minimum.
- .3 Contact adhesive: quick-setting.
- .4 Tie wire: 1.5 mm stainless steel.
- .5 Fasteners: 4 mm diameter pins with 35 mm diameter clips, length to suit thickness of insulation.

PART 3 - EXECUTION

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 PRE- INSTALLATION REQUIREMENTS

- .1 Pressure test ductwork systems complete, witness and certify.
- .2 Ensure surfaces are clean, dry, free from foreign material.

3.3 INSTALLATION

- .1 Install in accordance with TIAC National Standards.
 - .2 Apply materials in accordance with manufacturers instructions and as indicated.
 - .3 Use 2 layers with staggered joints when required nominal thickness exceeds 75 mm.
 - .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.
 - .1 Ensure hangers, and supports are outside vapour retarder jacket.
 - .5 Hangers and supports:
 - .1 Apply high compressive strength insulation where insulation may be compressed by weight of ductwork.
 - .6 Fasteners: install at 300 mm on centre in horizontal and vertical directions, minimum 2 rows each side.
-

3.4 DUCTWORK INSULATION SCHEDULE

- .1 Insulation types and thicknesses: conform to following table:

	TIAC Code	Vapour Retarder	Thickness (mm)
Rectangular cold and dual temperature supply air ducts	C-1	yes	50
Round cold and dual temperature supply air ducts	C-2	yes	50
Acoustically lined ducts	none		

3.5 CLEANING

- .1 Clean in accordance with Section 01 00 10 - General Instructions.
- .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

PART 1 - GENERAL

1.1 REFERENCES

- .1 American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE)
- .2 ASTM International
 - .1 ASTM A653/A653M-13, Standard Specification for Steel Sheet, Zinc Coated (Galvanized) or Zinc-Iron Alloy Coated (Galvannealed) by the Hot-Dip Process.
- .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)
 - .1 SMACNA HVAC Duct Construction Standards - Metal and Flexible, 2005.
 - .2 SMACNA HVAC Air Duct Leakage Test Manual, 2012.
 - .3 IAQ Guideline for Occupied Buildings Under Construction 2007.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for metal ducts and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Ontario, Canada.
- .4 Test and Evaluation Reports:
 - .1 Certification of Ratings:
 - .1 Catalogue or published ratings to be those obtained from tests carried out by manufacturer or independent testing agency signifying adherence to codes and standards.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
 - .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
 - .3 Storage and Handling Requirements:
 - .1 Store materials off ground, indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect metal ducts from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
-

PART 2 - PRODUCTS

2.1 SEAL CLASSIFICATION

- .1 Classification as follows:

<u>Maximum Pressure Pa</u>	<u>SMACNA Seal Class</u>
500	C
250	C
125	C
125	Unsealed

- .2 Seal classification:

- .1 Class A: longitudinal seams, transverse joints, duct wall penetrations and connections made airtight with sealant and tape.
- .2 Class B: longitudinal seams, transverse joints and connections made airtight with sealant, tape or combination thereof.
- .3 Class C: transverse joints and connections made air tight with gasket, sealant, tape or combination thereof. Longitudinal seams unsealed.
- .4 Unsealed seams and joints.

2.2 SEALANT

- .1 Sustainability Characteristics:

- .1 Adhesives and sealants: in accordance with Section 07 92 00 - Joint Sealants.

- .2 Sealant: oil resistant, water borne, polymer type flame resistant duct sealant. Temperature range of minus 30 degrees C to plus 93 degrees C.

2.3 TAPE

- .1 Tape: polyvinyl treated, open weave fiberglass tape, 50 mm wide.

2.4 DUCT LEAKAGE

- .1 In accordance with SMACNA HVAC Air Duct Leakage Test Manual.

2.5 FITTINGS

- .1 Fabrication: to SMACNA.

- .2 Radiused elbows:

- .1 Rectangular: standard radius short radius with single thickness turning vanes centreline radius: 1.5 times width of duct.
- .2 Round: smooth radius five piece, centreline radius: 1.5 times diameter.

- .3 Branches:

- .1 Rectangular main and branch: with radius on branch 1.5 times width of duct 45 degrees entry on branch.
- .2 Round main and branch: enter main duct at 45 degrees with conical connection.

- .3 Provide volume control damper in branch duct near connection to main duct.
- .4 Main duct branches: with splitter damper.
- .4 Transitions:
 - .1 Diverging: 20 degrees maximum included angle.
 - .2 Converging: 30 degrees maximum included angle.
- .5 Offsets:
 - .1 Full radiused elbows as indicated.
- .6 Obstruction deflectors: maintain full cross-sectional area.
 - .1 Maximum included angles: as for transitions.

2.6 FIRE STOPPING

- .1 Retaining angles around duct, on both sides of fire separation in accordance with Section 07 84 00 - Fire Stopping.
- .2 Fire stopping material and installation must not distort duct.

2.7 GALVANIZED STEEL

- .1 Lock forming quality: to ASTM A653/A653M, Z90 zinc coating.
- .2 Thickness, fabrication and reinforcement: to ASHRAE & SMACNA.
- .3 Joints: to ASHRAE, SMACNA or proprietary manufactured duct joint. Proprietary manufactured flanged duct joint to be considered to be a class A seal.

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for metal duct installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 GENERAL

- .1 Do work in accordance with ASHRAE & SMACNA as indicated.
 - .2 Do not break continuity of insulation vapour barrier with hangers or rods.
 - .1 Insulate strap hangers 100 mm beyond insulated duct. Ensure diffuser is fully seated.
 - .3 Support risers in accordance with ASHRAE & SMACNA.
-

- .4 Install breakaway joints in ductwork on sides of fire separation.
- .5 Install proprietary manufactured flanged duct joints in accordance with manufacturer's instructions.
- .6 Manufacture duct in lengths and diameter to accommodate installation of acoustic duct lining.

3.3 HANGERS

- .1 Strap hangers: install in accordance with SMACNA.
- .2 Angle hangers: complete with locking nuts and washers.
- .3 Hanger spacing: in accordance with ASHRAE & SMACNA as follows:

<u>Duct Size</u>	<u>Spacing</u>
(mm)	(mm)
to 1500	3000
1501 and over	2500

3.4 SEALING AND TAPING

- .1 Apply sealant in accordance with SMACNA and to manufacturer's recommendations.
- .2 Bed tape in sealant and recoat with minimum of 1 coat of sealant to manufacturers recommendations.

3.5 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 00 10 - General Instructions.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 00 10 - General Instructions.

PART 1 - GENERAL**1.1 REFERENCES**

- .1 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)
 - .1 SMACNA - HVAC Duct Construction Standards - Metal and Flexible, 2005.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for air duct accessories and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate:
 - .1 Flexible connections.
 - .2 Duct access doors.
 - .3 Turning vanes.
 - .4 Instrument test ports.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
 - .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
 - .3 Storage and Handling Requirements:
 - .1 Store materials off ground, indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect air duct accessories from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
 - .4 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding, and packaging materials as specified in Construction Waste Management Plan Waste Reduction Workplan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
-

PART 2 - PRODUCTS**2.1 GENERAL**

- .1 Manufacture in accordance with SMACNA - HVAC Duct Construction Standards.

2.2 FLEXIBLE CONNECTIONS

- .1 Frame: galvanized sheet metal frame 10 mm thick with fabric clenched by means of double locked seams.
- .2 Material:
 - .1 Fire resistant, self extinguishing, neoprene coated glass fabric, temperature rated at minus 40 degrees C to plus 90 degrees C, density of 1.3 kg/m².

2.3 SPIN-IN COLLARS

- .1 Conical galvanized sheet metal spin-in collars with lockable butterfly damper.
- .2 Sheet metal thickness to co-responding round duct standards.

PART 3 - EXECUTION**3.1 EXAMINATION**

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for air duct accessories installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION

- .1 Flexible Connections:
 - .1 Install in following locations:
 - .1 Inlets and outlets to supply air units and fans.
 - .2 Inlets and outlets of exhaust and return air fans.
 - .3 As indicated.
 - .2 Length of connection: 100 mm.
 - .3 Minimum distance between metal parts when system in operation: 75 mm.
 - .4 Install in accordance with recommendations of SMACNA.
 - .5 When fan is running:
 - .1 Ducting on sides of flexible connection to be in alignment.
 - .2 Ensure slack material in flexible connection.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 00 10 - General Instructions.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 00 10 - General Instructions.

PART 1 - GENERAL**1.1 REFERENCES**

- .1 Sheet Metal and Air Conditioning National Association (SMACNA)
 - .1 SMACNA HVAC Duct Construction Standards, Metal and Flexible-2013.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for dampers and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for dampers for incorporation into manual.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
 - .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
 - .3 Storage and Handling Requirements:
 - .1 Store materials off ground, indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect dampers from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
-

PART 2 - PRODUCTS**2.1 GENERAL**

- .1 Manufacture to SMACNA standards.

2.2 SINGLE BLADE DAMPERS

- .1 Fabricate from same material as duct, but one sheet metal thickness heavier. V-groove stiffened.
- .2 Size and configuration to recommendations of SMACNA, except maximum height 100 mm as indicated.
- .3 Locking quadrant with shaft extension to accommodate insulation thickness.
- .4 Inside and outside nylon bronze end bearings.
- .5 Channel frame of same material as adjacent duct, complete with angle stop.

PART 3 - EXECUTION**3.1 EXAMINATION**

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for damper installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION

- .1 Install where indicated.
 - .2 Install in accordance with recommendations of SMACNA and in accordance with manufacturer's instructions.
 - .3 Locate balancing dampers in each branch duct, for supply, return and exhaust systems.
 - .4 Runouts to registers and diffusers: install single blade damper located as close as possible to main ducts.
 - .5 Dampers: vibration free.
 - .6 Ensure damper operators are observable and accessible.
 - .7 Corrections and adjustments conducted by Departmental Representative.
-

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 00 10 - General Instructions.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 00 10 - General Instructions.

PART 1 - GENERAL

1.1 REFERENCES

- .1 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE)
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA (Fire) 90A, Standard for the Installation of Air-Conditioning and Ventilating Systems, 2015 Edition.
 - .2 NFPA (Fire) 90B, Standard for Installation of Warm Air Heating and Air-Conditioning Systems, 2015 Edition.
- .3 Sheet Metal and Air-Conditioning Contractors' National Association (SMACNA)
 - .1 SMACNA HVAC Duct Construction Standards - Metal and Flexible, 2005.
 - .2 SMACNA IAQ Guideline for Occupied Buildings under Construction, 2005.
- .4 Underwriters' Laboratories (UL)
 - .1 UL 181, Standard for Factory-Made Air Ducts and Air Connectors.
- .5 Underwriters' Laboratories of Canada (ULC)
 - .1 CAN/ULC-S110-13, Standard Methods of Tests for Air Ducts.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for flexible ducts and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate:
 - .1 Thermal properties.
 - .2 Friction loss.
 - .3 Acoustical loss.
 - .4 Leakage.
 - .5 Fire rating.
- .3 Test and Evaluation Reports:
 - .1 Catalogue or published ratings to be those obtained from tests carried out by manufacturer or independent testing agency signifying adherence to codes and standards.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials off ground, indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.

- .2 Store and protect flexible ducts from nicks, scratches, and blemishes.
- .3 Replace defective or damaged materials with new.

PART 2 - PRODUCTS

2.1 GENERAL

- .1 Factory fabricated to CAN/ULC-S110.
- .2 Pressure drop coefficients listed below are based on relative sheet metal duct pressure drop coefficient of 1.00.
- .3 Flame spread rating not to exceed 25. Smoke developed rating not to exceed 50.

2.2 METALLIC - INSULATED

- .1 Type 1: spiral wound flexible aluminum with factory applied, 37 mm thick flexible glass fibre thermal insulation with vapour barrier and vinyl jacket, as indicated.
- .2 Performance:
 - .1 Factory tested to 2.5 kPa without leakage.
 - .2 Maximum relative pressure drop coefficient: 3.

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for flexible ducts installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 DUCT INSTALLATION

- .1 Install in accordance with: CAN/ULC-S110, UL 181, NFPA (Fire) 90A, NFPA (Fire) 90B & SMACNA.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 00 10 - General Instructions .
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 00 10 - General Instructions.

PART 1 - GENERAL

1.1 REFERENCES

- .1 ASTM International
 - .1 ASTM C177-13, Standard Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Guarded-Hot-Plate Apparatus.
 - .2 ASTM C423-09a, Standard Test Method for Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method.
 - .3 ASTM C916-14, Standard Specification for Adhesives for Duct Thermal Insulation.
 - .4 ASTM C1071-12, Standard specification for Fibrous Glass Duct Lining Insulation (Thermal and Sound Absorbing Material).
 - .5 ASTM C1338-14, Standard Test Method for Determining Fungi Resistance of Insulation Materials and Facings.
 - .6 ASTM G21-13, Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi.
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA (Fire) 90A, Standard for the Installation of Air Conditioning and Ventilating Systems, 2015 Edition.
 - .2 NFPA (Fire) 90B, Standard for the Installation of Warm Air Heating and Air Conditioning Systems, 2015 Edition.
- .3 North American Insulation Manufacturers Association (NAIMA)
 - .1 NAIMA AH116-2002, Fibrous Glass Duct Construction Standards.
- .4 Sheet Metal and Air Conditioning Contractor's National Association (SMACNA)
 - .1 SMACNA, HVAC Duct Construction Standards, Metal and Flexible-2005.
 - .2 SMACNA IAQ Guideline for Occupied Buildings Under Construction-2007.
- .5 Underwriter's Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-10, Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for duct liners and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
 - .2 Operation and Maintenance Data: submit operation and maintenance data for duct liners for incorporation into manual.
-

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials off ground, indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect duct liners from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.

PART 2 - PRODUCTS

2.1 DUCT LINER

- .1 General:
 - .1 Mineral Fibre duct liner: air surface coated mat facing.
 - .2 Flame spread rating shall not exceed 25. Smoke development rating shall not exceed 50 when tested in accordance with CAN/ULC-S102 and NFPA 90A NFPA 90B.
 - .3 Recycled Content: EcoLogo certified with minimum 35% by weight recycled content.
 - .4 Fungi resistance: to ASTM C1338 & ASTM G21.
- .2 Rigid:
 - .1 Use on flat surfaces where indicated.
 - .2 25 mm thick, to ASTM C1071 Type 2, fibrous glass rigid board duct liner.
 - .3 Density: 48 kg/m³ minimum.
 - .4 Thermal resistance to be minimum 0.76 (m². degrees C)/W for 25 mm thickness when tested in accordance with ASTM C177, at 24 degrees C mean temperature.
 - .5 Maximum velocity on faced air side: 20.3 m/s.
 - .6 Minimum NRC of 0.70 at 25 mm thickness based on Type A mounting to ASTM C423.
 - .7 Recycled Content: EcoLogo certified containing minimum 45% by weight recycled content.
- .3 Flexible:
 - .1 Use on round or oval surfaces surfaces indicated.
 - .2 25 mm thick, to ASTM C1071 Type 1, fibrous glass blanket duct liner.
 - .3 Density: 24 kg/m³ minimum.
 - .4 Thermal resistance to be minimum 0.37 (m².degrees C)/W for 12 mm thickness when tested in accordance with ASTM C177, at 24 degrees C mean temperature.
 - .5 Maximum velocity on coated air side: 25.4 m/s.
 - .6 Minimum NRC of 0.65 at 25 mm thickness based on Type A mounting to ASTM C423.

2.2 ADHESIVE

- .1 Adhesive: to NFPA (Fire) 90A, NFPA (Fire) 90B and ASTM C916.
- .2 Flame spread rating shall not exceed 25. Smoke development rating shall not exceed 50. Temperature range minus 29 degrees C to plus 93 degrees C.

- .3 Water-based fire retardant type.

2.3 FASTENERS

- .1 Weld pins 2.0 mm diameter, length to suit thickness of insulation. Metal retaining clips, 32 mm square.

2.4 JOINT TAPE

- .1 Poly-Vinyl treated open weave fiberglass membrane 50 mm wide.

2.5 SEALER

- .1 Meet requirements of NFPA (Fire) 90A and NFPA (Fire) 90B.
- .2 Flame spread rating shall not exceed 25. Smoke development rating shall not exceed 50. Temperature range minus 68 degrees C to plus 93 degrees C.

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for duct liner installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 GENERAL

- .1 Do work in accordance with SMACNA HVAC Duct Construction Standard, NAIMA AH116 and as indicated except as specified otherwise.
- .2 Line inside of ducts where indicated.
- .3 Duct dimensions, as indicated, are clear inside duct lining.

3.3 DUCT LINER

- .1 Install in accordance with manufacturer's recommendations, and as follows:
 - .1 Fasten to interior sheet metal surface with 100% coverage of adhesive to ASTM C916.
 - .1 Exposed leading edges and transverse joints to be factory coated or coated with adhesive during fabrication.
 - .2 In addition to adhesive, install weld pins not less than 2 rows per surface and not more than 425 mm on centres, to compress duct liner sufficiently to hold it firmly in place.
-

- .2 In systems, where air velocities exceeds 20.3 m/s, install galvanized sheet metal noising to leading edges of duct liner.

3.4 JOINTS

- .1 Seal butt joints, exposed edges, weld pin and clip penetrations and damaged areas of liner with joint tape and sealer. Install joint tape in accordance with manufacturer's written recommendations, and as follows:
 - .1 Bed tape in sealer.
 - .2 Apply 2 coats of sealer over tape.
- .2 Replace damaged areas of liner at discretion of Departmental Representative.
- .3 Protect leading and trailing edges of duct sections with sheet metal nosing having 15 mm overlap and fastened to duct.

3.5 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 00 10 - General Instructions.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 00 10 - General Instructions.

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 23 33 00 - Air Duct Accessories.

1.2 REFERENCES

- .1 Air Movement and Control Association (AMCA)
 - .1 AMCA 99-10, Standards Handbook.
 - .2 AMCA 210-07, Laboratory Methods of Testing Fans for Aerodynamic Performance Rating.
 - .3 AMCA 300-08, Reverberant Room Method for Sound Testing of Fans.
 - .4 AMCA 301-14, Methods for Calculating Fan Sound Ratings from Laboratory Test Data.
- .2 The Master Painters Institute (MPI)
 - .1 Architectural Painting Specification Manual - current edition.
 - .1 MPI #18, Primer, Zinc Rich, Organic.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for HVAC fans and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Ontario, Canada.
 - .2 Provide:
 - .1 Fan performance curves showing point of operation, bhp and efficiency.
 - .2 Sound rating data at point of operation.
 - .3 Indicate:
 - .1 Motors, sheaves, bearings, shaft details.
 - .2 Minimum performance achievable with variable speed controllers and variable inlet vanes as appropriate.

1.4 MAINTENANCE MATERIAL SUBMITTALS

- .1 Extra Materials:
 - .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
 - .1 Furnish list of individual manufacturer's recommended spare parts for equipment, include:
 - .1 Bearings and seals.
 - .2 Addresses of suppliers.
 - .3 List of specialized tools necessary for adjusting, repairing or replacing.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials off ground, indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect HVAC fans from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards in force.
 - .2 Capacity: flow rate, total static pressure, bhp, efficiency, revolutions per minute, power, model, size, sound power data and as indicated on schedule.
 - .3 Fans: statically and dynamically balanced, constructed in conformity with AMCA 99.
 - .4 Sound ratings: comply with AMCA Standard 301, tested to AMCA 300. Supply unit with AMCA certified sound rating seal.
 - .5 Performance ratings: based on tests performed in accordance with AMCA 210. Supply unit with AMCA certified rating seal, except for propeller fans smaller than 300 mm diameter.

2.2 FANS GENERAL

- .1 Motors:
 - .1 Sizes as indicated.
- .2 Factory primed before assembly in colour standard to manufacturer.
- .3 Scroll casing drains: as indicated.
- .4 Flexible connections: to Section 23 33 00 - Air Duct Accessories.

2.3 CENTRIFUGAL FANS

- .1 Fan wheels:
 - .1 Welded steel or aluminum construction.
 - .2 Maximum operating speed of centrifugal fans not more than 40% of first critical speed.
 - .3 Backward inclined blades, as indicated.
 - .2 Bearings: heavy duty grease lubricated ball or roller self aligning type with oil retaining, dust excluding seals and a certified minimum rated life of 100,000 hours.
-

2.4 CABINET FANS - GENERAL PURPOSE

- .1 Fan characteristics and construction: as centrifugal fans.
- .2 Cabinet hung single or multiple wheel with DWDI centrifugal fans in factory fabricated casing complete with vibration isolators and seismic control measures, motor, variable speed controller.
- .3 Fabricate casing of zinc coated or phosphate treated steel reinforced and braced for rigidity. Provide removable panels for access to interior. Paint uncoated, steel parts with corrosion resistant paint to MPI #18. Finish inside and out, over prime coat, with rust resistant enamel. Internally line cabinet with 25 mm thick rigid acoustic insulation, pinned and cemented.
- .4 Solid state speed controller, CSA listed, shipped loose for mounting on wall by electrical trade.

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for HVAC fans installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 FAN INSTALLATION

- .1 Install fans as indicated, complete with resilient mountings, flexible electrical leads and flexible connections in accordance with Section 23 33 00 - Air Duct Accessories.
- .2 Access doors and access panels to be easily accessible.

3.3 ANCHOR BOLTS AND TEMPLATES

- .1 Size anchor bolts to withstand seismic acceleration and velocity forces as specified.

3.4 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 00 10 - General Instructions.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 00 10 - General Instructions.

PART 1 - GENERAL**1.1 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for diffusers, registers and grilles and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate following:
 - .1 Capacity.
 - .2 Throw and terminal velocity.
 - .3 Noise criteria.
 - .4 Pressure drop.
 - .5 Neck velocity.

1.2 MAINTENANCE MATERIAL SUBMITTALS

- .1 Extra Materials:
 - .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
 - .2 Include:
 - .1 Keys for volume control adjustment.
 - .2 Keys for air flow pattern adjustment.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
 - .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
 - .3 Storage and Handling Requirements:
 - .1 Store materials off ground, indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect diffuser, registers and grilles from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
-

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards.

2.2 GENERAL

- .1 Frames:
 - .1 Full perimeter gaskets.
 - .2 Plaster frames where set into plaster or gypsum board and as specified.
 - .3 Concealed fasteners.
- .2 Concealed manual volume control damper operators.
- .3 Colour: standard.

2.3 MANUFACTURED UNITS

- .1 Grilles, registers and diffusers of same generic type, products of one manufacturer.

2.4 RETURN AND EXHAUST GRILLES AND REGISTERS

- .1 Type RG1/TG1: aluminum, 13 x 13 mm egg crate type face bars, size as indicated on drawings, with drywall frame in coffered ceiling tiles. Finish: White.

2.5 DIFFUSERS

- .1 General: volume control dampers with flow straightening devices and gaskets.
 - .2 Type SD-1: existing coffered ceiling diffuser to remain or be relocated.
 - .3 Type SD-2: steel, square type, 300 x 300, having fixed pattern, neck size as indicated on drawings, maximum NC 18, throw of 0.9 m, 1.5 m & 3.0 m at velocities of 0.76 m/s, 0.51 m/s & 0.26 m/s, maximum neck velocity of 2.55 m/s, lay-in mounted. Finish: White.
-

PART 3 - EXECUTION**3.1 EXAMINATION**

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for diffuser, register and grille installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION

- .1 Install in accordance with manufacturers instructions.
- .2 Install with cadmium plated screws in countersunk holes where fastenings are visible.
- .3 Bolt grilles, registers and diffusers, in place, in gymnasium and similar game rooms.
- .4 Provide concealed safety chain on each grille, register and diffuser in gymnasium and similar game rooms and elsewhere as indicated.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 00 10 - General Instructions.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 00 10 - General Instructions.