

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Complete removal of existing wharf in its entirety, as shown on the drawings. All cribwork, including any which may have settled into the harbour bottom, to be completely removed.
 - .2 Removal of the existing timber retaining wall, as shown on the drawings.
 - .3 Remove and salvage the existing navigational light, as shown on the drawings.
 - .4 Saw cutting and removal of existing asphalt pavement, as shown on drawings.
 - .5 Clean-up and removal of existing rip-rap, geotextile, guiderail and posts, and any other miscellaneous debris at the wharf approach area, as shown on the drawings.
 - .6 Remove all electrical within demolition limits and as indicated on the electrical drawings and specifications.

1.2 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.

PART 2 - PRODUCTS

N/A

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with the Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

**PART 3 - EXECUTION
(CONT'D)**

3.2 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place.
- .3 Remove in their entirety all cribwork designated for removal, including any cribwork that may have settled into the harbour bottom.

3.3 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be salvaged for the Departmental Representative or reused on the project, will be property of Contractor and will be removed from site and disposed to satisfaction of Departmental Representative.
- .2 Contractor to dispose of all demolished materials at an approved waste disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.
- .3 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.
- .4 Excavated material and dredging from below water to be transported using watertight dump trucks to an approved waste disposal site.

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.