

PART 1 - GENERAL

- |                                       |    |   |
|---------------------------------------|----|---|
| <u>1.1 SECTION INCLUDES</u>           | .1 | Barriers.   |
|                                       | .2 | Traffic Controls.   |
| <u>1.2 INSTALLATION AND REMOVAL</u>   | .1 | Provide temporary controls in order to execute work expeditiously.  |
|                                       | .2 | Remove from site all such work after use.   |
| <u>1.3 HOARDING</u>                   | .1 | Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m centres. Provide one lockable truck gate. Maintain fence in good repair. |
| <u>1.4 GUARD RAILS AND BARRICADES</u> | .1 | Provide secure, rigid guard rails and barricades around open excavations.   |
|                                       | .2 | Provide barricades along wharf structure when wheelguard is removed.  |
|                                       | .3 | Provide as required by governing authorities.   |
| <u>1.5 ACCESS TO SITE</u>             | .1 | Provide and maintain access to adjacent harbour facilities.   |
| <u>1.6 PUBLIC TRAFFIC FLOW</u>        | .1 | Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public.                             |

- |  |    |   |
|--|----|---|
| <u>1.7 FIRE ROUTES</u>                                 | .1 | Maintain access to property including overhead clearances for use by emergency response vehicles. |
| <u>1.8 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY</u> | .1 | Protect surrounding private and public property from damage during performance of work.           |
|  | .2 | Be responsible for damage incurred.   |