

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 01 51 00, Temporary utilities.
- .2 Section 01 52 00, Construction facilities

1.2 HOARDING

- .1 Erect temporary site enclosures with 1.8 m high steel wire mesh solidly anchored in the ground to the requirements of CSST
- .2 Provide at least one lockable entrance gate conforming to directives. Equip gates with locks and keys.
- .3 Keep the gate to the work site closed.

1.3 GUARD RAILS AND BARRICADES

- .1 Provide secure, rigid guard rails and barricades around Work zone.
- .2 Provide as required by governing authorities and as directed by Departmental Representative.

1.4 SNOW REMOVAL

- .1 For the duration of the contract, during construction, Contractor to proceed to the removal of snow in the areas occupied by the construction. Snow removal in the access road and in the zones beyond the work areas will be provided by Transport Canada.
- .2 The removal and disposal of snow off site must be carried out in compliance with applicable federal, provincial and municipal laws and regulations. Snow cover accumulation or build-up will not be tolerated on the site.

1.5 FIRE ROUTES

- .1 Maintain access to property for use by emergency response vehicles.

1.6 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

1.7 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION