

# Addendum / Addenda

Project Description / Description de projet		
M20 Abatement- 2nd Floor Renovation		
Solicitation No./N° de sollicitation	Project No./N° de projet	W.O. No./N° d'ordre de travail
15-22060	5059	A1-006431-01-01
Departmental Representative / représentant ministériel		Date
Mark O'Connor		August 13, 2015
<b>Notice:</b> This addendum shall form part of the tender documents and all conditions shall apply and be read in conjunction with the original plans and specifications.		<b>Nota:</b> Cet addenda fait partie intégrale des dossiers d'appel; toutes les conditions énoncées doivent être lues et appliquées en conjonction avec les plans et les devis originaux.

- 1 All noisy work, as determined by the Departmental Representative, to be completed afterhours.
- 2 Electrical shutdown by NRC, contractor to verify all devices prior to removal.
- 3 PC350 Partitions at room 232 will be removed prior to this contract.
- 4 Mechanical drawing 5059-SKM1 for reference and location of ductwork to be capped and area of project work posted as part of addendum.
- 5 Pinchin report posted for reference.
- 6 Mechanical removal will be acceptable alternate to chemical removal of floor adhesive, work to take place after hours.
- 7 NRC will provide daily fire alarm bypasses, contractor to protect and temporarily support all heat detectors (approximately 16) and carry certified electrician to repair any troubles that result from project work. Fire alarm to be fully operational everyday prior to leaving construction site.
- 8 Contractor to supply temporary lighting for the project
- 9 Revise section 02 62 00.01 Schedule A- Hazardous Materials Table from "Approximately one hundred (100) ballasts" to "Approximately one hundred and forty (140) ballasts"

End of Addendum