

Amendment 002

1) Questions and Answers:

Q1) Where ladders are to be removed, some rungs appear to be underwater. Do you want these cut out as well?

A1) Ladders indicated to be removal are to be fully removed as noted on Drawing – S-07.

Q2) There is an old boat ramp at Stn 000, can we use this ramp for the duration of the project?

A2) The old boat ramp we believe can be used if required by the Contractor. The City would need to be consulted and approvals obtained by the Contractor for temporarily moving the existing landscaping rocks and/or fencing. Traffic control is to be provide during construction and temporary barriers and warning signs.

Q3) At Stn 430+ to 582+ are we replacing the concrete around the bollards or just leave the pedestal as is?

A3) Drawings specify that the Bollards and Concrete anchorage are to remain.

Q4) Who inspects and how will the scour mat be inspected?

A4) Refer to specification Section 35 31 22, , paragraph 2.2 INSPECTION. The Contractor is required to screed the level the scour protection to the specified grade. The method of inspection will be determined during construction.

2) Unit Price Table- Quantity Change

Scenario D- East and West Pier Works with East and West Scour Protection

DELETE:

| Item | Specification Reference | Class of Labour, Plant or Material | Unit of Measurement | Estimated Quantity EQ | Price per Unit PU | Estimated Total Price EQ x PU GST/HST Extra |
|------|-------------------------|------------------------------------|---------------------|-----------------------|-------------------|--|
| 21 | 32 14 10 | 750 mm Wide Unit Paver Restoration | m | 9 | | |

Solicitation No. - N° de l'invitation
F2930-150020/A
Client Ref. No. - N° de réf. du client
150020

Amd. No. - N° de la modif.
002
File No. - N° du dossier
PWL-5-38047

Buyer ID - Id de l'acheteur
pw1037
CCC No./N° CCC - FMS No./N° VME F2930-

INSERT:

| Item | Specification Reference | Class of Labour, Plant or Material | Unit of Measurement | Estimated Quantity EQ | Price per Unit PU | Estimated Total Price EQ x PU GST/HST Extra |
|------|-------------------------|------------------------------------|---------------------|-----------------------|-------------------|---|
| 21 | 32 14 10 | 750 mm Wide Unit Paver Restoration | m | 39 | | |

3) Spec Reference 03 30 00 Cast in Place Concrete Section 1.2.2

Remove: East Pier concrete deck replacement between Station 0+430.3E and Station 0+522.6E shall be measured by the square metre of concrete deck and shall include all labour materials and equipment necessary to complete the work including expansion and control joints.

Insert: East Pier concrete deck replacement between Station 0+430.3E and Station 0+549.4E shall be measured by the square metre of concrete deck and shall include all labour materials and equipment necessary to complete the work including expansion and control joints.