

Part 1 General

1.1 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for aggregate materials and include product characteristics, performance criteria, physical size, finish and limitations
- .3 Samples:
 - .1 Submit 1 sample.
 - .2 Allow continual sampling by Departmental Representative during production.
 - .3 Provide Departmental Representative with access to source and processed material for sampling.
 - .4 Supply new or clean sample bags or containers according appropriate to aggregate materials.
 - .5 Pay cost of sampling and testing of aggregates which fail to meet specified requirements.

Part 2 Products

2.1 MATERIALS

- .1 Aggregate quality: sound, hard, durable material free from soft, thin, elongated or laminated particles, organic material, clay lumps or minerals, free from adherent coatings and injurious amounts of disintegrated pieces or other deleterious substances.
- .2 Flat and elongated particles of coarse aggregate: to ASTM D 4791.
 - .1 Greatest dimension to exceed 5 times least dimension.
- .3 Fine aggregates satisfying requirements of applicable section to be one, or blend of following:
 - .1 Screenings produced in crushing of quarried rock, boulders, gravel or slag.
 - .2 Reclaimed asphalt pavement.
 - .3 Reclaimed concrete material.
- .4 Coarse aggregates satisfying requirements of applicable section to be one of or blend of following:
 - .1 Crushed rock.
 - .2 Crushed gravel composed of naturally formed particles of stone.
 - .3 Light weight aggregate, including slag and expanded shale.
 - .4 Reclaimed asphalt pavement.
- .5 All utility pipe bedding to be 25 mm minus washed drain rock.

2.2 SOURCE QUALITY CONTROL

- .1 Inform Departmental Representative of proposed source of aggregates and provide access for sampling 2 weeks minimum before starting production.
- .2 If materials from proposed source do not meet, or cannot reasonably be processed to meet, specified requirements, locate alternative source.
- .3 Advise Departmental Representative 2 weeks minimum in advance of proposed change of material source.
- .4 Acceptance of material at source does not preclude future rejection if it fails to conform to requirements specified, lacks uniformity, or if its field performance is found to be unsatisfactory.

Part 3 Execution

3.1 PREPARATION

- .1 Processing:
 - .1 Process aggregate uniformly using methods that prevent contamination, segregation and degradation.
 - .2 Blend aggregates, as required, including reclaimed materials that meet physical requirements of specification is permitted in order to satisfy gradation requirements for material and, percentage of crushed particles, or particle shapes specified.
 - .1 Use methods and equipment approved in writing by Departmental Representative.
 - .2 When operating in stratified deposits use excavation equipment and methods that produce uniform, homogeneous aggregate gradation.
 - .3 Where necessary, screen, crush, wash, classify and process aggregates with suitable equipment to meet requirements.
 - .1 Use only equipment approved in writing by Departmental Representative.
- .4 Stockpiling:
 - .1 Stockpile aggregates on site in locations as indicated unless directed otherwise by Departmental Representative. Do not stockpile on completed pavement surfaces.
 - .2 Stockpile aggregates in sufficient quantities to meet project schedules.
 - .3 Stockpiling sites to be level, well drained, and of adequate bearing capacity and stability to support stockpiled materials and handling equipment.
 - .4 Except where stockpiled on acceptably stabilized areas, provide compacted sand base not less than 300 mm in depth to prevent contamination of aggregate. Stockpile aggregates on ground but do not incorporate bottom 300 mm of pile into Work.
 - .5 Separate different aggregates by strong, full depth bulkheads, or stockpile far enough apart to prevent intermixing.

- .6 Do not use intermixed or contaminated materials. Remove and dispose of rejected materials as directed by Departmental Representative within 48 hours of rejection.
- .7 Stockpile materials in uniform layers of thickness as follows:
 - .1 Maximum 1.5 m for coarse aggregate and base course materials.
 - .2 Maximum 1.5 m for fine aggregate and sub-base materials.
 - .3 Maximum 1.5 m for other materials.
- .8 Uniformly spot-dump aggregates delivered to stockpile in trucks and build up stockpile as specified.
- .9 Do not cone piles or spill material over edges of piles.
- .10 Do not use conveying stackers.
- .11 During winter operations, prevent ice and snow from becoming mixed into stockpile or in material being removed from stockpile.

3.2 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Leave aggregate stockpile site in tidy, well drained condition, free of standing surface water.
- .4 Leave any unused aggregates in neat compact stockpiles as directed by Departmental Representative.

END OF SECTION

Part 1 General

1.1 MEASUREMENT PROCEDURES

- .1 Measure following items in hectares within limits as indicated.
 - .1 Clearing.
 - .2 Grubbing.
 - .3 Close cut clearing.
 - .4 Underbrush clearing.
- .2 Measure clearing isolated trees and grubbing isolated tree stumps as number of isolated trees cleared and number of isolated stumps grubbed.

1.2 DEFINITIONS

- .1 Clearing consists of cutting off trees and brush vegetative growth to not more than specified height above ground and disposing of felled trees, previously uprooted trees and stumps, and surface debris.
- .2 Close-cut clearing consists of cutting off standing trees, brush, scrub, roots, stumps and embedded logs, removing at, or close to, existing grade and disposing of fallen timber and surface debris.
- .3 Clearing isolated trees consists of cutting off to not more than specified height above ground of designated trees, and disposing of felled trees and debris.
- .4 Underbrush clearing consists of removal from treed areas of undergrowth, deadwood, and trees smaller than 50 mm trunk diameter and disposing of fallen timber and surface debris.
- .5 Grubbing consists of excavation and disposal of stumps and roots to not less than specified depth below existing ground surface.

Part 2 Not Used

2.1 NOT USED

Part 3 Execution

3.1 TEMPORARY EROSION AND SEDIMENTATION CONTROL

- .1 Provide temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to requirements of authorities having jurisdiction.
- .2 Inspect, repair, and maintain erosion and sedimentation control measures during construction until permanent vegetation has been established.
- .3 Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.

3.2 PREPARATION

- .1 Inspect site and verify with Departmental Representative, items designated to remain.
- .2 Locate and protect utility lines: preserve in operating condition active utilities traversing site.
 - .1 Notify Departmental Representative immediately of damage to or when unknown existing utility lines are encountered.
 - .2 When utility lines which are to be removed are encountered within area of operations, notify Departmental Representative in ample time to minimize interruption of service.
- .3 Notify utility authorities before starting clearing and grubbing.
- .4 Keep roads and walks free of dirt and debris.

3.3 CLEARING

- .1 Clearing includes felling, trimming, and cutting of trees into sections and satisfactory disposal of trees and other vegetation designated for removal, including downed timber, snags, brush, and rubbish occurring within cleared areas.
- .2 Clear as directed by Departmental Representative, by cutting at height of not more than 300 mm above ground. In areas to be subsequently grubbed, height of stumps left from clearing operations to be not more than 1000 mm above ground surface.
- .3 Cut off branches and cut down trees overhanging area cleared as directed by Departmental Representative.
- .4 Cut off unsound branches on trees designated to remain as directed by Departmental Representative.

3.4 CLOSE CUT CLEARING

- .1 Close cut clearing to ground level to within 100 mm of ground surface.
- .2 Perform close cut clearing by hand so that existing muskeg is not damaged.
- .3 Cut off branches overhanging area cleared as directed by Departmental Representative.
- .4 Cut off unsound branches on trees designated to remain as directed by Departmental Representative.

3.5 ISOLATED TREES

- .1 Cut off isolated trees as directed by Departmental Representative at height of not more than 300 mm above ground surface.
- .2 Grub out isolated tree stumps.
- .3 Prune individual trees as indicated.
- .4 Trim trees designated to be left standing within cleared areas of dead branches 4 cm or more in diameter; and trim branches to heights as indicated.
- .5 Cut limbs and branches to be trimmed close to bole of tree or main branches.
- .6 Paint cuts more than 3 cm in diameter with approved tree wound paint.

3.6 UNDERBRUSH CLEARING

- .1 Clear underbrush from areas as indicated at ground level.

3.7 GRUBBING

- .1 Remove and dispose of roots larger than 7.5 cm in diameter, matted roots, and designated stumps from indicated grubbing areas.
- .2 Grub out stumps and roots to not less than 200 mm below ground surface.
- .3 Grub out visible rock fragments and boulders, greater than 300 mm in greatest dimension, but less than 0.25 m³.
- .4 Fill depressions made by grubbing with suitable material and to make new surface conform with existing adjacent surface of ground.

3.8 REMOVAL AND DISPOSAL

- .1 Remove cleared and grubbed materials off site as indicated by Departmental Representative.
- .2 Remove diseased trees identified by Departmental Representative and dispose of this material to approval of Departmental Representative.

3.9 FINISHED SURFACE

- .1 Leave ground surface in condition suitable for immediate grading operations to approval of Departmental Representative.

3.10 CLEANING

- .1 Proceed in accordance with Section 01 74 11 – Cleaning.
- .2 On completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 MEASUREMENT PROCEDURES

- .1 Work performed under this section will be incidental to work involved in other sections.
- .2 Shoring, bracing, cofferdams, underpinning and de-watering of excavation will not be measured separately for payment.

1.2 DEFINITIONS

- .1 Excavation classes: two classes of excavation will be recognized; common excavation and rock excavation.
 - .1 Rock : solid material in excess of 1.00 m \bar{u} and which cannot be removed by means of heavy duty mechanical excavating equipment with 0.95 to 1.15 m³ bucket. Frozen material not classified as rock.
 - .2 Common excavation: excavation of materials of whatever nature, which are not included under definitions of rock excavation.
- .2 Unclassified excavation: excavation of deposits of whatever character encountered in Work.
- .3 Topsoil:
 - .1 Material capable of supporting good vegetative growth and suitable for use in top dressing, landscaping and seeding.
 - .2 Material reasonably free from subsoil, clay lumps, brush, objectionable weeds, and other litter, and free from cobbles, stumps, roots, and other objectionable material larger than 25 millimeters in any dimension.
- .4 Waste material: excavated material unsuitable for use in Work or surplus to requirements.
- .5 Borrow material: material obtained from locations outside area to be graded, and required for construction of fill areas or for other portions of Work.
- .6 Recycled fill material: material, considered inert, obtained from alternate sources and engineered to meet requirements of fill areas.
- .7 Unsuitable materials:
 - .1 Weak, chemically unstable, and compressible materials.
 - .2 Frost susceptible materials:
 - .1 Fine grained soils with plasticity index less than 10 when tested to ASTM D 4318, and gradation within limits specified when tested to ASTM D 422 and ASTM C 136: Sieve sizes to CAN/CGSB-8.1 CAN/CGSB-8.2.

- .2 Table:

<u>Sieve Designation % Passing</u>	
2.00 mm	100
0.10 mm	45 - 100
0.02 mm	10 - 80
0.005 mm	0 - 45

- .3 Coarse grained soils containing more than 20 % by mass passing 0.075 mm sieve.
- .8 Unshrinkable fill: very weak mixture of cement, concrete aggregates and water that resists settlement when placed in utility trenches, and capable of being readily excavated.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.4 EXISTING CONDITIONS

- .1 Buried services:
 - .1 Before commencing work verify location of buried services on and adjacent to site.
 - .2 Arrange with appropriate authority for relocation of buried services that interfere with execution of work: pay costs of relocating services.
 - .3 Size, depth and location of existing utilities and structures as indicated are for guidance only. Completeness and accuracy are not guaranteed.
 - .4 Prior to beginning excavation Work, notify applicable Departmental Representative, establish location and state of use of buried utilities and structures. Authorities having jurisdiction to clearly mark such locations to prevent disturbance during Work.
 - .5 Confirm locations of buried utilities by careful soil hydrovac methods.
 - .6 Maintain and protect from damage, water, sewer, gas, electric, telephone and other utilities and structures encountered.
 - .7 Where utility lines or structures exist in area of excavation, obtain direction of Departmental Representative before removing or re-routing. Costs for such Work to be incidental.
 - .8 Record location of maintained, re-routed and abandoned underground lines.
 - .9 Confirm locations of recent excavations adjacent to area of excavation.
- .2 Existing buildings and surface features:
 - .1 Conduct, with Departmental Representative condition survey of existing buildings, trees and other plants, lawns, fencing, service poles, wires, rail tracks, pavement, survey bench marks and monuments which may be affected by Work.
 - .2 Protect existing buildings and surface features from damage while Work is in progress. In event of damage, immediately make repair as directed by Departmental Representative.

Part 2 Products

2.1 MATERIALS

- .1 Type 1 and Type 2 fill: properties to Section 31 05 16 - Aggregate Materials and the following requirements:
 - .1 Crushed, pit run or screened stone, gravel or sand.

- .2 Gradations to be within limits specified when tested to ASTM C 136 and ASTM C 117. Sieve sizes to CAN/CGSB-8.1.

Sieve Designation	%Passing	
	<u>Type1</u>	<u>Type2</u>
75 mm	-	100
50 mm	-	-
37.5 mm	-	-
25 mm	100	-
19 mm	75-100	-
12.5 mm	-	-
9.5 mm	50-100	-
4.75 mm	30-70	22-85
2.00 mm	20-45	-
0.425 mm	10-25	5-30
0.180 mm	-	-
<u>0.075 mm</u>	<u>3-8</u>	<u>0-10</u>

- .2 Type 3 fill: selected material from excavation or other sources, approved by Departmental Representative for use intended, unfrozen and free from rocks larger than 75 mm, cinders, ashes, sods, refuse or other deleterious materials.
- .3 All utility pipe bedding to be 25 mm minus washed drain rock.

Part 3 Execution

3.1 TEMPORARY EROSION AND SEDIMENTATION CONTROL

- .1 Provide temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to requirements of authorities having jurisdiction.
- .2 Inspect, repair, and maintain erosion and sedimentation control measures during construction until permanent vegetation has been established.
- .3 Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.

3.2 SITE PREPARATION

- .1 Remove obstructions, ice and snow, from surfaces to be excavated within limits indicated.
- .2 Cut pavement or sidewalk neatly along limits of proposed excavation in order that surface may break evenly and cleanly in accordance with Section 02 41 13 - Selective Site Demolition.

3.3 PREPARATION/ PROTECTION

- .1 Protect existing features in accordance with Section 01 56 00 - Temporary Barriers and Enclosures and applicable local regulations.

- .2 Keep excavations clean, free of standing water, and loose soil.
- .3 Where soil is subject to significant volume change due to change in moisture content, cover and protect to Departmental Representative approval.
- .4 Protect natural and man-made features required to remain undisturbed. Unless otherwise indicated or located in an area to be occupied by new construction, protect existing trees from damage.
- .5 Protect buried services that are required to remain undisturbed.

3.4 STOCKPILING

- .1 Stockpile fill materials in areas designated by Departmental Representative.
 - .1 Stockpile granular materials in manner to prevent segregation.
 - .2 Protect fill materials from contamination.
 - .3 Implement sufficient erosion and sediment control measures to prevent sediment release off construction boundaries and into water bodies.

3.5 COFFERDAMS, SHORING, BRACING AND UNDERPINNING

- .1 Maintain sides and slopes of excavations in safe condition by appropriate methods and in accordance with Section 01 35 29.06 - Health and Safety Requirements.
 - .1 Where conditions are unstable, Departmental Representative to verify and advise methods.
- .2 Construct temporary Works to depths, heights and locations as approved by Departmental Representative.
- .3 During backfill operation:
 - .1 Unless otherwise indicated or directed by Departmental Representative, remove sheeting and shoring from excavations.
 - .2 Do not remove bracing until backfilling has reached respective levels of such bracing.
 - .3 Pull sheeting in increments that will ensure compacted backfill is maintained at elevation at least 500 mm above toe of sheeting.
- .4 When sheeting is required to remain in place, cut off tops at elevations as indicated.
- .5 Upon completion of substructure construction:
 - .1 Remove cofferdams, shoring and bracing.
 - .2 Remove excess materials from site and restore watercourses as indicated by Departmental Representative.

3.6 DEWATERING AND HEAVE PREVENTION

- .1 Keep excavations free of water while Work is in progress.
- .2 Provide for Departmental Representative's approval details of proposed dewatering or heave prevention methods, including dikes, well points, and sheet pile cut-offs.
- .3 Avoid excavation below groundwater table if quick condition or heave is likely to occur.

- .1 Prevent piping or bottom heave of excavations by groundwater lowering, sheet pile cut-offs, or other means.
- .4 Protect open excavations against flooding and damage due to surface run-off.
- .5 Dispose of water in accordance with Section 01 35 43 - Environmental Procedures to approved areas and in a manner not detrimental to public and private property, or portion of Work completed or under construction.
- .1 Provide and maintain temporary drainage ditches and other diversions outside of excavation limits.

3.7 EXCAVATION

- .1 Advise Departmental Representative at least 7 days in advance of excavation operations for initial cross sections to be taken.
- .2 Excavate to lines, grades, elevations and dimensions as directed by Departmental Representative.
- .3 Remove concrete, asphalt, walks and other obstructions encountered during excavation in accordance with Section 02 41 13 - Selective Site Demolition.
- .4 Excavation must not interfere with bearing capacity of adjacent foundations.
- .5 For trench excavation, unless otherwise authorized by Departmental Representative in writing, do not excavate more than 30 m of trench in advance of installation operations and do not leave open more than 15 m at end of day's operation.
- .6 Keep excavated and stockpiled materials safe distance away from edge of trench as directed by Departmental Representative.
- .7 Restrict vehicle operations directly adjacent to open trenches.
- .8 Dispose of surplus and unsuitable excavated material outside of Waterton Lakes National Park.
- .9 Do not obstruct flow of surface drainage or natural watercourses.
- .10 Earth bottoms of excavations to be undisturbed soil, level, free from loose, soft or organic matter.
- .11 Notify Departmental Representative when bottom of excavation is reached.
- .12 Obtain Departmental Representative approval of completed excavation.
- .13 Remove unsuitable material from trench bottom including those that extend below required elevations to extent and depth as directed by Departmental Representative.
- .14 Hand trim, make firm and remove loose material and debris from excavations.
- .1 Where material at bottom of excavation is disturbed, compact foundation soil to density at least equal to undisturbed soil.

3.8 FILL TYPES AND COMPACTION

- .1 Use types of fill as indicated or specified below.
 - .1 Under road pavement, parking lot, sidewalk and other graveled areas, use Type 3 fill material for backfill, compact to 95% of maximum dry density to ASTM D698.

- .2 Under grass and other areas not subject to vehicular traffic, use Type 3 fill for backfill. Compact to 90% of maximum dry density to ASTM D698.

3.9 BEDDING AND SURROUND OF UNDERGROUND SERVICES

- .1 Place and compact granular material for bedding and surround of underground services as indicated and as specified in Section 33 11 16 - Site Water Utility Distribution Piping and Section 33 31 13 - Public Sanitary Utility Sewerage Piping.
- .2 Place bedding and surround material in unfrozen condition.

3.10 BACKFILLING

- .1 Do not proceed with backfilling operations until completion of following:
 - .1 Departmental Representative has inspected and approved installations.
- .2 Areas to be backfilled to be free from debris, snow, ice, water and frozen ground.
- .3 Do not use backfill material which is frozen or contains ice, snow or debris.
- .4 Place backfill material in uniform layers not exceeding 150 mm compacted thickness up to grades indicated. Compact each layer before placing succeeding layer.
- .5 Backfilling around installations:
 - .1 Place bedding and surround material as specified elsewhere.
 - .2 Do not backfill around or over cast-in-place concrete within 24 hours after placing of concrete.
 - .3 Place layers simultaneously on both sides of installed Work to equalize loading.
 - .4 Backfill trenches with Type 3 material.

3.11 RESTORATION

- .1 Upon completion of Work, remove waste materials and debris, trim slopes, and correct defects as directed by Departmental Representative.
- .2 Reinstall lawns to elevation which existed before excavation.
- .3 Reinstall pavements and sidewalks disturbed by excavation to thickness, structure and elevation which existed before excavation.
- .4 Clean and reinstall areas affected by Work as directed by Departmental Representative.
- .5 Protect newly graded areas from traffic and erosion and maintain free of trash or debris.

END OF SECTION