



Public Works and Government Services Canada / Travaux publics et Services gouvernementaux Canada

REAL PROPERTY SERVICES
Western Region
SERVICES IMMOBILIERS
Région de l'ouest

PRELIMINARY
NOT FOR CONSTRUCTION

WATERMAIN DATA

STATION	REF.	INVERT	DESCRIPTION	REMARKS
4+328.9	V102	1283.063	200mm GATE VALVE	
4+331.8	H26	1283.024	HYDRANT #26, VALVE AND TEE	
4+455.6	F103	1281.388	45° BEND	
4+471.2	F104	1281.488	90° BEND	
4+472.2	V103	1281.507	200mm GATE VALVE	
4+472.6	F105	1281.507	150 X 150 X 200 TEE	

NOTES:

1. ALL HOUSES, BATHROOMS AND KITCHEN SHELTER WATER AND SANITARY SERVICES REQUIRE RECONNECTION UNLESS OTHERWISE DIRECTED BY THE DEPARTMENTAL REPRESENTATIVE. THIS SHALL INCLUDE A NEW CURB STOP.

2. ALL WATER INSTALLATIONS SHALL BE IN ACCORDANCE WITH SPECIFICATION SECTION 33 11 16.

3. ALL SANITARY INSTALLATIONS SHALL BE IN ACCORDANCE WITH SPECIFICATION SECTION 33 31 13.

4. HISTORIC FILES SHOW EXISTING WATER AND SANITARY SERVICES ARE LOCATED IN A COMMON TRENCH FOR ALL HOUSES EXCEPT WHERE SANITARY SERVICE SHOWN AND LOT MARKED WITH ⚠ .

5. EXACT LOCATION OF NEW CURB STOPS, HYDRANTS AND HYDRANT VALVES TO BE CONFIRMED IN THE FIELD TO AVOID GAS LINE.

amec foster wheeler

Consultant's Name / Nom de l'expert-conseil

Amec Foster Wheeler
Environment & Infrastructure
469 - 40th Street South
Lethbridge, Alberta CANADA T1J 4M1
Tel. (403) 329-1467
Fax (403) 327-4938

Eng. Stamp / Sceau de l'ingenieur

PROFESSIONAL ENGINEER ALBERTA
BART ZACHER
P. ENG
DATE:

DO NOT SCALE DRAWINGS

Revision/ Revision	Description/Description	Date/Date
5		
4		
3		
2	100% DESIGN COMPLETION	07/13/15
1	75% DESIGN COMPLETION	07/01/15
0	50% DESIGN COMPLETION	05/17/15

Client/client

Parks Canada Agency / L'Agence Parcs Canada
Western and Northern Region / Ouest et Nord du Canada
Canada

Project title/Titre du projet

WATERTON TOWNSITE MUNICIPAL INFRASTRUCTURE UPGRADES PHASE A AND B

WATERTON NATIONAL PARK ALBERTA

Approved by/Approuve par

Designed by/Concept par
B. ZACHER

Drawn by/Dessine par
B. JOHNSON

PWGSC Project Manager/Administrateur de Projets TPSGC
M. BURKE

PWGSC, Architectural and Engineering Resources Manager/ Ressources Architectural et de Directeur d'ingénierie, TPSGC

Client/client
J. LAMBE

Drawing title/Titre du dessin

NEW UTILITIES
EVERGREEN AVENUE
NORTH
PLAN PROFILE
Sta. 4+300 to Sta. 4+600

Project No./No. du projet	Sheet/Feuille	Revision no./ La Révision no.
R.075721.001	C22 OF 41	2

PWGSC – A1 – 841X594

NEW UTILITIES