



PARKS CANADA AGENCY

MERRICKVILLE WEIR REHABILITATION

ADDENDUM NO. 1

August 20, 2015

Prepared by KGS Group



A. Amendments:

1. Concrete removal shall be not less than 200 mm. Removal deeper than 200 mm shall only be allowed if it is necessary to reach sound concrete and shall be agreed with the Consultant prior to the additional concrete removal. Removal of sound concrete beyond 200 mm depth from the original line of the concrete shall not be measured or paid. Please provide the following rates:
 1. Concrete removal beyond 200 mm depth _____ \$ per cu. m.
 2. Concrete replacement for removal beyond 200 mm depth _____ \$ per cu. m.

2. Remove deteriorated concrete from the top of the centre pier, upstream of the upstream edge of the weir deck to a maximum depth of 150 mm below the top of the steel pier nosing liner. Reinststate the concrete to the level of the top of the steel liner with 30 MPa air entrained concrete. Place, compact and finish the concrete to the satisfaction of the consultant.
 1. Item _____\$ Lump Sum