



ADDENDUM A-01
ARCHITECTURE

COWANSVILLE INSTITUTION
MAJOR RENOVATION OF A DETENTION BLOCK

PUBLIC WORKS AND GOVERNMENT SERVICES CANADA

ISSUED FOR TENDER
SEPTEMBER 30th 2015

TPSGC No. R.042138.001
SCC No. 350-4907
PRAA No. 224-A-21179
STANTEC No. 247 P043799

<u>PART 1 - GENERAL</u>	
1.0 Généralités	<p>.1 This Addendum forms part of the contract documents and is effective immediately.</p> <p>.2 Note that all numbers of doors, frames and parts that start with an 'X', this indicates that these are only for the building 8. This note is typical for all items and all documents.</p>
2.0 Technical Specifications	<p>.1 Section 01 35 13 : .1 Remplacer l'article 1.2.1.5 par celui-ci: " tout autre article non décrit aux paragraphes 1) à 4), possédé sans autorisation préalable, et pouvant mettre en danger la sécurité des personnes ou du pénitencier.</p> <p>.2 Section 01 45 00 : .1 Add the following articles to the article 1.10 Mock ups :</p> <p>.8 Before starting the production of steel mechanical shafts (horizontal and vertical) in the cells, build a complete sample of the mechanical steel shafts in two cells one above each other. Include all electromechanical elements, architectural elements, fasteners and all the elements that will permit to make a judgment and for approval by the Departmental Representative before starting mass production. The mock up must comply totally with the plans and specifications.</p> <p>.9 Before starting the production of aluminum windows, build a new type of window N-FEN-1, install it as the requirements of section 085113 for approval by the Departmental Representative before starting mass production. The mock up must comply totally with the plans and specifications.</p> <p>.3 Section 05 50 00 : .1 Replace article 1.1.3 by this article : .3 The Contractor / subcontractor shall provide all materials, equipment, labor and services required for the metal fabrication works, so that the works perfectly fulfill the purposes for which they are intended.</p> <p>.4 Section 08 00 00T (Doors and frames Schedule): .1 The following doors will have : .1 A door elevation of type B; .2 A frame elevation of type A; .3 Will not have a fixed panel above the door; .4 The frame will be filled with cement grout. .2 The doors implicated are: X-1B-18, X-1C-18, X-2B-18, X-2C-19 and X-2D_18. 3. Note that all reference numbers for the doors that start with an 'X', it indicates the building 8 only.</p>
End of addendum A-01	