

PART 1 - GENERAL

1.1 SECTION INCLUDES

- .1 Barriers.
- .2 Traffic Controls.

1.2 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.3 GUARD RAILS AND BARRICADES

- .1 Provide secure, rigid guard rails and barricades around open excavations.
- .2 Provide as required by governing authorities.

1.4 ACCESS TO SITE

- .1 Provide and maintain access roads, crossings, ramps and construct runways as may be required for site access including snow clearing of work areas.

1.5 PUBLIC TRAFFIC FLOW

- .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public.

1.6 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.7 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY

- .1 Protect surrounding private and public property from damage during performance of work.
 - .2 Be responsible for damage incurred.
-

1.8 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule three (3) days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

1.9 MEASUREMENT FOR PAYMENT

- .1 No separate measurement for payment shall be made for items under this section. Include costs incidental in the Lump Sum Amount on the Combined Price Form.

PART 2 - PRODUCTS

Not applicable

PART 3 - EXECUTION

Not applicable