NAME OF LINE	DIMENSIONS	COLOR
LANE LINE – SOLID	LINE WIDTH 150 mm	WHITE OR YELLOW
LANE LINE – BROKEN	3.0 3.0 3.0 LINE WIDTH 150 mm	WHITE
STOP BARS	LINE WIDTH 0.45m VARIES	WHITE

ROAD MARKING PAINTING TABLE

SCALE : N.T.S.



SCALE: 1:250

0m 5m 10m 15m 20m 25m

NOTES:

1. STRAPPING BEHIND SIGN IS TO BE PAINTED THE SAME COLOUR AS THE SIGN.
2. SIGN POSTS TO BE PRESSURE TREATED.
3. SIGNS TO BE INSTALLED ON BACK SLOPE WHENEVER POSSIBLE.
4. FOR LARGER SIGNS, USE MAX. END SPACE OF 45 mm AND MAX. POST SPACING OF 1200 mm WITH 150 x 150 POSTS.
5. SIZE OF SIGN TO BE DETERMINED BY PARKS CANADA
6. SIGN TO BE INSTALLED IN ACCORDANCE WITH "PARKS CANADA EXTERIOR SIGNAGE STANDARDS AND GUIDELINES", LATEST EDITION

WOOD SIGN ASSEMBLY DETAIL (TYP.) 2 C02

SCALE : N.T.S.

Public Works and Government Services Canada / Travaux Publics et Services gouvernementaux Canada

SNC·LAVALIN

SNC·LAVALIN Inc.
Halifax, Nova Scotia, Canada
Member of the SNC·LAVALIN Group



PROVINCE OF NEWFOUNDLAND
PERMIT HOLDER
CLASS "A"
This Permit Allows
SNC-LAVALIN Inc.
To practice Professional Engineering in Newfoundland and Labrador.
Permit No. as issued by PEGNL NO458
which is valid for the year 2015.

REGISTERED PROFESSIONAL ENGINEER
NORMAND D. J. LANDRY III
SIGNATURE
31 March 2015
PERMIT
NEWFOUNDLAND & LABRADOR

revisions		date
C01	ISSUED FOR TENDER	MAR 31 2015

project / projet

NEWMAN SOUND REGISTRATION AREA REDESIGN TERRA NOVA NATIONAL PARK, NL

drawing / dessin

PAVEMENT MARKING AND SIGNAGE PLAN

designed / conçu	A.G.M.
date	2014-03-14
drawn / dessiné	D.P.B.
date	2014-03-14
approved / approuvé	
date	
Tender / Soumission	
PWGSC Project Manager / Administrateur de projets TPSGC	
project number / no. du projet	R.065741.001
drawing no. / no. du dessin	C03

617732-D-C-DWG-0008-01_B01

PWGSC B1 (2004)

E-DRM/GDD-E: # E0225-489732