

PART 1 - GENERAL

1.1 RELATED SECTIONS

- .1 Section 01 74 21 - Construction/Demolition Waste Management and Disposal
- .2 Section 03 10 00 - Concrete Forming and Accessories
- .3 Section 03 20 00 - Concrete Reinforcing
- .4 Section 03 30 00 - Cast-in-Place Concrete
- .5 Section 31 23 33.01 - Excavating, Trenching and Backfilling
- .6 Section 32 12 16 - Asphalt Paving

1.2 REFERENCES

- .1 American Society for Testing and Materials (ASTM)
 - .1 ASTM D 698-12, Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400ft-lbf/ft³) (600kN-m/m³).
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.2-98, Boiled Linseed Oil.
 - .2 CAN/CGSB-3.3-2007, Kerosene.
- .3 Canadian Standards Association (CSA)
 - .1 CAN/CSA-A23.1/A23.2-09, Concrete Materials and Methods of Concrete Construction/Test Methods and Practices for Concrete.

1.3 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate and recycle waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Place materials defined as hazardous or toxic waste in designated containers.
- .3 Ensure emptied containers are sealed and stored safely.

1.4 MEASUREMENT FOR PAYMENT

- .1 Concrete Curb Removal & Disposal: The supply of all material, labour, plant and equipment for the demolition, removal and disposal of the concrete curb, as indicated on the drawings, will be measured by the Lineal Metre (LM) calculated

from actual field measurements.

- .2 Concrete Sidewalk: Supply of all materials, labour, plant and equipment for the installation of reinforced concrete sidewalk, as indicated on the drawings to be measured in Lineal Metres (LM) calculated from actual field measurements. Include incidental to the unit price all costs for granular base, formwork, reinforcing steel, control joints, expansion joints and ramping as required.
- .3 Concrete Curb & Gutter: Supply of all material, labour, plant and equipment for the installation of concrete curb and gutter, as indicated on the drawings, will be measured in Lineal Metres (LM) calculated from actual field measurements. Include incidental to the unit price all costs for granular base, formwork and expansion joints.
- .4 Bollards: The supply of all labour, materials, plant and equipment for the installation of the Bollards, as indicated on the drawings, will be measured by the Each (Ea.) as calculated from actual field measurements.
- .5 Include incidental to the unit price the costs of all excavation, reinforced concrete foundations, hardware, backfilling, compaction and painting.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Concrete mixes and materials: to Section 03 30 00 - Cast-in-Place Concrete.
 - .2 Reinforcing steel: to Section 03 20 00 - Concrete Reinforcing.
 - .3 Joint filler and Curing Compound: to Section 03 30 00 - Cast-in-Place Concrete.
 - .4 Granular base: to Section 31 23 33.01 - Excavating, Trenching and Backfilling.
 - .5 Non-staining mineral type form release agent: chemically active release agents containing compounds that react with free lime to provide water soluble soap.
 - .6 Fill material: to Section 31 23 33.01 - Excavating, Trenching and Backfilling.
 - .7 Boiled linseed oil: to CAN/CGSB-1.2.
 - .8 Kerosene: to CAN/CGSB-3.3.
-

PART 3 - EXECUTION

3.1 GRADE PREPARATION

- .1 Do grade preparation work in accordance with Section 31 23 33.01 - Excavating, Trenching and Backfilling.
- .2 Construct embankments using excavated material free from organic matter or other objectionable materials. Dispose of surplus and unsuitable excavated material off site at approved location.
- .3 When constructing embankment, provide for minimum 0.5 m shoulders, where applicable, outside of neat lines of concrete.
- .4 Place fill in maximum 150 mm layers and compact to at least 100% of maximum density to ASTM D 698.

3.2 GRANULAR BASE

- .1 Obtain Departmental Representative's approval of subgrade before placing granular base.
- .2 Place granular base material to lines, widths, and depths as indicated.
- .3 Compact granular base to at least 100% of maximum density to ASTM D 698.

3.3 CONCRETE

- .1 Obtain Departmental Representative's approval of granular base and reinforcing steel prior to placing concrete.
 - .2 Do concrete work in accordance with Section 03 30 00 - Cast-in-Place Concrete.
 - .3 Immediately after floating, give sidewalk surface uniform broom finish to produce regular corrugations not exceeding 2 mm deep, by drawing broom in direction normal to centre line.
 - .4 Provide edging as indicated with 10 mm radius edging tool.
 - .5 Slip-form pavers equipped with string line system for line and grade control may be used if quality of work acceptable to Departmental Representative can be demonstrated. Hand finish surfaces when directed by Departmental Representative.
-

3.4 TOLERANCES

- .1 Finish surfaces to within 3 mm as measured with 3 m straightedge placed on surface.

3.5 EXPANSION AND CONTRACTION JOINTS

- .1 Install tooled transverse contraction joints after floating, when concrete is stiff, but still plastic, at intervals of 3m for curbs and 1.5 m for sidewalks.
- .2 Install expansion joints as directed by Departmental Representative or at intervals of 6 m.
- .3 When sidewalk is adjacent to curb, make joints of curb, gutters and sidewalk coincide.

3.6 ISOLATION JOINTS

- .1 Install isolation joints around manholes and catch basins and along length adjacent to concrete curbs, catch basins, buildings, or permanent structure.
- .2 Install joint filler in isolation joints in accordance with Section 03 30 00 - Cast-in-Place Concrete or as indicated.
- .3 Seal isolation joints with sealant approved by Departmental Representative.

3.7 CURING

- .1 Cure concrete by adding moisture continuously in accordance with CAN/CSA-A23.1 to exposed finished surfaces for at least one (1) day after placing, or sealing moisture in by curing compound approved by Departmental Representative.
- .2 Where burlap is used for moist curing, place two pre-wetted layers on concrete surface and keep continuously wet during curing period.
- .3 Apply curing compound evenly to form continuous film. In accordance with manufacturer's requirements.

3.8 BACKFILL

- .1 Allow concrete to cure for seven (7) days prior to backfilling.
- .2 Backfill to designated elevations with material approved by Departmental Representative. Compact and shape to required contours as indicated or as

directed by Departmental Representative.

3.9 LINSEED OIL TREATMENT

- .1 After concrete has cured for specified curing time and when surface of concrete is clean and dry, apply two (2) coats of linseed oil mixture uniformly to surfaces of sidewalks, curbs, walks and gutters.
- .2 Linseed oil mixture to consist of 50% boiled linseed oil and 50% mineral spirits by volume.
- .3 Apply treatment when air temperature above 10°C.
- .4 Apply first coat at 135 mL/m².
- .5 Apply second coat at 90 mL/m² when first coat has dried.