

PART 1 - GENERAL

1.1 INSTALLTION AND REMOVAL

- .1 Prepare site plan indicating proposed location and dimensions of area to be fenced and used by Contractor, avenues of ingress/egress to fenced area and details of fence installation.
- .2 Identify areas which have to be gravelled to prevent tracking of mud.
- .3 Indicate use of supplemental or other staging area.
- .4 Provide construction facilities in order to execute work expeditiously.
- .5 Remove from site all such work after use.

1.2 CONTRACTOR'S SITE OFFICE

- .1 Be responsible for and provide own site office, if required, including electricity, heat, lights and telephone. Locate site office as directed by Departmental Representative in consultation with Parks Canada.

1.3 SITE STORAGE/LOADING

- .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .2 Do not load or permit to load any part of Work with weight or force that will endanger Work.

1.4 CONSTRUCTION PARKING

- .1 Parking will be permitted on site provided it does not disrupt performance of Work or inconvenience park user or operations personnel.
 - .2 Provide and maintain adequate access to project site.
 - .3 If authorized to use existing roads for access to project site, maintain such roads for duration of Contract and make good damage resulting from Contractors' use of roads.
-

1.5 EQUIPMENT, TOOL AND MATERIALS STORAGE

- .1 Provide and maintain, in clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in weatherproof sheds on site in manner to cause least interference with work activities.

1.6 SANITARY FACILITIES

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition.

1.7 CONSTRUCTION SIGNS AND NOTICES

- .1 Contractor or sub-contractor advertisement signboards are not permitted on site.
- .2 Only notices of safety or instructions are permitted on site.
- .3 Safety and instruction signs and notices shall be in both official languages. Graphic symbols shall conform to CAN/CSA-Z321-96 (R2001).
- .4 Maintain approved signs and notices in good condition for duration of project and dispose of off site on completion of project or earlier if directed by Departmental Representative.

1.8 PROTECTION AND MAINTENANCE OF TRAFFIC

- .1 Provide access and temporary relocated roads as necessary to maintain traffic, including foot traffic.
 - .2 Maintain and protect traffic on affected roads during construction period except as otherwise specifically directed by Departmental Representative.
 - .3 Provide measures for protection and diversion of traffic, including provision of watch-persons and flag-persons, erection of barricades, placing of lights around
-

and in front of equipment and work, and erection and maintenance of adequate warning, danger, and direction signs

- .4 Protect travelling public from damage to person and property.
- .5 Verify adequacy of existing roads and allowable load limit on these roads. Contractor: responsible for repair of damage to roads caused by construction operations.
- .6 Provide necessary lighting, signs, barricades, and distinctive markings for safe movement of traffic.
- .7 Dust control: adequate to ensure safe operation at all times.
- .8 Lighting: to assure full and clear visibility for full width of haul road and work areas during night work operations.
- .9 Provide snow removal during period of Work if required.

1.9 MEASUREMMENT FOR PAYMENT

- .1 No separate measurement for payment shall be made for items under this section. Include costs for Construction Facilities in the Lump Sum Amount on the Combined Price Form.

PART 2 - PRODUCTS

Not applicable

PART 3 - EXECUTION

Not applicable