
1 GENERAL

1.1 Definitions

- .1 Recycle: Process by which waste and recyclable materials are transformed or collected for purpose of being transferred into new products.
- .2 Recycling: Process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for purpose of using in altered form. Recycling does not include burning, incinerating, or thermally destroying waste.
- .3 Reuse: Repeated use of product in same form but not necessarily for same purpose. Reuse includes:
 - .1 Salvaging reusable materials from re-modelling projects, before demolition stage, for resale, reuse on current project or for storage for use on future projects.
 - .2 Returning reusable items including pallets or unused products to vendors.
- .4 Salvage: Removal of structural and non-structural materials from deconstruction/disassembly projects for purpose of reuse or recycling.
- .5 Separate Condition: Refers to waste sorted into individual types.
- .6 Source Separation: Acts of keeping different types of waste materials separate beginning from first time they became waste.

1.2 Documents

- .1 Maintain at job site, one copy of following documents:
 - .1 Material Source Separation Plan.

1.3 Submittals

- .1 Not required.

1.4 Storage, Handling & Protection

- .1 Store, materials to be reused, recycled and salvaged in locations as directed by Departmental Representative.
- .2 Unless specified otherwise, materials for removal become Contractor's property.
- .3 Protect, stockpile, store and catalogue salvaged items.
- .4 Separate non-salvageable materials from salvaged items. Transport and deliver non-salvageable items to licensed disposal facility.
- .5 Prevent contamination of materials to be salvaged and recycled and handle materials in accordance with requirements for acceptance by designated facilities.
 - .1 On-site source separation is recommended.
 - .2 Remove co-mingled materials to off-site processing facility for separation.

1.5 Disposal of Wastes

- .1 Do not bury rubbish or waste materials.
- .2 Do not dispose of volatile materials, mineral spirits, paint thinner into waterways, storm, or sanitary sewers.
- .3 Remove materials from deconstruction as deconstruction/disassembly Work progresses.

1.6 Use of Site and Facilities

- .1 Execute work with least possible interference or disturbance to normal use of premises.
- .2 Maintain security measures established by existing facility provide temporary security measures approved by Departmental Representative.

1.7 Scheduling

- .1 Coordinate Work with other activities at site to ensure timely and orderly progress of Work.

2 PRODUCTS Not applicable

3 EXECUTION

3.1 Application

- .1 Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.

3.2 Cleaning

- .1 Remove tools and waste materials on completion of Work, and leave work area in clean and orderly condition.
- .2 Clean-up work area as work progresses.
- .3 Source separate materials to be reused/recycled into specified sort areas.

END OF SECTION