

---

**1 GENERAL**

**1.1 Installation and Removal**

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

**1.2 Fire Routes**

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

**1.3 Protection for Off-Site and Public Property**

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for and repair damage incurred.

**1.4 Protection of Building Finishes**

- .1 Provide protection for adjacent building finishes and equipment during performance of Work.
- .2 Provide necessary dust tight screens, covers, and hoardings.
- .3 Be responsible for and repair damage incurred due to lack of or improper protection.

**2 PRODUCTS** not applicable

**3 EXECUTION** not applicable

**END OF SECTION**