
1 GENERAL

1.1 Standards Referred to in this Section

- .1 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-Z321-06, Signs and Symbols for the Occupational Environment.

1.2 Installation and Removal

- .1 Provide construction facilities in order to execute work expeditiously.
- .2 Remove from site all such facilities after completion of Work.

1.3 Scaffolding

- .1 Provide and maintain scaffolding, ramps and ladders.

1.4 Site Storage and Loading

- .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .2 Do not load or permit to load any part of Work with a weight or force that will endanger the Work.

1.5 Construction Parking

- .1 Parking to be confirmed by Departmental Representative.
- .2 Provide and maintain adequate access to project site.

1.6 Security

- .1 Site will be occupied at all times. Refer to Section 01 11 00.

1.7 Offices

- .1 Not required.

1.8 Equipment, Tool and Materials Storage

- .1 Provide and maintain, in a clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.

1.9 Sanitary Facilities

- .1 Existing sanitary facilities may be used by Contractor. Keep area and premises in a clean condition.

1.10 Construction Signage

- .1 No Departmental Representative signage will be posted.
- .2 No other signs or advertisements, other than warning signs, are permitted on site.

2 PRODUCTS not applicable

3 EXECUTION not applicable

END OF SECTION