

PHOTOGRAPHS, A11

C2-1 FREESTANDING CASEGOODS IN THIS PHOTO REMOVED BY OTHERS. REMOVE ALL WALL MOUNTED ACCESSORIES.

C2-2 REMOVE BULKHEADS, VALANCES, RECESSED LIGHTING, WING WALLS WALL MOUNTED ACCESSORIES. LOWER CABINETS REMOVED BY OTHERS.

C2-3 REMOVE BULKHEADS C/W RECESSED LIGHT FIXTURES

C2-4

C2-5 REMOVE ALL WALL MOUNTED CASEWORK, ACCESSORIES, HARDWARE AND PARTITIONS AND FINISHES TO BARE CONCRETE (TYPICAL).

C2-6 CERAMIC SHELVES EMBEDDED IN WALL

C2-7 FREESTANDING CASEGOODS IN THIS PHOTO REMOVED BY OTHERS. REMOVE 81 CERAMIC SHELVES EMBEDDED IN GYPSUM BOARD WALL. SEE DETAIL C2-13

C2-8 REMOVE CASEWORK, WALL MOUNTED METAL ACCESSORIES, BULKHEADS WALL MOUNTED MIRRORS, ALL FINISHES TO BARE CONCRETE.

C2-9 REMOVE WALL MOUNTED CASEWORK, AND WALL MOUNTED METAL ACCESSORIES.

C2-10 DETAIL OF CERAMIC TILE SHELVES EMBEDDED INTO GYPSUM BOARD AND SHOWN IN PHOTO C2-6 AND C2-7 ABOVE. TOTAL QTY.81

C2-11 REMOVE FULL HEIGHT WALL MOUNTED CASEWORK IN THIS PHOTO

C2-12 REMOVE FULL HEIGHT WALL MOUNTED CASEWORK SHOWN IN THIS PHOTO.

C2-13

C2-14 REMOVED GLAZED RECESS DISPLACE CASES.

C2-15 REMOVE WING WALL C/W MIRROR FINISH.

C2-16 REMOVE CASEWORK AND ALL COLUMN COVERS (MIRROR, GYPSUM BOARD, WOOD FINISHES)

C2-17 REMOVE WALL MOUNTED CASEWORK

C2-18 REMOVE WALL MOUNTED CASEWORK AND WOOD COLUMN CLADDING

C2-19 REMOVE WOOD COLUMN CLADDING

C2-20 REMOVE WALL MOUNTED MILLWORK

C2-21 REMOVE WALL MOUNTED MILLWORK AND ACCESSORIES. TYPICAL

C2-22a REMOVE MIRROR CLADDING FROM COLUMN.

C2-22b REMOVE GLASS WALL PANELS AND RAISED PLATFORM

C2-23 REMOVE PLATFORM, BLACK PODIUM AND GLASS WALL PANELS.

C2-24 REMOVE SHORT WING WALL AND 2 BLACK PODIUMS ON EITHER SIDE OF ENTRANCE STAIRS.

C2-25 REMOVE FREESTANDING MILLWORK THIS LOCATION. DISCONNECT ELECTRICAL.

C2-26 REMOVE WALL MOUNTED MIRROR PANELS ACCESSORIES MILLWORK PARTITIONS TYPICAL

C2-27 REMOVE WALL MOUNTED AV BOX, WALL MOUNTED SHELVES, PLYWOOD BACKER BOARDS.

C2-28 SAFE AND SHELVING TO BE REMOVED.

C2-29 SIDE VIEW COMMERCIAL FRIDGE TO BE REMOVED.

C2-30 COMMERCIAL FRIDGE TO BE REMOVED

C2-31 REMOVE EXISTING WOOD FRAME STORAGE UNITS C/W RODS AND SHELVES BRACKETS.

C2-32 REMOVE ALL WALL MOUNTED LIGHT BOXES, FIXTURES, GLASS SHELVING, CABINETS, BRACKETS ACCESSORIES AND BASE.

C2-33 REMOVE ALL WALL MOUNTED LIGHT BOXES, FIXTURES, GLASS SHELVING, CABINETS, BRACKETS ACCESSORIES AND BASE.

C2-34 REMOVE WALL MOUNTED MIRROR, CABINET MILLWORK, SINK AND PLUMBING. SEE MECHANICAL.




PETER J. KINDREE ARCHITECT

79 Hinton Avenue N. Ottawa K1Y 0Z7 (613) 860-1530

NOTES ON PHOTOS A11

PHOTOS ARE SHOWN TO ILLUSTRATE EXTENT OF SPECIALTY ITEMS FOR REMOVAL. ALL FREESTANDING ITEMS SHOWN WILL BE REMOVED BY OTHERS PRIOR TO START OF DEMOLITION WORK UNLESS OTHERWISE INDICATED. ALL FIXTURES, FITTINGS, WALL MOUNTED ACCESSORIES, MILLWORK, LOOSE FURNISHINGS VISIBLE IN PHOTOS, PLANS AND AS NOTED TO BE REMOVED.

C2-X FLOOR LEVEL AND PHOTO NUMBER. ARROW HEAD INDICATES DIRECTION AND LOCATION FROM WHICH THE PHOTO IS TAKEN.



L'ENTREPRENEUR DEVRA VÉRIFIER TOUTES LES DIMENSIONS ET LES CONDITIONS SUR LE CHANTIER ET AVISER SANS DÉLAI LE REPRÉSENTANT DU MINISTÈRE DE TOUTE ANOMALIE.

Contractor to verify all dimensions and conditions on site and immediately notify the departmental representative of all discrepancies.

revisions	description	date
6		
5		
4		
3	ISSUED FOR TENDER	2015/06/30
2	ISSUED FOR 90% REVIEW	2015/06/01
1	ISSUED FOR 66% REVIEW	2015/05/22

A	A
C	B C

project CD HOWE BLDG. LEVELS C2 & C3 DEMOLITION

OTTAWA, ONTARIO

drawing LEVEL C2 SPECIALTY ITEMS REMOVAL FLOOR PLAN

Designed By	PK/DL	Conçu par	
Date	MAY /15	(yyyy/mm/dd)	
Drawn By	LC	Dessiné par	
Date	MAY /15	(yyyy/mm/dd)	
Reviewed By	DL	Examiné par	
Date	MAY /15	(yyyy/mm/dd)	
Approved By	DL	Approuvé par	
Date	MAY /15	(yyyy/mm/dd)	
Tender		Soumission	
Project Manager	STEPHANIE CORMIER	Administrateur de projets	
Project no.		No. du projet	
	R077051.3		
Drawing no.		No. du dessin	
	A11		