

RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works and Government
Services Canada/Réception des
soumissions/Travaux publics et Services
gouvernementaux Canada
The Cambridge Building
3 Queen Street/3, rue Queen
Charlottetown
Prince Edward Island
C1A 4A2

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada
The Cambridge Building
3 Queen Street/3 rue, Queen
PO Box 1268/CP 1268
Charlottetown
Prince Ed
C1A 4A2

Title - Sujet Greenhouse Expansion, Harrington PE	
Solicitation No. - N° de l'invitation ED001-161244/A	Amendment No. - N° modif. 005
Client Reference No. - N° de référence du client R.077468.001	Date 2015-10-19
GETS Reference No. - N° de référence de SEAG PW-\$PWC-021-3706	
File No. - N° de dossier PWC-5-38082 (021)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2015-10-23	Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Donovan, Janine E.	Buyer Id - Id de l'acheteur pwc021
Telephone No. - N° de téléphone (506) 636-5347 ()	FAX No. - N° de FAX (506) 636-4376
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This Solicitation Amendment No. Five (5) is raised to include the following Addendum No. Five (5).

The following Addendum to the tender is effective immediately. This addendum shall form part of the contract documents.

All other terms and conditions remain the same.

Addendum No. 5

1. **REQUEST FOR PROPOSAL DOCUMENT**

1 Category 1 - Design-Build Capability and Experience

Under 1, **REMOVE:**

- a. How the two (2) projects were similar to the Harrington project
- b. How budget, schedule and quality were managed
- h. How requirements of site safety and site security were addressed
- i. How the expansion work was delivered at active business operations
- j. How the work was undertaken in the harsh winter environment

And **REPLACE WITH:**

- a. How the two (2) projects were similar to the Harrington project
- b. How budget, schedule and quality were managed
- c. How requirements of site safety and site security were addressed
- d. How the expansion work was delivered at active business operations
- e. How the work was undertaken in the harsh winter environment

2. GC3 Execution and Control of the Work, REMOVE 3.11 Use of the Work and Cleanup of Site in its entirety and **REPLACE WITH:**

GC3.11 USE OF THE WORK AND CLEANUP OF SITE

- 1) The Contractor shall be responsible for analyzing conditions at the site of the Work and selecting the appropriate design and construction solution for the successful completion of the Work.
- 2) The Contractor shall not load or permit to be loaded any part of the Work or its site with a weight or force that will endanger the safety of the Work.

-
- 3) The Contractor shall maintain the Work and its site in a tidy condition and free from an accumulation of waste material and debris.
 - 4) Before the issue of a Certificate of Substantial Performance, the Contractor shall remove waste material and debris, and all Plant and Material not required for the performance of the remaining work and, unless otherwise stipulated in the Contract documents, shall cause the Work and its site to be clean and suitable for occupancy by Canada.
3. Clarification, as per the Terms of Reference, Appendix C, Section 01 51 00, Clause 1.7, Sub- Clauses 1 and 2, AAFC will provide electricity for tools and lights only. Heating of the addition (ie new space) will be Design-Builder's responsibility and cost.
 4. Replace Terms of Reference, Clause 3.4.4.1.7 and the Sub-Clauses 1, 2, and 3 in their entirety with the following sentence:
'Concrete floors in the addition are to be finished with non-metallic hardener with a clear non-yellowing sealer.'
 5. Add to the Terms of Reference, Clause 1.3.3 the following Sub-Clauses:
'3 There will be no hours of work restricted once the Design-Builder's work forces have been security cleared.
.4 A fence for security purposes, around the work site, will not be required by AAFC but a fence can be installed to meet Health and Safety and/or other Design-Builder requirements.
.5 AAFC will provide snow removal to the work site for purposes of vehicle circulation.'
 6. Add to the Terms of Reference, Clause 1.8.1 the following Sub-Clause:
'2 To facilitate Fall concrete placement, PWGSC anticipates a phased design delivery that would allow security and safety requirements to be addressed in parallel to the foundation and slab design - all of which would be reviewed in advance of the other design-build elements.'
 7. Add to the Terms of Reference, Clause 3.5.1.1.2 the following sentence:
'Should the Design-Builder's Mechanical Engineer determine that it is necessary to move the louvered exhaust on grid 1/D4, then the louvered exhaust could be moved vertically within the present framing with minor changes to the trimmers.'

-
8. Add to the Terms of Reference, Clause 3.6.1.4.1 the following sentence:
' There should be sufficient capacity in the existing electrical panels, in the adjacent Building-80 mezzanine, to meet the electrical requirements of the new addition.'