



ATWATER PEDESTRIAN BRIDGE REHABILITATION WORKS 2015-2016

CLAC-IIF-899-1510-PPSD

PRICE TABLE

ITEM	DESCRIPTION OF WORK	QUANTITY	UNIT	UNIT PRICE	AMOUNT
1	JOBSITE ORGANISATION				
1.1	PHASE I				
1.1.1	Mobilization / Demobilization	1	Lump Sum	\$	\$
1.1.2	Environment preservation	1	Lump Sum	\$	\$
1.1.3	Concrete heating	18	m ³	\$	\$
1.1.4	Working platform & Heated shelter	62	m	\$	\$
	TOTAL SECTION 1.1 :				- \$
1.2	PHASE II				
1.2.1	Mobilization / Demobilization	1	Lump Sum	\$	\$
1.2.2	Environment preservation	1	Lump Sum	\$	\$
1.2.3	Working platform	4	m	\$	\$
	TOTAL SECTION 1.2 :				- \$
	TOTAL SECTION 1 :				- \$
2	DECK REHABILITATION WORK				
2.1	Concrete slab demolition	180	m ²	\$	\$
2.2	Steel cleaning and painting	1	Lump Sum	\$	\$
2.3	HSS 178 x 178 Cross beam reinforcement	12	m	\$	\$
2.4	Steel angle	125	m	\$	\$
2.5	Concrete slab	18	m ³	\$	\$
2.6	Studs	20	Unit	\$	\$
2.7	Drain	8	Unit	\$	\$
	TOTAL SECTION 2 :				- \$
3	PILES WORK				
3.1	Structure support	2	Unit	\$	\$
3.2	Steel Bearing system cleaning and painting	4	Unit	\$	\$
3.3	Base Reconstruction	4	Unit	\$	\$
	TOTAL SECTION 3 :				- \$
4	ABUTMENT REHABILITATION WORK				
4.1	Structure support	2	Unit	\$	\$
4.2	Approach slab demolition	40	m ²	\$	\$
4.3	Excavation and Fill	1	Lump Sum	\$	\$
4.4	Concrete demolition	8	m ³	\$	\$
4.5	Bearing system replacement	4	Unit	\$	\$
4.6	Studs	150	Unit	\$	\$
4.7	Galvanized reinforcement	1200	kg	\$	\$
4.8	Concrete - Abutment and backwall	8	m ³	\$	\$
4.9	Expansion joint	6	m	\$	\$
4.10	Concrete - Approach slab	5	m ³	\$	\$
	SECTION 4 TOTAL :				- \$
	SUBTOTAL				- \$
	<i>TPS (5%)</i>				- \$
	<i>TVQ (9.975%)</i>				- \$
	GRAND TOTAL				- \$