



**RETURN BIDS TO:**  
**RETOURNER LES SOUMISSIONS À:**  
Bid Receiving Public Works & Government  
Services Canada/Réception des soumissions Travaux  
publics et Services gouvernementaux Canada  
1713 Bedford Row  
Halifax, N.S./Halifax,(N.E.)  
B3J 1T3  
Halifax  
Bid Fax: (902) 496-5016

**SOLICITATION AMENDMENT**  
**MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise  
indicated, all other terms and conditions of the Solicitation  
remain the same.

Ce document est par la présente révisé; sauf indication contraire,  
les modalités de l'invitation demeurent les mêmes.

**Comments - Commentaires**

**Vendor/Firm Name and Address**  
**Raison sociale et adresse du**  
**fournisseur/de l'entrepreneur**

**Issuing Office - Bureau de distribution**  
Atlantic Region Acquisitions/Région de l'Atlantique  
Acquisitions  
1713 Bedford Row  
Halifax, N.S./Halifax, (N.E.)  
B3J 3C9  
Halifax  
Nova Scot

<b>Title - Sujet</b> Caribou & Woods Islands Ferry Ramp	
<b>Solicitation No. - N° de l'invitation</b> EB144-161214/A	<b>Amendment No. - N° modif.</b> 002
<b>Client Reference No. - N° de référence du client</b> EB144-16-1214	<b>Date</b> 2015-11-04
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWA-122-5297	
<b>File No. - N° de dossier</b> PWA-5-74100 (122)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2015-11-17</b>	
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Chinye (PWA), Chukwudi	<b>Buyer Id - Id de l'acheteur</b> pwa122
<b>Telephone No. - N° de téléphone</b> (902) 496-5476 ( )	<b>FAX No. - N° de FAX</b> (902) 496-5016
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b>	

**Instructions: See Herein**

**Instructions: Voir aux présentes**

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

PWASolicitation No. - N° de l'invitation

Amd. No. - N° de la modif.

Buyer ID - Id de l'acheteur

EB144-161214/001/PWA

Amd002

pwa122

Client Ref. No. - N° de réf. du client

File No. - N° du dossier

CCC No./N° CCC - FMS No./N° VME

EB144-12-1214

PWA-5-74100

Due to the technical nature of amendment 002, this amendment will be available in English ONLY.

Amendment 002 is raised to answer the following questions:

**Question 1:** As per drawing PEI-M1, there is a side view reference notation (at the top of the drawing) for 2/PEI-M1. It references: B/PEI-M2. However there is no HPU reference shown, nor is there detail as to the location of the HPU.

**Answer to Question 1:** The section is showing the exterior of the control booth.

**Question 2:** Is the HPU located indoors or outdoors?

**Answer to Question 2:** The HPU is located indoors per drawings 2/NS-M1 & 2/PEI-M1

**Question 3:** Expected temperature extremes for that location (indoors or outdoors).

**Answer to Question 3:** 35C summer and 10C winter

**Question 4:** Are there space constraints for the HPU envelope?

**Answer to Question 4:** The intent is to house the new HPU in the space occupied by the existing HPU which is approximately an 882x1530 (34.75"x60.25") footprint. The maximum allowable height of the unit is 2440mm (8').

**Question 5:** What are the expected environmental conditions at each site that the systems have to be designed to, Minimum & Maximum Operating Temperatures?

**Answer to Question 5:** Caribou Extreme Ambient Temperatures: 36.0C in August and -25.0C in December  
Wood Islands Extreme Ambient Temperatures: 34.4C in August and -28.1 in December

**Question 6:** Minimum & Maximum Storage Temperatures

**Answer to Question 6:** Caribou Extreme Ambient Temperatures: 36.0C in August and -32.5C in January  
Wood Islands Extreme Ambient Temperatures: 34.4C in August and -30.5C in January

**Question 7:** In reference to #1 above, if the HPU is not in the control room, will it be subject to icing conditions and, if so, expected levels of precipitation.

**Answer to Question 7:** The HPU is indoors.

**Question 8:** None of the drawings show the width of the ramps. It is difficult to approximate quantity of required hydraulic tubing without such information.

**Answer to Question 8:** The transfer bridge is 9.1m wide, clear between HSS railings, with a 1.030m cantilevered walkway. The bridge (excluding the walkway) is centered between concrete abutments, spaced 11.854m apart, inside face. It should also be noted that the drawings are to scale referencing as-built drawings sheet 1-14 dated Jan. 1993.

All Other Terms and Conditions Remain the Same