



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works & Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
1713 Bedford Row
Halifax, N.S./Halifax,(N.E.)
B3J 1T3
Halifax
Bid Fax: (902) 496-5016

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Atlantic Region Acquisitions/Région de l'Atlantique
Acquisitions
1713 Bedford Row
Halifax, N.S./Halifax, (N.E.)
B3J 3C9
Halifax
Nova Scot

| | |
|---|--|
| Title - Sujet Caribou & Woods Islands Ferry Ramp | |
| Solicitation No. - N° de l'invitation EB144-161214/A | Amendment No. - N° modif. 002 |
| Client Reference No. - N° de référence du client EB144-16-1214 | Date 2015-11-04 |
| GETS Reference No. - N° de référence de SEAG PW-\$PWA-122-5297 | |
| File No. - N° de dossier PWA-5-74100 (122) | CCC No./N° CCC - FMS No./N° VME |
| Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2015-11-17 | |
| Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT | |
| F.O.B. - F.A.B. | |
| Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/> | |
| Address Enquiries to: - Adresser toutes questions à: Chinye (PWA), Chukwudi | Buyer Id - Id de l'acheteur pwa122 |
| Telephone No. - N° de téléphone (902) 496-5476 () | FAX No. - N° de FAX (902) 496-5016 |
| Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: | |

Instructions: See Herein

Instructions: Voir aux présentes

| | |
|--|--|
| Delivery Required - Livraison exigée | Delivery Offered - Livraison proposée |
| Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur | |
| Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur | |
| Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie) | |
| Signature | Date |

PWASolicitation No. - N° de l'invitation

EB144-161214/001/PWA

Client Ref. No. - N° de réf. du client

EB144-12-1214

Amd. No. - N° de la modif.

Amd002

File No. - N° du dossier

PWA-5-74100

Buyer ID - Id de l'acheteur

pwa122

CCC No./N° CCC - FMS No./N° VME

Due to the technical nature of amendment 002, this amendment will be available in English ONLY.

Amendment 002 is raised to answer the following questions:

Question 1: As per drawing PEI-M1, there is a side view reference notation (at the top of the drawing) for 2/PEI-M1. It references: B/PEI-M2. However there is no HPU reference shown, nor is there detail as to the location of the HPU.

Answer to Question 1: The section is showing the exterior of the control booth.

Question 2: Is the HPU located indoors or outdoors?

Answer to Question 2: The HPU is located indoors per drawings 2/NS-M1 & 2/PEI-M1

Question 3: Expected temperature extremes for that location (indoors or outdoors).

Answer to Question 3: 35C summer and 10C winter

Question 4: Are there space constraints for the HPU envelope?

Answer to Question 4: The intent is to house the new HPU in the space occupied by the existing HPU which is approximately an 882x1530 (34.75"x60.25") footprint. The maximum allowable height of the unit is 2440mm (8').

Question 5: What are the expected environmental conditions at each site that the systems have to be designed to, Minimum & Maximum Operating Temperatures?

Answer to Question 5: Caribou Extreme Ambient Temperatures: 36.0C in August and -25.0C in December
Wood Islands Extreme Ambient Temperatures: 34.4C in August and -28.1 in December

Question 6: Minimum & Maximum Storage Temperatures

Answer to Question 6: Caribou Extreme Ambient Temperatures: 36.0C in August and -32.5C in January
Wood Islands Extreme Ambient Temperatures: 34.4C in August and -30.5C in January

Question 7: In reference to #1 above, if the HPU is not in the control room, will it be subject to icing conditions and, if so, expected levels of precipitation.

Answer to Question 7: The HPU is indoors.

Question 8: None of the drawings show the width of the ramps. It is difficult to approximate quantity of required hydraulic tubing without such information.

Answer to Question 8: The transfer bridge is 9.1m wide, clear between HSS railings, with a 1.030m cantilevered walkway. The bridge (excluding the walkway) is centered between concrete abutments, spaced 11.854m apart, inside face. It should also be noted that the drawings are to scale referencing as-built drawings sheet 1-14 dated Jan. 1993.

All Other Terms and Conditions Remain the Same