

**Ross rj Boyle Architect**

11 Weaver Cres.  
Kanata, Ontario K2K 3E1  
Tel. 613-592-1651  
Ross@RossBoyleArchitect.com

**Addendum No. 05**

Page 1 of

Project No.     PTS 3043  
Date:            November 04, 2015

**Project:         Safety Access to Tarmac**

---

The following information supplements the bid documents issued.

This Addendum forms part of the contract documents and is to be read, interpreted, and coordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above-named project to the extent referenced and shall become part thereof. Acknowledge receipt of this Addendum by inserting its number and date on the Tender Form. Failure to do so may subject bidder to disqualification.

---

Addendum Items.

- 5.1     (Q32) Louver in door is 400 mm x 600 mm wide.
- 5.2     (Q33) Specification for door operator:
- 5.3     (Q34) Exterior rolling shutter door is to operate on fire alarm. Existing OH door is not connected on fire alarm is to be used as daily operation.
- 5.4     (Q35) Lazy Boy chairs supply and installation is N.I.C., by others.
- 5.5     (Q36) Work stations supply and installation is N.I.C., by others.
- 5.6     (Q37) Shelving N.I.C., by others.
- 5.7     (Q38) See previous Addendum, there is to be transom above door. Run ceiling same height as top of door frame for a distance of 400 mm horizontally then drop to 2440 mm. Bulkhead is to be made of drywall and finished.
- 5.8     (Q39) See previous addendum 02, item 2.3.
- 5.9     (Q40) See above.

5.10 (Q46) See comment Addendum No. 02 item 2.10, this is the best guide we can provide at this time. Grades are to blend with existing. There is insufficient time to complete a grading plan at this time, so use the guide provided.

**END OF ADDENDUM No. 05**