

# PART 1 - GENERAL

<u>1.1 SECTION INCLUDES</u>	.1	Barriers.
	.2	Traffic Controls.
<u>1.2 INSTALLATION AND REMOVAL</u>	.1	Provide temporary controls in order to execute work expeditiously.
	.2	Remove from site all such work after use.
<u>1.3 HOARDING</u>	.1	Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m centres. Provide one lockable truck gate. Maintain fence in good repair.
<u>1.4 GUARD RAILS AND BARRICARDS</u>	.1	Provide secure, rigid guard rails and barricades around open excavations.
	.2	Provide barricades along wharf structure when wheelguard is removed.
	.3	Provide as required by governing authorities.
<u>1.5 ACCESS TO SITE</u>	.1	Provide and maintain access to adjacent facilities.
<u>1.6 PUBLIC TRAFFIC FLOW</u>	.1	Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public.
<u>1.7 FIRE ROUTES</u>	.1	Maintain access to property including overhead clearances for use by emergency response vehicles.

- |  |    |   |
|--|----|---|
| <u>1.8 PROTECTION FOR<br/>OFF-SITE AND PUBLIC<br/>PROPERTY</u> | .1 | Protect surrounding private and public property from damage during performance of work. |
|  | .2 | Be responsible for damage incurred.   |
- 
- |  |    |  |
|--|----|--|
| <u>1.9 MEASUREMENT FOR<br/>PAYMENT</u> | .1 | No separate measurements for payment shall be made for items under this section. Include costs for Temporary Barriers & Enclosures in the Lump Sum portion of the work on the Bid and Acceptance Form. |
|--|----|--|

## PART 2 - PRODUCTS

2.1 NOT USED

## PART 3 - EXECUTION

3.1 NOT USED