

PWGSC	Excavating, Trenching	Section 31 23 10
Fishway Upgrades	& Backfilling	Page 1
Bishop's Falls, NL		
Job No. R.075582.004		October 2015

PART 1 - GENERAL

- | | |
|------------------------------------|---|
| <u>1.1 RELATED SECTIONS</u> | <ul style="list-style-type: none"> .1 Section 01 35 43 - Environmental Procedures. .2 Section 06 10 00 - Rough Carpentry. |
| <u>1.2 MEASUREMENT FOR PAYMENT</u> | <ul style="list-style-type: none"> .1 No separate payment shall be made for Excavating, Trenching and Backfilling. Include all costs in the unit price item for which Excavating, Trenching and Backfilling is required. If no unit price item exists then include all costs in the Lump Sum Portion of the bid and acceptance form. |
| <u>1.3 REFERENCES</u> | <ul style="list-style-type: none"> .1 American Society for Testing and Materials (ASTM) <ul style="list-style-type: none"> .1 ASTM C117-04, Standard Test Method for Material Finer Than 0.075 mm (No. 200) Sieve in Mineral Aggregates by Washing. .2 ASTM C136-06, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates. .3 ASTM D422-63(2007), Standard Test Method for Particle-Size Analysis of Soils. .4 ASTM D698-07, Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbs/ft³) (600 kN-m/m³). .5 ASTM D4318-05, Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils. .2 Canadian General Standards Board (CGSB) <ul style="list-style-type: none"> .1 CAN/CGSB-8.1-88, Sieves, Testing, Woven Wire, Inch Series. .2 CAN/CGSB-8.2-M88, Sieves, Testing, Woven Wire, Metric. .3 Canadian Standards Association (CSA) <ul style="list-style-type: none"> .1 CAN/CSA-A23.1-04, Concrete Materials and Methods of Concrete Construction. |
| <u>1.4 DEFINITIONS</u> | <ul style="list-style-type: none"> .1 Excavation classes: two classes of excavation will be recognized; common excavation and rock excavation. <ul style="list-style-type: none"> .1 Rock : any solid material in excess of 0.25 m³ and which cannot be removed by means of heavy duty mechanical excavating equipment with 0.95 to 1.15 m³ bucket. Frozen material not classified as rock. .2 Common excavation: excavation of materials of whatever nature, which are not included under definitions of rock excavation. |

- .2 Waste material: excavated material unsuitable for use in Work or surplus to requirements.
 - .3 Borrow material: material obtained from locations outside area to be graded, and required for construction of fill areas or for other portions of Work.
 - .4 Unsuitable materials:
 - .1 Weak and compressible materials under excavated areas.
 - .2 Frost susceptible materials under excavated areas.
 - .3 Frost susceptible materials:
 - .1 Fine grained soils with plasticity index less than 10 when tested to ASTM D4318, and gradation within limits specified when tested to ASTM D422 and ASTM C136: Sieve sizes to CAN/CGSB-8.1.
 - .2 Table

<u>Sieve Designation</u>	<u>% Passing</u>
2.00 mm	100
0.10 mm	45 - 100
0.02 mm	10 - 80
0.005 mm	0 - 45
 - .3 Coarse grained soils containing more than 20% by mass passing 0.075 mm sieve.
- .5 Unshrinkable fill: very weak mixture of Portland cement, concrete aggregates and water that resists settlement when placed in utility trenches, and capable of being readily excavated.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Type 1 fill: to the following requirements:
 - .1 Crushed, pit run or screened stone, gravel or sand.
 - .2 Gradations to be within limits specified when tested to ASTM C 136. Sieve sizes to CAN/CGSB-8.1.
- .2 Type 2 fill: selected material from excavation or other sources, approved by Departmental Representative for use intended, unfrozen and free from rocks larger than 75 mm, cinders, ashes, sods, refuse or other deleterious materials.
- .3 Table

PWGSC	Excavating, Trenching	Section 31 23 10
Fishway Upgrades	& Backfilling	Page 3
Bishop's Falls, NL		
Job No. R.075582.004		October 2015

Sieve Designation	% Passing
	Type 1
101.6 mm	100
50 mm	75-100
4.75 mm	25-55
1.2 mm	10-35
0.3 mm	5-20
0.075 mm	0-12

- .4 Sand bedding: clean, hard, durable sand, gravel or crushed stone, free from shale, clay, friable materials, organic matter and other deleterious substances when tested to ASTM C136-84a and ASTM C117-87 and giving a smooth curve without sharp breaks when plotted on a semi-log grading chart:

ASTM sieve designation	% Passing
9.5 mm	100
4.75 mm	5-100
2.00 mm	30-90
0.075 mm	0-10

PART 3 - EXECUTION

3.1 SITE PREPARATION

- .1 Remove obstructions, ice and snow, from surfaces to be excavated within limits indicated.

3.2 EXCAVATION

- .1 Excavate to lines, grades, elevations and dimensions as indicated.
- .2 Excavation must not interfere with bearing capacity of adjacent foundations.
- .3 Dispose of surplus and unsuitable excavated material in approved location off site.
- .4 Do not obstruct flow of surface drainage.
- .5 Earth bottoms of excavations to be undisturbed soil, level, free from loose, soft or organic matter.
- .6 Notify Departmental Representative when bottom of excavation is reached.
- .7 Obtain Departmental Representative's approval of completed excavation.

PWGSC	Excavating, Trenching	Section 31 23 10
Fishway Upgrades	& Backfilling	Page 4
Bishop's Falls, NL		
Job No. R.075582.004		October 2015

<u>3.3 FILL TYPES AND COMPACTION</u>	.1	Use fill of types as directed by the Departmental Representative.
<u>3.4 BACKFILLING</u>	.1	Do not proceed with backfilling operations until Departmental Representative has inspected and approved installations.
	.2	Areas to be backfilled to be free from debris, snow, ice, water and frozen ground.
	.3	Do not use backfill material which is frozen or contains ice, snow or debris.
	.4	Place backfill material in uniform layers not exceeding 150 mm compacted thickness up to grades indicated. Compact each layer before placing succeeding layer.
	.5	Backfilling around installations.
	.1	Place bedding and surround material as specified elsewhere.
	.2	Do not backfill around or over cast-in-place concrete or repaired concrete within 24 hours after placing of concrete and approval from Departmental Representative.
	.3	Place layers simultaneously on both sides of installed Work to equalize loading. Difference not to exceed 1.0 m.
<u>3.5 DEWATERING</u>	.1	Keep excavation dry at all stages of operation.
	.2	Direct surface drainage away from slopes. Do not allow spillage over embankments.
	.3	See Section 35 00 00 - Dewatering.
<u>3.6 CLEARING</u>	.1	Do not clear any areas or remove any trees, beyond the minimum limits required to accommodate the work. Obtain approval of Departmental Representative for any clearing required.
	.2	In areas of clearing, reinstatement to be carried out following completion of work to leave it in a clean and natural state, free of any dead or cut organic debris.
	.3	See Section 32 01 91 - Tree and Shrub Preservation.

PWGSC	Excavating, Trenching	Section 31 23 10
Fishway Upgrades	& Backfilling	Page 5
Bishop's Falls, NL		
Job No. R.075582.004		October 2015

3.7 RESTORATION

- .1 Upon completion of Work, remove waste materials and debris, trim slopes, and correct defects as directed by Departmental Representative.
- .2 Clean and reinstate areas affected by Work as directed by Departmental Representative.
- .3 Restore site to its normal state prior to excavation.