
PART 1 - GENERAL

- 1.1 Related Work
- .1 Refer to other Specification Sections for related information.
 - .2 Refer to **Section 01 33 00** for Shop Drawing/Submissions requirements.
- 1.2 Reference Standards
- .1 Do concrete formwork and falsework in accordance with CSA standard A23.1-94 (or latest edition), Concrete Materials and Methods of Concrete Construction, except where stricter standards specify otherwise.
 - .2 CSA S269.1-1975 (or latest edition), Falsework for Construction Purposes
- 1.3 Submissions
- .1 Shop Drawings:
 - .1 Upon request, submit to Departmental representative for review four (4) sets of formwork and falsework shop drawings, in accordance with **Section 01 33 00**, at least four (4) weeks prior to erection. All such drawings to be stamped and signed by a Professional Engineer registered in the Province of Nova Scotia.
 - .2 Clearly indicate method and schedule of construction, materials, arrangement of joints, ties, shores, liners, and locations of temporary embedded parts. Comply with CSA S269.1 for falsework drawings.
 - .2 Product Data/Samples:
 - .1 Provide product data and samples for form ties.
 - .3 Provide submissions in accordance with **Section 01 33 00**.
- 1.4 Measurement for Payment
- .1 This item will not be measured separately.

PART 2 - PRODUCTS

- 2.1 Materials
- .1 Formwork lumber: plywood and wood formwork materials to CSA A23.1
 - .2 Falsework materials: to CSA S269.1
 - .3 Form stripping agent: colourless mineral oil, free of kerosene, with viscosity between 70 and 110 s Saybolt Universal, 15 to 14 mm²/s at 40DC, flash-point minimum 150DC, open cup.
 - .4 Form ties: removable or snap-off metal ties, fixed or adjustable length, free of devices leaving holes larger than 25 mm diameter in concrete surface. When forms are removed, no metal will be less than 50 mm from the surface of the concrete.

PART 3 - EXECUTION

- 3.1 Erection
- .1 Verify lines and levels before proceeding with formwork and ensure dimensions agree with drawings.
 - .2 Construct forms to produce finished concrete conforming to shape, dimensions, locations and levels indicated within tolerances required by CSA A23.1
 - .3 Line forms with material only as approved by Departmental representative.
 - .4 Construct falsework in accordance with CSA S269.1
 - .5 Align form joints and make watertight. Keep form joints to minimum.
 - .6 Use 25 mm chamfer strips on external corners.
 - .7 Clean formwork in accordance with CSA A23.1, before placing concrete.
 - .8 Leave formwork in place for at least [seven] days, exclusive for days when temperature

Concrete Formwork and Falsework

Page 3

falls below 5NC, unless otherwise directed by
Departmental representative.

- .9 Reuse of formwork and falsework subject to
requirements of CSA A23.1
- .10 All holes from form ties and rods to be
plugged with mortar to requirements of CSA
A23.1. When forms are removed, no metal will
be less than 25 mm from the surface of the
concrete.

PART 1 - GENERAL

- 1.1 Related Work
- .1 Refer to other Specification Sections for related information.
 - .2 Refer to **Section 01 33 00** for Shop Drawing/Submission requirements.
- 1.2 Reference Standards
- .1 Do concrete reinforcement work in accordance with CSA standard A23.1-94 (or latest edition), Concrete Materials and Methods of Concrete Construction, except where stricter standards specify otherwise.
 - .2 Reinforcing Steel Manual of Standard Practice (Second Edition - 1995) (or latest edition) by Reinforcing Steel Institute of Ontario.
 - .3 CSA G30.18 (or latest edition), Billet-Steel Bars for Concrete Reinforcement.
 - .4 CSA G30.3-M1983 (R1991) (or latest edition), Cold-Drawn Steel Wire for Concrete Reinforcement.
- 1.3 Source Sampling
- .1 Upon request, provide Departmental representative with certified copy of mill test of steel supplied showing physical and chemical analysis not less than [2] weeks prior to commencement of work.
- 1.4 Submissions
- .1 Shop Drawings:
 - .1 Clearly indicate bar sizes, spacing, location and quantities of reinforcement, mesh, chairs, spacers and hangers with identifying code marks to permit correct placement without reference to structural drawings; to Reinforcing Steel Manual of Standard Practice.
 - .2 Detail placement of reinforcing where special conditions occur.
 - .3 Design and detail lap lengths and bar development lengths to CSA standard

Concrete Reinforcement

Page 2

A23.1, unless otherwise specified on drawings.

.2 Product Data/Samples:

.1 Provide product data for supports and spacers.

.3 Test Results:

.1 Provide Mill Test Certificates cross referenced to the product supplied to the site.

.4 Provide submissions in accordance with **Section 01 33 00.**

1.5 Storage

.1 Store reinforcing steel on racks or sills that will permit easy access for identification and handling and prevent it from becoming coated with material which would adversely affect bond.

.2 Do not store reinforcing steel in direct contact with the ground.

1.6 Measurement for Payment

.1 This item will not be measured separately.

.2 Wire ties and spacers to be considered incidental to supply and placing of reinforcement.

PART 2 - PRODUCTS

2.1 Materials

.1 Reinforcing steel: to CSA G30.18; billet steel grade 400 deformed bars.

.2 Wire ties: to CSA G30.3 plain, cold drawn annealed steel wire.

.3 Spacers: PVC, Fabricated to suit site dimensions.

.4 Polypropylene Fibres to be suited for marine applications. Contractor to submit product specifications for approval by Departmental representative.

Concrete Reinforcement

Page 3

2.2 Reinforcing Steel
Fabrication

- .1 Fabricate reinforcing to CSA standard A23.1
- .2 Fabrication tolerances for reinforcing steel to Reinforcing Steel Manual of Standard Practice.
- .3 Obtain Departmental representative's acceptance for locations of reinforcement splices other than shown on steel placing drawings.
- .4 Ship bundles of bar reinforcement, clearly identified in accordance with bar list.
- .5 Do not weld reinforcing steel.

PART 3 - EXECUTION

3.1 Placing

- .1 Accurately place reinforcing in positions indicated and hold firmly during placing, compacting and setting of concrete.
- .2 Tie reinforcement where spacing in each direction is:
 - .1 Less than 300 mm: - tie at alternate intersections.
 - .2 300 mm or more: - tie at each intersection.

3.2 Field Bending

- .1 Do not field bend reinforcement except where indicated or authorized by Departmental representative.
- .2 When authorized, bend reinforcement without heat, by applying slow and steady pressure.
- .3 Replace bars which develop cracks or splits.

3.3 Cleaning

- .1 Clean reinforcing before placing concrete.

3.4 Inspection

- .1 Do not place concrete until Departmental representative has inspected and accepted reinforcement work in place.

Concrete Reinforcement

Page 4

-
- 3.5 Surface Conditions .1 Reinforcement, at time concrete is placed, to be free from mud, oil or other non-metallic coatings that adversely affect bonding capacity.
- .2 Reinforcement, with rust, mill scale, or combination of both to be considered as satisfactory, provided minimum dimensions, including height of deformations, and mass of hand wire brushed test specimen are not less than specified requirements in applicable CSA Standards.

Cast-in-Place Concrete

Page 1

PART 1 - GENERAL

1.1 Related Work

- .1 Refer to other Specification Sections for related information on aggregates, form work and false work, concrete reinforcement, underwater concrete, paint, miscellaneous items.
- .2 Refer to **Section 01 33 00** for Shop Drawing/Submissions requirements.

1.2 Reference Standards

- .1 Do structural concrete work in accordance with CSA A23.1-94 (or latest edition), Concrete Materials and Methods of Concrete Construction, except where stricter standards specify otherwise.
- .2 CAN/CSA-A5/A8/A362-93 (or latest edition), Portland Cement/ Masonry Cement/ Blended Hydraulic Cement.
- .3 CSA A23.5-M86 (R1992) (or latest edition), Supplementary Cementing Materials.
- .4 ASTM C494-92 (or latest edition), Chemical Admixtures for Concrete.

1.3 Submissions

- .1 Shop Drawings:
 - .1 Upon request, submit shop drawings and erection drawings for formwork and falsework. All such drawings to be stamped and signed by a Professional Departmental representative registered in the Province of Nova Scotia.
 - .2 Upon request, submit placement drawings for reinforcing steel.
 - .3 Upon request, submit placement drawings for miscellaneous items.
- .2 Product Data/Samples:
 - .1 Provide technical data and/or samples for curing compounds (winter/ summer /green /white /red), evaporation

Cast-in-Place Concrete

Page 2

retardant and finishing aids, expansion joint materials/sealants, grouts.

.3 Certificates:

.1 Minimum four weeks prior to starting concrete work submit to Departmental representative manufacturer's test data and certification by qualified independent inspection and testing laboratory that the following materials will meet specified requirements:

- .1 Portland cement.
- .2 Admixtures.

.2 Provide certification that plant, equipment, and materials to be used in concrete work comply with requirements of CSA A23.1

.3 Provide certification that mix proportions selected will produce concrete of specified quality and yield and that strength will comply with CSA A23.1

.4 Provide certification that concrete will not include alkali reactivity aggregates.

.4 Methodology:

- .1 Submit methodology for cold weather concreting.
- .2 Submit methodology for hot weather concreting.
- .3 Submit methodology for concrete placement operations.
- .4 Submit methodology for concrete deck finishing operations.
- .5 Submit methodology for supporting reinforcing steel.

.5 Test Results:

- .1 Provide design mix tests results.

Cast-in-Place Concrete

Page 3

-
- | | | |
|--------------------------------------|----|---|
| | .2 | Provide mill test certificates for reinforcing steel. |
| 1.4 <u>Storage of Materials</u> | .1 | Store all materials to prevent contamination or deterioration, whether at the plant or at the job site. |
| | .2 | Store cement in watertight bins or silos that provide protection from dampness and easy access for inspection and identification of each shipment whether at the plant or at the job site. |
| | .3 | Prevent stored liquid admixtures and compounds from freezing and powdered admixtures and compounds from absorbing moisture. |
| 1.5 <u>Source Sampling</u> | .1 | At least 4 weeks prior to commencing work, inform Departmental representative of proposed source of aggregates and provide access for sampling. |
| 1.6 <u>Ready-Mix Concrete Supply</u> | .1 | Provide, with each load of concrete delivered to site, duplicate delivery slips containing following:

1. Name of ready-mix batch plant.
2. Serial number of ticket.
3. Date and truck number.
4. Project identification.
5. Class of concrete or mix.
6. Amount of concrete in cubic metres.
7. Time of loading or first mixing of aggregate, cement and water.
8. Time of discharge of concrete.
9. Admixtures added at plant.
10. Amount of water added at plant. |
| 1.7 <u>Measurement for Payment</u> | .1 | Heating of water and aggregates and providing cold weather protection will not be measured but considered incidental to work. |
-

Cast-in-Place Concrete

Page 4

- .2 Cooling of concrete and providing hot weather protection will not be measured but considered incidental to work.
- .3 Supply of anchor bolts, washers and nuts will not be measured but considered incidental to work. Bolt grouting will be considered incidental to the work.
- .4 Supply and installation of rigid PVC sleeves, expansion joints/sealants and curing compounds, or other compounds will be considered incidental to the work.
- .5 Concrete work will be measured in accordance with **Section 01 29 00.**

PART 2 - PRODUCTS

2.1 Materials

- .1 Aggregates: to CSA A23.1, for Class "C-1" exposure.
- .2 Portland Cement: to CSA A5, normal type 10.
- .3 Water: to CSA A23.1
- .4 Admixtures:
 - .1 Air entraining admixtures: to CSA A23.5
 - .2 Chemical admixtures: to CSA A23.5 and ASTM C494
 - .3 Pozzolanic mineral admixtures: to CSA A23.5
- .5 Non-shrink grout: premixed compound consisting of non-metallic aggregate, Portland cement, water reducing and plasticizing agents, of pouring consistency, capable of developing compressive strength of 50 MPa at 28 days.
- .6 Curing compound: To ASTM-C309-M81 and CSA A23.1-M94 (or latest editions) type 1, 1D, or 2.
- .7 Premoulded joint fillers:

Cast-in-Place Concrete

Page 5

-
- .1 Bituminous impregnated fibre board: to ASTM D1751 (latest edition), non-extruding resilient type.
 - .8 Joint sealer: self levelling, two component sealant capable of remaining resilient over temperatures ranging from - 25° C to 35° C. Material will be capable of an elongation of 300%, have tensile recovery of 90% ASTM D412-75 (or latest edition), hardness of 25-35 Shore A and have a high bond strength to the concrete faces.
- 2.2 Concrete Mixes
- .1 Prior to starting concrete work, submit to the Departmental representative the proposed mix design(s) for approval. Mix design(s) to be in accordance with Alternative 1 of Table 11 in CSA A23.1-94 (or latest edition). Comply with additional requirements of CSA A23.1-94 (or latest edition), **Section 15** for concrete placed near sea water.
 - .1 Use concrete mix designed to produce air entrained concrete meeting the following requirements:
 - .2 Cement to be normal Portland cement, Type 10.
 - .3 Minimum compressive strength at 28 days: 35 MPA.
 - .4 Exposure: Class C-1.
 - .5 Maximum aggregate size to CSA A23.1-M94 (or latest edition) table 2, Group 1, 20 mm sieve size.
 - .6 Minimum cement content 390 kg/m³.
 - .7 Air content: 6 to 8%.
 - .8 Maximum water/cement ratio to be 0.40.
 - .9 Slump at time and point of discharge 20 to 80 mm. Where the nature of the work requires larger slumps, they are to be obtained by the use of admixtures rather than increasing the water content. The use of such admixtures and the increase in slump to be approved by the Departmental representative prior to implementation in the work.
 - .10 Modify concrete mix to the approval of the Departmental representative to accommodate pumping.

Cast-in-Place Concrete

Page 6

-
- .11 Admixtures to the approval of the Departmental representative and the recommendation of the manufacturer. Admixtures must be dispersed separately into mixing water.
 - .2 Fibre reinforced concrete mix design outlined under Section 03 37 26.
 - .3 Do not use calcium chloride or compounds containing calcium chloride.
 - .4 Weigh aggregates, cement, water and admixtures separately when batching. Inspect and test scales for accuracy as directed. Accuracy to be such that successive quantities can be measured to within one percent of desired amounts. Test certificates to be submitted to Departmental representative upon request.
 - .5 Where seven day strength is less than 70% of specified 28 day strength, provide additional protection curing and make changes to mix proportions to the satisfaction of the Departmental representative.
 - .6 Provide certification that plant, equipment and all materials to be used in concrete comply with the requirements of CSA A23.1-94 (or latest edition).
 - .7 Provide certification from independent testing and inspection company that mix proportions selected will produce concrete of specified quality and can be effectively placed and finished for all work under this contract.

PART 3 - EXECUTION

3.1 General

- .1 Obtain Departmental representative's approval before placing concrete. Provide 24 hours notice of intended placement.

Cast-in-Place Concrete

Page 7

-
- .2 Place, consolidate, finish, cure and protect concrete to CSA A23.1-94 (or latest edition) except where specified otherwise.
 - .3 Prior to placing of concrete, obtain Departmental representative's approval of proposed method for protection of concrete during placing and curing in adverse weather.
 - .4 Comply with additional requirements of CSA A23.1-94 (or latest edition) Section 15 except where specified otherwise, for concrete exposed to seawater environment.
 - .5 Do not commence placing concrete until Departmental representative has inspected/reviewed forms, inserts, dowels, reinforcing steel, joints; conveying, spreading, consolidation, finishing, curing and protective methods.
 - .6 Ensure that reinforcement and anchorage are not disturbed during placing.
 - .7 Maintain accurate records of placed concrete items to indicate date, location of pour, quality, air temperature and test samples taken.
 - .8 Do not place load(s) upon new concrete until Departmental representative is satisfied that the Contractor has carried out all calculations and tests necessary to confirm that the load(s) will not cause damage or create a safety hazard. Calculations and tests to be stamped by a Professional Departmental representative registered in the Province of Nova Scotia.
 - .9 Comply with additional requirements of CSA A23.1-94 (or latest edition), Clause 15, for concrete exposed to seawater environments during placement and curing.

3.2 Reinforcing Steel

- .1 Place new reinforcing steel according to **Section 03 20 00.**

Cast-in-Place Concrete

Page 8

-
- | | | |
|--|----|---|
| | .2 | Provide 75 mm minimum cover for all reinforcing steel unless indicated otherwise on drawings. |
|--|----|---|
-
- | | | | |
|-----|-----------------|----|---|
| 3.3 | <u>Formwork</u> | .1 | Verify field dimensions to determine applicable sizes of formwork. |
| | | .2 | Design and construct form work to allow adequately for proper placement and consolidation while conforming with shape and dimensions shown on plans. |
| | | .3 | Formwork design will include closures at both top and bottom of form, and all necessary hardware to support the forms. |
| | | .4 | Upon request, submit drawings for review by the Departmental representative, at least 3 weeks before placement of concrete. Drawings, will show formwork details and illustrate dimensions, method of placing of concrete, connections and support. |
| | | .5 | Strip formwork after minimum [5] days. This condition might be waived only if an alternative method to curing and preventing alternate wetting and drying is provided, to the satisfaction of the Departmental representative. This condition will be waived if the forms are left permanently in place, where approved by the Departmental representative. |
-
- | | | | |
|-----|------------------------------|----|---|
| 3.4 | <u>Placement of Concrete</u> | .1 | Place and consolidate concrete to CSA A23.1-94 (or latest edition). |
| | | .2 | If allowed by Departmental representative, pump concrete to following requirements: |
| | | .1 | Arrange equipment so that no vibrations result which might damage freshly placed concrete. |
| | | .2 | Where concrete is conveyed and placed by mechanically applied pressure, provide suitable equipment. |
| | | .3 | Operate pump so that concrete, without air pockets, is produced. |
-

Cast-in-Place Concrete

Page 9

-
- .4 When pumping is discontinued and concrete remaining in pipe line is to be used, void pipe line in a manner that prevents contamination of concrete or separation of ingredients.
 - .3 Concrete will be deposited in all cases as neatly as practicable, directly in its final position, and will not be caused to flow in a manner to permit or cause segregation.
 - .4 Each layer of concrete will be vibrated and tamped with an appropriate vibrator as allowed by the Departmental representative. The concrete must be compacted to the maximum practicable density, free of air pockets, and until it is in complete contact with the reinforcement and formwork.
- 3.5 Inserts
- .1 Set galvanized sleeves and other inserts and openings as indicated or specified elsewhere. Sleeves and openings greater than 100 x 100 mm not indicated on drawings must be approved by Departmental representative.
 - .2 Do not eliminate or displace reinforcement to accommodate hardware. If inserts cannot be located as specified, obtain approval of all modifications from Departmental representative before placing of concrete.
 - .3 Galvanized items embedded in concrete will be completely separated from reinforcing steel.
 - .4 Anchor bolts:
 - .1 Set anchor bolts to templates under supervision of appropriate trade prior to placing concrete.
 - .2 With Departmental representative's concurrence, grout anchor bolts in pre-formed holes or holes drilled after concrete has set. Formed holes to be at least 100 mm in diameter. Drilled holes to be minimum 25 mm larger in diameter than bolts used.
 - .3 Protect anchor bolt holes from water accumulations.

Cast-in-Place Concrete

Page 10

3.6 Protection and
Curing

- .4 Set bolts and fill holes with non-shrink grout.
 - .5 Anchor bolts for base plates will be set to allow at least 25 mm of grout under the base plates.
-
- .1 Provide protection and curing in accordance with CSA A23.1
 - .2 Protect concrete with windproof shelter to allow free circulation of inside air around fresh concrete. Do not let walls of shelter touch formwork and provide sufficient space for removal of formwork.
 - .3 Supply approved heating equipment to maintain inside air at following temperatures:
 - .1 For an initial three days, at not less than 10° C nor more than 25° C at surfaces.
 - .2 At not less than 10° C for an additional 4 consecutive days or for the time necessary to attain 70% of the specified 28-day compressive strength of the concrete.
 - .3 Reduce temperature near end of curing period at rate not exceeding 20° C per day.
 - .4 Do not overheat.
 - .4 Keep concrete surfaces continuously moist during protection stage and allow concrete to dry before removal of protection.
 - .5 Freshly deposited concrete will be protected from premature drying and excessively hot and cold temperatures, will be maintained without drying at a relatively constant temperature for the period of time necessary for hydration of the cement and proper hardening of the concrete. It will be protected from harmful effects of sunshine, drying winds, cold weather, running or surface water and mechanical shock.

Cast-in-Place Concrete

Page 11

-
- .6 Wood floating, broom finishing, placing of burlap and inspection of concrete to be done from transverse bridges of rigid construction free from wobbles and springing under use, unless other methods have been submitted and accepted.
- 3.7 Finishing
- .1 Finish concrete in accordance with CSA A23.1-94 (or latest edition).
- .2 Grind off fins, nibs and other raised protuberances with an approved hand stone.
- .3 When concrete has hardened sufficiently, give deck surface a uniform finish free from porous spots, irregularities, depressions, small pockets or rough spots using a float.
- .4 Following use of a float, provide coarse broom finish using stiff, coarse, fibre broom. Use broom to produce transverse ridges satisfactory to Departmental representative. Brooming will be delayed until concrete is sufficiently hard to retain ridges.
- .5 Rub exposed sharp edges of concrete with carborundum to produce 3 mm radius edges unless otherwise detailed.
- 3.8 Joint Fillers
- .1 Furnish filler for each joint in single piece for depth and width required for joint, unless otherwise authorized by Departmental representative. When more than one piece is required for a joint, fasten abutting ends and hold securely to shape by stapling or other positive fastening.
- .2 Locate and form separation joint as indicated. Install joint filler.
- .3 Unless indicated otherwise, use 13 mm thick joint filler to separate deck slabs and extend joint filler from bottom of slab to within 13 mm of finished concrete surface.

Cast-in-Place Concrete

Page 12

-
- 3.9 Field
Quality Control
- .1 Inspection and testing of concrete and concrete materials will be carried out by Testing Laboratory designated by the Departmental representative in accordance with CSA A23.1-94 (or latest edition).
 - .2 Departmental representative will pay for costs of tests as specified in **Section 01 45 00**.
 - .3 Departmental representative will take additional test cylinders during cold weather concreting. Cure cylinders on job site under same conditions as concrete which they represent.
 - .4 If tests do not meet requirements of the Departmental representative, take such measures as indicated in CSA A23.1-94 and CSA A23.2-94 (or latest editions).
 - .5 Arrange and pay for inspection and testing when necessary for production control to meet requirements.
 - .6 Inspection and testing by Departmental representative will not augment Contractor's quality control or relieve him of contractual responsibility.
- 3.10 Defective Work
- .1 Concrete is defective when:
 - .1 failing to meet any requirement of this specification
 - .2 concrete contains honeycombing or embedded debris
 - .3 28-day strength in any area is less than 95% of specified minimum.
 - .2 Repair or remove and replace defective work as directed by the Departmental representative.
 - .3 Take corrective measures as directed by the Departmental representative to prevent occurrence of further defective concrete.

PART 1 - GENERAL

1.1 Reference Standards

- .1 Do Concrete work in accordance with CSA standard A23.1-94 (or latest edition), Concrete Materials and Methods of Concrete Construction, except where stricter standards specify otherwise.
- .2 Do testing for concrete in accordance with CSA standard A23.2-94 (or latest edition), Methods of Test for Concrete, except where stricter standards specify otherwise.
- .3 CAN/CSA-A5/A8/A362-93 (or latest edition), Portland Cement/ Masonry Cement/ Blended Hydraulic Cement
- .4 CSA A23.5-M86 (R1992) (or latest edition), Supplementary Cementing Materials.
- .5 ASTM C494-92 (or latest edition), Chemical Admixtures for Concrete

1.2 Definitions

- .1 Tremie concrete is placed underwater through a tube called a tremie pipe. Tremie pipe has a hopper at upper end and may be open ended or may have a foot valve, plug or traveling plug to control flow of concrete. Concrete is placed in hopper and a sufficient head of concrete is maintained in tremie pipe to provide desired rate of flow.
- .2 Pumped concrete method of placing concrete underwater uses a concrete pump with a discharge line used in a similar manner to a tremie pipe.

1.3 Samples

- .1 Submit shop drawings in accordance with **Section 01 33 00** - Shop Drawings, Product Data, Samples and Mockup.

1.4 Certificates

- .1 Minimum 2 weeks prior to starting concrete work, submit to Departmental Representative,

Underwater Concreting

Page 2

manufacturer's test data and certification by qualified independent inspection and testing laboratory that the following materials will meet specified requirements:

- .1 Cement Type 50
- .2 Admixtures
- .3 Aggregates
- .4 Water

- .2 Provide certification that plant, equipment and materials to be used in concrete comply with requirements of CSA standard A23.1
- .3 Provide certification that mix proportions selected will produce concrete of specified quality, yield, strength, and will comply with CSA standard A23.1

1.5 Ready-Mix
Concrete Supply

- .1 Provide with each load of concrete delivered to site, duplicate delivery slips containing following:
 - .1 Name of ready-mix batch plant.
 - .2 Serial number of ticket.
 - .3 Date and truck number.
 - .4 Name or number of project.
 - .5 Class of concrete or mix.
 - .6 Amount of concrete in cubic metres.
 - .7 Time of loading or first mixing of aggregate, cement and water.
 - .8 Time that discharge of concrete begins and ends.
 - .9 Type and quantity of admixtures added at plant.
 - .10 Quantity of water added at plant.

1.6 Measurement
For Payment

- .1 Concrete for Fibre Reinforced concrete pile jackets will be measured for payment in accordance with Section 01 29 00.

PART 2 - PRODUCTS

2.1 Materials

- .1 Portland Cement: to CSA A3001
- .2 Water, fine aggregates, normal density,

Underwater Concreting

Page 3

coarse aggregates: to CSA standard A23.1

- .3 Air entraining admixture: to CSA A23.5
- .4 Polypropylene Fibres to be suited for marine applications. Contractor to submit product specifications for approval by Departmental representative.
- .5 Formwork to meet the requirements of **Section 03 10 00.**

2.2 Concrete Mixes

- .1 Fibre Reinforced concrete.
 - .1 Portland Cement Type GU - 360 kg/m³.
 - .2 Low Calcium Fly ash - 70 kg/m³.
 - .3 Sand - 1050 kg/m³.
 - .4 10 mm stone - 700 kg/m³.
 - .5 Water - 160 L/m³.
 - .6 AEA - 6-9%
 - .7 ADVA - 2-3 L/m³.
 - .8 Polypropylene Fibers - 2 kg/m³.

2.3 Admixtures

- .1 Admixtures will be subject to approval of Departmental Representative. Admixtures will only be permitted to correct deficiencies in mix or to improve placement of concrete.
- .2 Departmental Representative may withdraw prior approval of admixture if conditions encountered during course of work indicate unsatisfactory performance.
- .3 Do not use calcium chloride or materials containing calcium chloride.

PART 3 - EXECUTION

3.1 General

- .1 Do concrete work in accordance with CSA standard A23.1

3.2 Preparation

- .1 Notify Departmental Representative at least 24 hours in advance of intention to commence underwater work.

Underwater Concreting

Page 4

-
- 3.3 Tremie Method
- .1 Provide tremie pipe which is watertight and sufficiently large to allow free flow of concrete.
 - .2 Provide hopper at top of tremie pipe and means to raise and lower tremie.
 - .3 Provide plug or foot valve at end of tremie pipe to permit filling pipe with concrete initially.
 - .4 Start pour with tremie pipe full of concrete and keep end of pipe buried in freshly placed concrete at least 300 mm. Control rate of flow by increasing or decreasing depth of end in concrete.
 - .5 If seal is lost, allowing water to enter pipe, withdraw pipe immediately.
 - .6 If tremie operation is interrupted so that a horizontal construction joint has to be made, cut surface laitance by jetting, within 24 to 36 hours and remove loose material by pumping or air lifting before placing next lift.
 - .7 Do not place concrete in flowing water. Do not vibrate, disturb or puddle concrete after it has been placed.
- 3.4 Pumped Concrete Method
- .1 Follow procedures as for tremie method in placing concrete using discharge line from concrete pump as tremie pipe.