


VRF FAN COILS																
TAG	OUTDOOR UNIT ID	MANUFACTURER/ MODEL	SERVING	TYPE	SUPPLY FANS				CAPACITY		COOLING			HEATING		COMMENTS:
					S/A I/s	ESP (Pa)	ELECTRICAL		COOLING		EAT (DB) °C	EAT (WB) °C	OAT (DB) °C	OAT (DB) °C	EAT (DB) °C	
							A	V/Hz/Ph	TOTAL (W)	SENS (W)						
FC-1	SEE NOTE 1	LG ARNU093BHA2	DIRECTOR'S OFFICE	FAN COIL	REFER TO FLOOR PLANS	75	0.9	208/1/60	2256	1787	22.8	16.1	29.4	-9.4	21.1	COMPLETE WITH CONDENSATE PUMP POWERED FROM FAN COIL <u>NOTE:</u> 1. REFER TO V2.4 WHICH SHOWS CONNECTIONS BETWEEN INDOOR AND OUTDOOR UNITS.
FC-2	SEE NOTE 1	LG ARNU283BGA2	ADMINISTRATION	FAN COIL		75	2.3	208/1/60	6590	5382	22.8	16.1	29.4	-9.4	21.1	
FC-3	SEE NOTE 1	LG ARNU123BHA2	OFFICES A103, A104	FAN COIL		75	0.9	208/1/60	2871	2285	22.8	16.1	29.4	-9.4	21.1	
FC-4	SEE NOTE 1	LG ARNU123BHA2	OFFICES A101, A102	FAN COIL		75	0.9	208/1/60	2871	2285	22.8	16.1	29.4	-9.4	21.1	
FC-5	SEE NOTE 1	LG ARNU123BHA2	SECURE FILE A108	FAN COIL		75	0.9	208/1/60	2871	2285	22.8	16.1	29.4	-9.4	21.1	
FC-6	SEE NOTE 1	LG ARNU093TRC2	SECURITY OFFICE	CEILING CASSETTE		0	0.2	208/1/60	2256	1787	22.8	16.1	29.4	-9.4	21.1	
FC-7	SEE NOTE 1	LG ARNU183BGA2	OFFICES B107, B108	FAN COIL		75	2.3	208/1/60	4483	3545	22.8	16.1	29.4	-9.4	21.1	
FC-8	SEE NOTE 1	LG ARNU123BHA2	OFFICES B105, B106	FAN COIL		75	0.9	208/1/60	2871	2285	22.8	16.1	29.4	-9.4	21.1	
FC-9	SEE NOTE 1	LG ARNU123BHA2	OFFICES B112, B113	FAN COIL		75	0.9	208/1/60	2871	2285	22.8	16.1	29.4	-9.4	21.1	
FC-10	SEE NOTE 1	LG ARNU093BHA2	OFFICES B103, B104	FAN COIL		75	0.9	208/1/60	2256	1787	22.8	16.1	29.4	-9.4	21.1	
FC-11	SEE NOTE 1	LG ARNU053TRC2	RECEPTION	CEILING CASSETTE		0	0.2	208/1/60	1289	996	22.8	16.1	29.4	-9.4	21.1	
FC-12	SEE NOTE 1	LG ARNU123SEL2	MAIN ELECT. RM. 010	WALL MOUNTED		0	0.3	208/1/60	2871	2265	22.8	16.1	29.4	-9.4	21.1	
FC-13	SEE NOTE 1	LG ARNU123SEL2	LAN RM. 012	WALL MOUNTED		0	0.3	208/1/60	2871	2265	22.8	16.1	29.4	-9.4	21.1	
FC-14	SEE NOTE 1	LG ARNU123SEL2	ELEV. MACH. RM. 013	WALL MOUNTED		0	0.3	208/1/60	2871	2265	22.8	16.1	29.4	-9.4	21.1	
FC-15	SEE NOTE 1	LG ARNU123SEL2	PHONE CABLE 011	WALL MOUNTED		0	0.3	208/1/60	2871	2265	22.8	16.1	29.4	-9.4	21.1	
FC-16	SEE NOTE 1	LG ARNU123SEL2	ELEC. CLOSET 104	WALL MOUNTED		0	0.3	208/1/60	2871	2265	22.8	16.1	29.4	-9.4	21.1	
FC-17	SEE NOTE 1	LG ARNU243TNA4	MEETING, STAFF	CEILING CASSETTE		0	0.6	208/1/60	5696	5078	22.8	16.1	29.4	-9.4	21.1	

NOTE:
FAN COILS TO BE COMPLETE WITH AUXILIARY HEAT RELAYS AND VRF CONTROLLERS.

 Public Works and Government Services Canada Travaux publics et Services gouvernementaux Canada	project HALIFAX—DARTMOUTH COMMUNITY CORRECTIONAL CENTRE DARTMOUTH, N.S.	project MECHANICAL VENTILATION SCHEDULES	designed CST	conçu	date NOV.19,2015
			drawn KRG	dessiné	date NOV.19,2015
			approved TEW	approuvé	date NOV.19,2015
Tender PWGSC Project Manager		Soumission Administrateur de projets TPSGC	project number R.035143.001	no. du projet	drawing no. V603