



NOTES:

- CONTRACTOR SHALL DISCONNECT AND TEMPORARILY REMOVE TECK CABLES ROUTED ON DECK SURFACE, SAW CUT CONCRETE DECK, INSTALL NEW 53mm PVC SLEEVES IN TRENCH AND FILL TRENCH WITH GROUT. REROUTE TECK CABLES THROUGH NEW PVC SLEEVES AND RECONNECT.
- PROVIDE STEEL COVER PLATES OVER ANY OPEN TRENCH CUTS. WHARF WILL REMAIN IN OPERATION DURING CONSTRUCTION.
- CONTRACTOR SHALL ROUTE NEW DIRECT BURIED CONDUITS BENEATH EXISTING CONDUITS IN THIS AREA. HAND EXCAVATE TO EXPOSE EXISTING CONDUIT CONTAINING ENERGIZED CONDUCTORS.

1	ADDED EDM AND PROJECT NUMBER	NOV. 13 2015
0	ISSUED FOR TENDER	NOV. 13 2015
C	GENERAL REVISION	NOV. 5 2015
B	ISSUED FOR CLIENT REVIEW	OCT. 16 2015
A	ISSUED FOR CLIENT REVIEW	MAY 25 2015
revisions	date	
project	project	

FALLS POINT ELECTRICAL UPGRADE PHASE 2

FALLS POINT
SHELBOURNE COUNTY, NOVA SCOTIA

ELECTRICAL SITE PLANS EXISTING AND NEW

designed	F. FAHEY	conçu
date	FEB 2015	
drawn	M. SHEPPARD	dessiné
date	FEB 2015	
approved	<i>[Signature]</i>	approuvé
date	2015-11-13	
Tender		Submission
PWSSC Project Manager	Administrateur de projets TPSSC	
project number	no. du projet	
	R.071175.001	
drawing no.	no. du dessin	
	E3	

LEGEND:

- NEW CONDUIT IN TRENCH
- NEW CONDUIT IN WHARF DECK
- NEW TECK CABLE SECURED UNDER DECK

