

Part 1 General

1.1 SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Prepare site plan indicating proposed location and dimensions of area to be fenced and used by Contractor, avenues of ingress/egress to fenced area and details of fence installation.
- .3 Indicate use of supplemental or other staging area.
- .4 Provide construction facilities in order to execute work expeditiously.
- .5 Remove from site all such work after use.

1.2 SCAFFOLDING

- .1 Scaffolding in accordance with CAN/CSA-S269.2.
- .2 Provide and maintain scaffolding, ramps, ladders, swing staging, platforms and temporary stairs as required.

1.3 HOISTING

Provide, operate and maintain hoists, cranes required for moving of workers, materials and equipment.

- .1 Hoists, cranes to be operated by qualified operator.

1.4 SITE STORAGE/LOADING

- .1 The loading/ storage areas are to be reviewed and approved by Departmental Representative prior to the start of work.
- .2 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .3 Do not load or permit to load any part of Work with weight or force that will endanger Work.

1.5 CONSTRUCTION PARKING

- .1 Parking will be permitted on site provided it does not disrupt performance of Work or building operations.
- .2 Provide and maintain adequate access to project site.

1.6 EQUIPMENT, TOOL AND MATERIALS STORAGE

- .1 Provide and maintain, in clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
-

- .2 Locate materials not required to be stored in weatherproof sheds on site in manner to cause least interference with work activities.

1.7 SANITARY FACILITIES

- .1 Sanitary facilities will be assigned for Contractor's personnel. Others shall not be used. Keep facilities clean.
- .2 Post notices and take precautions as required by local health authorities. Keep area and premises in sanitary condition.

1.8 CONSTRUCTION SIGNAGE

- .1 No signs or advertisements, other than warning signs, are permitted on site.
- .2 Signs and notices for safety and instruction in both official languages Graphic symbols to CAN/CSA-Z321.
- .3 Maintain approved signs and notices in good condition for duration of project, and dispose of off site on completion of project or earlier if directed by Departmental Representative.

1.9 PROTECTION AND MAINTENANCE OF TRAFFIC

- .1 Provide access and temporary relocated roads as necessary to maintain traffic.
- .2 Protect travelling public from damage to person and property.
- .3 Contractor's traffic on roads selected for hauling material to and from site to interfere as little as possible with public traffic/farm duties.
- .4 Verify adequacy of existing roads and allowable load limit on these roads. Contractor: responsible for repair of damage to roads caused by construction operations.

1.10 CLEAN-UP

- .1 Areas occupied by livestock are to be kept clear of nails, debris, waste materials and packaging material at all times.
- .2 Remove construction debris, waste materials and packaging material from work site daily.
- .3 Store materials resulting from demolition activities that are salvageable.
- .4 Stack stored new or salvaged material not in construction facilities.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION 01 52 00