

LEGEND


LANDS DEALT WITH BY THIS PLAN
FENCE	-X-X-
CALCULATED POINT
HYDRO POLE	H.P.
TELEPHONE POLE	T.P.
LIGHT POLE	L.P.
UTILITY POLE	U.
RIP/RAP
GUARD RAIL
OVERHEAD WIRE
UNDERGROUND WIRE
PARCEL IDENTIFIER	PID
PLACED SURVEY MARKER
PROPERTY LINE
NEW SANITARY LINE
NEW SANITARY FORCE MAIN
EXIST. SANITARY LINE
NEW WATER LINE
EXISTING WATER LINE
ROAD CENTER LINE
EXISTING ELEVATION
NEW ELEVATION
EXISTING SANITARY MANHOLE	SSMH
NEW SANITARY MANHOLE	MH
EXISTING WATER VALVE	W.V.
NEW WATER VALVE	W.V.
NEW REDUCER
EXISTING UTILITY POLE
NEW FIRE HYDRANT
EXISTING TREES
LIFT STATION

GENERAL NOTES:

- EXAMINE SITE AND REPORT ANY DISCREPANCIES TO THE DEPARTMENTAL REPRESENTATIVE BEFORE PROCEEDING WITH THE WORK.
- ALL DIMENSIONS AND ELEVATIONS ARE IN METRIC UNITS U.N.O.
- SURVEY DATA AND EXISTING TOPOGRAPHIC INFORMATION HAS BEEN OBTAINED BY LOCUS SURVEY, DWG 94611, DATED 3 NOV 2004. DATED ... 2005.
- SOUNDING DATA OBTAINED AND PROVIDED BY DFO ON A DWG DATED 30 MAY 2008.
- SUBSURFACE INVESTIGATION WAS CARRIED OUT BY STANTEC AND REPORT DATED 31 MARCH 2014 IS AVAILABLE FOR REVIEW AT PWGSC CHARLOTTETOWN OFFICE.
- PREVENT MOVEMENT OR SETTLEMENT AND SAFEGUARD AND MAINTAIN INTEGRITY OF EXISTING STRUCTURES, ADJACENT STRUCTURES, SERVICES AND ADJACENT GRADES AND ALSO MINIMIZE EXCAVATION.
- CONSTRUCTION SEQUENCE TO BE PROPOSED BY THE CONTRACTOR AND TO BE REVIEWED BY THE DEPARTMENTAL REPRESENTATIVE PRIOR TO CONSTRUCTION.

CONSTRUCTION SCHEDULE:

- THERE SHALL BE NO IN WATER CONSTRUCTION ACTIVITIES BETWEEN 1ST OF OCTOBER AND 31ST OF DECEMBER.



revisions

project

**BREAKWATER RELOCATION
AND BASIN EXPANSION**

**STANLEY BRIDGE
QUEENS COUNTY, P.E.I.**

drawing

**SITE PLAN
NEW**

designed N.L., P.Eng

date 9 NOV 2015

drawn N.L.

date 9 NOV 2015

approved

date

Tender *Mr. McGuire* Submission

PWGSC Project Manager Administrateur de projets TPWSC

project number

R.064507.001

drawing no.

M2 of 4