

## **Part 1 General**

### **1.1 RELATED SECTIONS**

- .1 Section 01 51 00 – Temporary Utilities.

### **1.2 REFERENCES**

- .1 Canadian General Standards Board (CGSB):
  - .1 CGSB 1.59-97, Alkyd Exterior Gloss Enamel.
  - .2 CAN/CGSB 1.189-00, Exterior Alkyd Primer for Wood.
- .2 Canadian Standards Association (CSA International):
  - .1 CSA-O121-M1978(R2003), Douglas Fir Plywood.

### **1.3 INSTALLATION AND REMOVAL**

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

### **1.4 GUARD RAILS AND BARRICADES**

- .1 Provide secure, rigid guard rails and barricades around open shafts/tunnels/manholes.
- .2 Provide as required by the governing Authorities Having Jurisdiction (AHJ).

### **1.5 DUST TIGHT SCREENS**

- .1 Provide dust tight screens or insulated partitions to localize dust generating activities, and for protection of workers, finished areas of Work and the general public.
- .2 Maintain and relocate protection until such work is complete.

### **1.6 ACCESS TO SITE**

- .1 Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

### **1.7 PUBLIC TRAFFIC FLOW**

- .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform Work and protect public.

### **1.8 FIRE ROUTES**

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

### **1.9 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY**

- .1 Protect surrounding private and public property from damage during performance of Work.

- .2 Be responsible for damage incurred.

#### **1.10 PROTECTION OF EXISTING FINISHES**

- .1 Provide protection for finished and partially finished finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule three (3) days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

#### **1.11 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

### **Part 2 Products**

#### **2.1 NOT USED**

- .1 Not Used.

### **Part 3 Execution**

#### **3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**