

## **Part 1 General**

### **1.1 REFERENCES**

- .1 Departmental Representative Standard Acquisition Clauses and Conditions  
SACC-ID: R0202D, Title: General Conditions "C", In Effect as of: Oct. 8, 2014.

### **1.2 PROJECT CLEANLINESS**

- .1 Maintain the work site and the existing manhole access points/entrances, etc. designated for use by construction work force in tidy condition, free from accumulation of waste products and debris. Clean areas on a daily basis.
- .2 Hourly, daily and/or nightly clean-up is required, which includes sweeping and/or vacuuming of dirt and debris.
- .3 Remove waste materials from site at daily regularly scheduled times or dispose of as directed by the Departmental Representative. Do not burn waste materials on-site, nor allow any materials to enter Halifax Harbour.
- .4 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .5 Provide on-site containers for collection of waste materials and debris.
- .6 Use separate collection bins, clearly marked as to purpose for recycling. Refer also to Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .7 Clean interior areas prior to start of finishing work, and maintain areas free of dust and other contaminants during finishing operations.
- .8 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .9 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .10 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
- .11 Employ dust barriers, dividers, seal doors with tape and provide other means required, and as approved by the Departmental Representative.
- .12 Be responsible to immediately clean construction dust and dirt transferred by foot traffic, or by other means, into the pipe Tunnel.

### **1.3 FINAL CLEANING**

- .1 When Work is Substantially Performed, remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3 Prior to final review remove surplus products, tools, construction machinery and equipment.

- .4 Remove waste products and debris.
- .5 Remove waste materials from site at regularly scheduled times or dispose of as directed by the Departmental Representative. Do not burn waste materials on site.
- .6 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .7 Clean all Mechanical, Electrical and Controls components installed. Replace broken, scratched or disfigured items.
- .8 Remove stains, spots, marks and dirt from Mechanical and/or Electrical and/or Controls.
- .9 Remove debris and surplus materials from Tunnel areas.

#### **1.4 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

#### **Part 2 Products**

##### **2.1 NOT USED**

- .1 Not Used.

#### **Part 3 Execution**

##### **3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**