



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works and Government
Services Canada/Réception des soumissions
Travaux publics et Services gouvernementaux
Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada -
Pacific Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Lighting and Power Upgrades	
Solicitation No. - N° de l'invitation EZ108-161544/A	Amendment No. - N° modif. 003
Client Reference No. - N° de référence du client	Date 2015-12-14
GETS Reference No. - N° de référence de SEAG PW-\$PWY-019-7684	
File No. - N° de dossier PWY-5-38293 (019)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2016-01-07	Time Zone Fuseau horaire Pacific Standard Time PST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Ngan, Ken (PWY)	Buyer Id - Id de l'acheteur pwy019
Telephone No. - N° de téléphone (604) 658-2755 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: NRCan - Pacific Forestry Centre - Victoria, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
EZ108-161544/A
Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.
003
File No. - N° du dossier
pwy-5-38293

Buyer ID - Id de l'acheteur
pwy019
CCC No./N° CCC - FMS No/ N° VME

Les documents français seront disponibles sur demande.

Please find following Addendum #2.

All other terms and conditions remain unchanged.

The following addendum supersedes information contained in drawings and specifications issued for the project to the extent referenced. This Addendum forms part of the Tender Documents and is subject to all of the conditions set out in the contract conditions.

This electrical addendum contains two (2) pages.

1. REFER TO: CLARIFICATION REQUEST NUMBER EC 1

- 1.1 Some feeders shown on E103 & E104 (ie Panel A, F, GG etc.) are solid line (as if new). The scope of work for the project does not indicate replacing any feeders and the referenced feeders are the same size as the existing. Please confirm if new feeders are to be provided.

AES Response:

Only feeders to be replaced are those serving the Wing A panels fed from the two bus ducts.

- 1.2 Please confirm if there is a required staging plan for the project.

AES Response:

Staging area has been added to site plan, final location to be confirmed by Departmental Representative.

- 1.3 Please issue a civil plan for the excavation contractors to reference when bidding their scope of work.

AES Response:

Civil details have been included in our drawing, and extent of new works laid out in the site plan.

- 1.4 Single lines show panels ACPP-01 & HX-1as new but Panel schedules on E105 & E106 indicate panels are existing. Please confirm if new.

AES Response:

Single line indicates panels are to be replaced. There are existing panels in those locations that are to be replaced.

- 1.5 Some existing switching is shown multiple (ie Rooms 071 & 073) but appear only as a single replacement sensor device. Please confirm the intent is to replace switching on a one for one basis without change to switching schemes.

AES Response:

Intent is to replace existing on a one for one basis.

- 1.6 Some switching is shown on the new installation drawings where none appears to have existed previously (ie Room 062 & 061). Please confirm these are not retrofit locations.

AES Response:

These are retrofit locations.

- 1.7 Please confirm a ceiling mount vacancy sensor is required in Room 064.

AES Response:

Should be wall mounted device.

- 1.8 Please confirm if PWGSC will provide paint or paint colour information for patching operations.

AES Response:

PWGSC Departmental Representative to Comment.

Room 066 shows replacement lighting to be explosion proof but also a Vacancy sensor switch to be installed. I am unaware of an explosion proof rated vacancy switch. Please confirm the rating is required.

AES Response:

Revise to be normal explosion proof switch.

- 1.9 Please confirm where I1 or I2 fixtures do NOT show a custom length they are (Nominal) 4ft.

AES Response:

Lengths to be standard 4'.

END OF ELECTRICAL ADDENDUM #2