



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
Room 100,
167 Lombard Ave.
Winnipeg
Manitoba
R3B 0T6
Bid Fax: (204) 983-0338

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada -
Western Region
Room 100
167 Lombard Ave.
Winnipeg
Manitoba
R3B 0T6

Title - Sujet Rain Shelters	
Solicitation No. - N° de l'invitation 01005-160089/B	Amendment No. - N° modif. 003
Client Reference No. - N° de référence du client 01005-160089	Date 2015-12-17
GETS Reference No. - N° de référence de SEAG PW-\$WPG-010-9658	
File No. - N° de dossier WPG-5-38035 (010)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2016-01-05	
Time Zone Fuseau horaire Central Standard Time CST	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Maki, Christie	Buyer Id - Id de l'acheteur wpg010
Telephone No. - N° de téléphone (204) 891-6126 ()	FAX No. - N° de FAX (204) 983-7796
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: See herein	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
01005-160089/B
Client Ref. No. - N° de réf. du client
01005-160089

Amd. No. - N° de la modif.
003
File No. - N° du dossier
WPG-5-38035

Buyer ID - Id de l'acheteur
wpg010
CCC No./N° CCC - FMS No./N° VME

This amendment 003 is raised to amend solicitation 01005-160089/B to respond to questions received by the industry:

Q4. Are the mounting brackets required to be flush with the frame tubing or on top of the tubing. This would depend on how the plastic is to be attached.

A4: The brackets could fit on top of the outside of the arches.

Q5. Is the intention to put boards (1" x 3" or similar) onto the mounting brackets and staple the plastic to the boards.

A5: Yes the intention is to put boards (1" x 3" or similar) onto the mounting brackets and staple the plastic to the boards.

Q6. Is the intention that the plastic would be a smooth cover over the frame. This being the case, we would need to know what type of lumber will be used for the strapping (we assume 1" x 3" or similar) so that the brackets can be recessed below the tubing so the boards run flush between each leg and arch.

A6: We plan to attach the lumber on the outside edge of the Arch, so the plastic will not fit tight to the arch. Brackets do not need to be recessed.

Q7: If you use square tubing for the frame does it need screw plates on it?

A7: We are unable to answer this question as we do not know the capabilities of the material being proposed.

Q8.1: Can we get a drawing showing where the lumber mounting plates should be located?

Q8.2: The tender states the plates should be half way "up the curve(d) or angled part". We are not exactly sure where this is. It appears to be the roof section of the rafter. If so, should the mount be on the top side or the underside of the rafter?

A8.1: Drawings are not being provided for this requirement.

A8.2: The lumber mounting plate on "roof" of the shelter should be placed half way between the peak and the top of the vertical wall. It is intended that the lumber should be on top of the rafter, hence the mounting bracket could be on top or flush with the outside of the rafter.

Q9: The tender requires all "straight sections" to be less than 6' long. The rafter sections are curved but are longer than 6'. Will they be acceptable?

A9: Pieces should not be longer than 6 Ft (approx.)

Q10: Is the plastic cover intended to go over top of the lumber strapping or below it? If the lumber strapping is going under the plastic, how is the plastic going to be affixed to the lumber?

A10: The cover will be placed over the lumber.

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME