

EXISTING PANELBOARD DIRECTORY 2B3

ITEM	LOAD (kW)	OCF	C	C	ITEM	LOAD	OCF	C	C	ITEM	LOAD (kW)	OCF	C	C	ITEM	LOAD	OCF	
EXISTING			1	22	EXISTING			*					15A	43	64	FURNITURE	1.00	15A,2P
*REC'S (x5) 111	1.25	15A	2	23	EXISTING			*					15A	44	65		1.00	
*PRINTER 111	1.00	15A	3	24	EXISTING			*					15A	45	66	FURNITURE	1.00	15A,2P
EXISTING			4	25	EXISTING			*					15A	46	67		1.00	
EXISTING			5	26	EXISTING			*					15A	47	68	FURNITURE	1.00	15A,2P
EXISTING			6	27	EXISTING			*					15A	48	69		1.00	
EXISTING			7	28	EXISTING			*					15A	49	70	FURNITURE	1.00	15A,2P
EXISTING			8	29	*FURNITURE	1.00	15A	*					15A	50	71		1.00	
EXISTING			9	30	*FURNITURE	1.00	15A	*					15A	51	72	FURNITURE	1.00	15A,2P
EXISTING			10	31	*FURNITURE	1.00	15A	*					15A	52	73		1.00	
EXISTING			11	32	EXISTING			*					15A	53	74			
EXISTING			12	33	*			15A	*				15A	54	75			
EXISTING			13	34	*			15A	*				15A	55	76			
EXISTING			14	35	*			15A	*				15A	56	77			
EXISTING			15	36	*			15A	*				15A	57	78	EXISTING		
EXISTING			16	37	*			15A	*				15A	58	79			
EXISTING			17	38	*			15A	*				15A	59	80			
EXISTING			18	39	*			15A	*				15A	60	81	EXISTING		
EXISTING			19	40	EXISTING			*					15A	61	82			
*REC'S (x2) 111A	0.50	15A	20	41	EXISTING			*					15A	62	83			
*WORKSTATIONS (x2) 111	1.00	15A	21	42	EXISTING			*					15A	63	84			

NOTES:  
 CIRCUITS DENOTED WITH AN ASTERISK (\*) ARE EXISTING CIRCUIT BREAKERS TO BE RE-USED. CONFIRM ON SITE.  
 RATING: 225A, 120/280V/3Ø/4W

EXISTING PANELBOARD DIRECTORY 'L2'

ITEM	LOAD (kW)	OCF	C	C	ITEM	LOAD	OCF
EXISTING			1	22	EXISTING		
EXISTING			2	23			
EXISTING			3	24			
EXISTING			4	25			
EXISTING			5	26			
EXISTING			6	27			
EXISTING			7	28			
EXISTING			8	29			
EXISTING			9	30			
EXISTING			10	31			
EXISTING			11	32			
EXISTING			12	33			
EXISTING			13	34			
EXISTING			14	35			
*COMMON AREA LIGHTING	3.192	15A	15	36			
*RM, 107A, 107B, 107C, 106, 105, 104, 102, 101	4.0116	15A	16	37			
*	1.874	15A	17	38			
EXISTING			18	39			
*			19	40			
*			20	41			
*			21	42			

NOTES:  
 CIRCUITS DENOTED WITH AN ASTERISK (\*) ARE EXISTING CIRCUIT BREAKERS TO BE RE-USED. CONFIRM ON SITE.  
 RATING: 225A, 347/600V/3Ø/4W


PANELBOARD DIRECTORY 2B4

ITEM	LOAD (kW)	OCF	C	C	ITEM	LOAD	OCF
P-1	1.176	20A	1	22	SPARE		15A
EF-1	0.15	15A	2	23	SPARE		15A
			3	24	SPARE		15A
IWH-1	2.4	30A	4	25	SPARE		15A
AC-1 THRU AC-6	0.175	15A, 2P	5	26	SPARE		15A
	0.175		6	27	SPACE		
AC-7 THRU AC-9	0.087	15A, 2P	7	28	SPACE		
	0.087		8	29	SPACE		
CP-1 THRU CP-6	0.6	15A	9	30	SPACE		
CP-7 THRU CP-9	0.3	15A	10	31	SPACE		
TF-1	0.15	15A	11	32	SPACE		
TF-2	0.15	15A	12	33	SPACE		
TF-3	0.05	15A	13	34	SPACE		
CU-1	4.32		14	35	SPACE		
	4.32	50A, 3P	15	36	SPACE		
	4.32		16	37	SPACE		
CU-2	1.35	15A, 2P	17	38	SPACE		
	1.35		18	39	SPACE		
DWC-1	0.144	15A	19	40	SPACE		
ROOF TOP REC	1.00	20A	20	41	SPACE		
SPARE		15A	21	42	SPACE		


NOTES:  
 MOUNTING: RECESSED  
 RATING: 225A, 120/208V/3Ø/4W

CIRCUITING

- POWERED FURNITURE TO BE '8-WIRE'. SEE CIRCUITING ABOVE.
- DETAIL SHOWN IS A TYPICAL REPRESENTATION OF FURNITURE WHIP. ELECTRICAL CONTRACTOR TO CONFIRM FINAL CONFIGURATION WITH FURNITURE SUPPLIER. PROVIDE ALL REQUIRED HARDWARE AND LABOUR REQUIRED TO INSTALL PER MANUFACTURER'S RECOMMENDATIONS.



- CIRCUITING
- LINE 1
  - LINE 2
  - NEUTRAL
  - GROUND
  - LINE 3
  - LINE 4
  - NEUTRAL
  - GROUND



1 PRE-WIRED FURNITURE SYSTEM DETAIL  
 E11 NTS

**HDK** HDK CONSULTING INCORPORATED  
 55-81 Garry St.  
 Winnipeg, Manitoba  
 Canada, R3C 4J9  
 T: 204.818.0390  
 www.hdkconsulting.com  
 info@hdkconsulting.com  
 Mechanical | Electrical | Communications | Security Engineering



**APEGM**  
 Certificate of Authorization  
 HDK Consulting Incorporated  
 No. 5539 Date: 04/30/2016

DO NOT SCALE DRAWINGS

Revision/	Description/Description	Date/Date
3	ISSUED FOR CONSTRUCTION	15/11/20
2	100% CD SUBMISSION	15/10/29
1	99% CD SUBMISSION	15/09/28
0	50% CD SUBMISSION	15/08/14

Client/client

**CANADA SCHOOL OF PUBLIC SERVICE (CSPS)**  
 Winnipeg  
 MANITOBA

Project title/Titre du projet  
**STANLEY KNOWLES BUILDING  
 2ND FLOOR - 391 YORK AVENUE  
 WINNIPEG, MANITOBA**

**CSPS WINNIPEG FIT-UP**

Approved by/Approuvé par  
 HUGO CEA CANAS

Designed by/Concept par  
 PAUL LAPOINTE

Drawn by/Dessiné par  
 RHODA DE CASTRO

PWSC Project Manager/Administrateur de Projets TPSC  
 JOHN ALIBIN

PWSC, Architectural and Engineering Resources Manager/  
 Ressources Architectural et de Directeur d'Ingénierie, TPSC

Client/client  
 PUBLIC WORKS AND GOVERNMENT SERVICES CANADA

Drawing title/Titre du dessin

**PANELBOARD DIRECTORY - 2**

Project No./No. du projet  
**R.060508.003**

Sheet/Fauille  
**E11**  
 OF 12

Revision no./  
 La Révision  
**3**

