


KEY PLAN
N.T.S.

- LEGEND:**
- DENOTES CONCRETE TO BE REMOVED.
 - DENOTES NEW CONCRETE.
 - DENOTES FENDER NUMBERS.
 - DENOTES EXISTING LADDER.
 - DENOTES NEW LADDER ON BOLLARD BLOCK (3 REQUIRED) - SEE DETAIL 5/S4.
 - EJ - DENOTES NEW EXPANSION JOINT - SEE DETAIL 7/S4.
 - LIGHT STANDARD
 - VALVE CHAMBER
 - W- - DENOTES EXISTING WATER LINE
 - W- - NEW WATERLINE
 - - - EXISTING CONDUITS
 - - - NEW CONDUIT




APPROX. NORTH

**WOOD ISLANDS
HARBOUR**




CENTRE PIER COPEWALL REMOVALS
SCALE : 1:100




APPROX. NORTH

**WOOD ISLANDS
HARBOUR**




CENTRE PIER COPEWALL REPAIRS
SCALE : 1:100



SEQUENCE OF WORK:

1. REMOVE SECTION OF EXISTING COPEWALL. ENSURE THAT NO MORE THAN ONE 50mm DIAMETER TIE ROD IS EXPOSED AT ANY ONE TIME.
2. INSTALL SUPPORT CLIPS, SEE DETAIL 6/S4.
3. REMOVE NEXT SECTION OF EXISTING COPEWALL ENSURING NO MORE THAN ONE 50mm DIAMETER TIE RODS IS EXPOSED AND INSTALL SUPPORT CLIPS.
4. CONTINUE PROCESS FOR ENTIRE LENGTH OF WALL.
5. MODIFY 50mm DIAMETER TIE ROD, SEE DETAIL 6 & SECT. A/S4.
6. POUR NEW COPEWALL INCLUDING EXPANSION JOINTS (EJ). IF POUR IS NOT CONTINUOUS, USE CONSTRUCTION JOINT, SEE DETAIL 8/S4.



0	ISSUED FOR TENDER	DEC.04 2015
revisions		date
project		project

**CENTRE PIER COPEWALL
WOOD ISLANDS,
QUEEN'S COUNTY, PEI**

drawing dessin

**COPEWALL
REMOVALS AND
REPAIRS**

designed G. PETERS	conqu
date AUGUST 2015	
drawn M. BOUTILIER	dessiné
date AUGUST 2015	
approved J. MACLEOD	approuvé
date DECEMBER 2015	
Tender <i>J. MacLeod</i>	Soumission
PWOSC Project Manager	Administrateur de projets TPSGC
project number	no. du projet
R.077637.001	
drawing no.	no. du dessin
S2 of 4	

