



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works and Government
Services Canada/Réception des soumissions
Travaux publics et Services gouvernementaux
Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada -
Pacific Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Sewage Lagoon Rehabilitation	
Solicitation No. - N° de l'invitation EZ899-161731/A	Amendment No. - N° modif. 004
Client Reference No. - N° de référence du client	Date 2015-12-31
GETS Reference No. - N° de référence de SEAG PW-\$PWY-019-7688	
File No. - N° de dossier PWY-5-38302 (019)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2016-01-08	Time Zone Fuseau horaire Pacific Standard Time PST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Ngan, Ken (PWY)	Buyer Id - Id de l'acheteur pwy019
Telephone No. - N° de téléphone (604) 658-2755 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: Parks Canada - Pacific Rim National Park - Ucluelet, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
EZ899-161731/A
Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.
004
File No. - N° du dossier
pwy-5-38302

Buyer ID - Id de l'acheteur
pwy019
CCC No./N° CCC - FMS No/ N° VME

Please find following Addendum #2.

All other terms and conditions remain unchanged.

GENERAL

The following changes / clarifications in the tender documents are effective immediately. This Addendum will form part of the Contract Documents.

DRAWINGS

1. Sheet C-2, Existing Facilities and Demolition Plan

Change: shown dimensions of Facultative Lagoon to **80m x 80m**.

CLARIFICATIONS

Questions Received by PWGSC to December 31, 2015

n/a

Additional Questions received to December 31, 2015

1. *Is locating and exposing the existing forcemain part of this contract?*

An alignment for the existing forcemain will be provided in digital format for layout by the Contractor. This alignment may be accessed by the trail that has been recently cleared along the general forcemain route.

The Contractor is to locate and expose the forcemain at roughly 100m intervals. These locations are to be surveyed as part of the Record Survey and are to include pipe and ground elevations. All excavated holes to be backfilled with native material following the final survey. The Contractor is to allow for locating the forcemain within 4m of the provided alignment.

2. *Does the existing forcemain have to be centered on the proposed 4m ROW?*

While centering the pipe is preferred, allowances will be made as dictated by existing conditions. This will be examined on a case by case basis. In all cases, the pipe will have to be within the cleared ROW.

3. *Are any repairs to the forcemain to be included in this contract?*

Contractors to allow for the potential repair/replacement of up to 30m of existing forcemain at one location. This location is where the forcemain is exposed approximately 20m NE of Sandhill Creek. Photos of the location is attached for reference. Supply and installation of all required parts, fittings, and material are to be included. Depth of bury to ensure no high spot in pipe is created.

As long as the integrity of the pipe is maintained, the alignment and elevations of the existing pipe may be adjusted and the pipe buried in place.

END OF ADDENDUM #2







Photo #1 – taken December 23, 2015



Photos #2 & #3 – taken November 19, 2015