



ADDENDUM # 1

Date: January 19, 2016

Project: Pigsty Walls and Ceiling Finishes Improvements

Bidders must make sure that their bids are based on the latest version of the tender documents published and take into consideration the following amendments and information, including any information provided in amendments or Q&As previously published for this project.

Bidders that do not comply with this requirement will be discarded.

In Annex E « TECHNICAL SPECIFICATIONS & PLANS»

1. Summary specifications 01 50 00 SITE FACILITIES AND TEMPORARY INSTALLATIONS, p.6

1. PARTICULAR MEASURES

REPLACE:

- 1.3. Clothes: contractor, employees and sub-contractors have to bring 2 days of working clothing, 24 hours before beginning work, that will stay at pigsty complex for the entire duration of the work. Clothes are going to be cleaned by pigsty staff before beginning work and every day for the entire duration of the work. For temporary sub-contractors, clothes can be provided by the pigsty complex.

BY:

- 1.3. Clothing: the Contractor, its employees and subcontractors must bring work clothes for two days, a minimum of 24 hours before the commencement of work so that they are cleaned by staff of the pigsty. The clothes will stay put for the duration of the work and subsequent washes will be performed by the contractor using the washers and dryers located in the complex of the barn. Occasional subcontractors may use clothing (without the steel toe boots) provided by the complex for a maximum of 4 people at a time. The contractor must ensure that all employees at the site will bring a pair of new construction boot to the pigpen. These boots will remain on site during construction.

2. Summary specifications 01 50 00 SITE FACILITIES AND TEMPORARY INSTALLATIONS, p.6

1. PARTICULAR MEASURES

REPLACE:

- 1.4. Contractor has to protect gutter with a plywood and make sure there is no construction debris in the room before removing them. These plywood sheets will be supplied by AAC.

BY:

- 1.4. The contractor and its subcontractors must take the necessary measures to prevent debris and other objects from getting into the gutters.



3. Summary specifications 01 50 00 SITE FACILITIES AND TEMPORARY INSTALLATIONS, p.7

7. DEBRIS AND WASTE DISPOSAL

REPLACE:

- 7.3. Contractor has to provide bin stands on coasters for A, C and G sections. Waste shall be transported to E building dock at the end of every day. When outside, contractor will throw them in the container and will leave the bin on the dock. Nobody can go outside and re-enter without passing through the shower. Bin can't go on the ground, otherwise it has to be cleaned by pigsty staff. For H section, use end corridor exit door, contractor has to build a temporary plywood shelter with a plywood roof, asphalt shingles and plywood raised floor on a 38 x 89 wood base to leave bins out there and avoid contamination. Shelter has to be big enough to have a free exit and have a door with spring hinges. Contractor shall take the same precautions as sections A, C and G.

BY:

- 7.3. The contractor will provide bins on wheels. The containers must not be rolled down the dock in any case. The waste will be transported and released through the section E dock. When they dispose debris, contractor and subcontractors will transfer materials without leaving the dock while respecting the pigsty biosecurity measures in place. They will also avoid blocking access to the dock for long periods of time.

4. Intervention legend, C building, p.20

REPLACE:

- D- All electrical works requiring disconnection/reconnection, has to be done by a qualified electrical contractor.

BY:

- D- All work involving electrical components must be performed by a qualified electrical contractor.

5. Intervention legend, C building, p.22

REPLACE:

29. Loop, metal hook or projecting screws (see picture 12 and 13, annex E): remove and reinstall once the work is done.

BY:

29. Loop, metal hook or projecting screws (see picture 12 and 13, annex E): remove and reinstall once the work is done. The row of bolts (29) located above the row of black clips (item 19) does not have to be reinstalled.

6. In Annex E – TECHNICAL SPECIFICATIONS & PLANS, Intervention legend, C building:

Replace pages 24, 34, 42 and 51 drawings with those included in the attachment « Plans C101-C104-E ».



7. Invitation to Tender

REPLACE:

Solicitation Closes: **Friday, January 22, 2016, at 02:00 PM, EST**

BY:

Solicitation Closes: **Tuesday, January 26, 2016, at 02:00 PM, EST**

All other terms and conditions remain the same







