

1 REFLECTED CEILING PLAN – LEVEL THREE

- (S1) INDICATES NEW FLOORING TYPE
(EX) EX INDICATES EXISTING FLOORING TO REMAIN


FINISHES NOTES

FLOORING
REMOVE ALL EXISTING FLOOR AND WALL BASE THROUGHOUT AREAS OF RENOVATIONS UNLESS NOTED OTHERWISE. REPAIR ALL DAMAGE TO FLOOR SLAB AND WALLS. SKIM FLOOR SMOOTH AND LEVEL AND PREP AS REQUIRED TO RECEIVE NEW PRODUCT AS PER SPECIFICATIONS. INSTALL NEW FLOORING AS PER PLAN.

W1 VINYL TILE – LUXURY VINYL TILE/PLANK AS PER SPECIFICATIONS
S1 SHEET LINOLEUM FLOORING AS PER SPECIFICATIONS

WALLS & BULKHEADS
SKIM ALL DRYWALL SURFACES TO A SMOOTH FINISH. APPLY NEW FINISHES AS SPECIFIED.

DOORS & FRAMES
ALL EXISTING AND NEW DOORS AND FRAMES THROUGHOUT AREA OF PROJECT ARE TO BE SANDED SMOOTH AND PREP FOR PAINT FINISH AS SPECIFIED



2 FINISH PLAN – LEVEL THREE

WINDOW COVERINGS
EXISTING BLINDS TO BE REMOVED FROM ALL PERIMETER WINDOWS, WRAPPED AND STORED IN A SECURE AND CLEAN LOCATION DURING THE CONSTRUCTION. AT THE END OF THE PROJECT, BLINDS ARE TO BE PROFESSIONALLY CLEANING AND REINSTALLED. ENSURE ALL BLINDS ARE IN GOOD WORKING ORDER AND REPLACE / REPAIR ALL BLINDS AS REQUIRED.

SCALE : 1:100
0m 1m 2m 3m 4m 5m 6m 7m 8m 9m 10m

consultant:

trilogy
interior design inc.

PO Box 321
Bedford Row
Halifax, Nova Scotia
Canada B3J 2N7

tel: 902 835-9333
fax: 902 835-9663

THESE DRAWINGS ARE TO BE USED SOLELY FOR THIS INTENDED PROJECT AND ARE NOT TO BE REPRODUCED OR USED FOR ANY OTHER PROJECT WITHOUT WRITTEN AUTHORIZATION DIRECTLY FROM TRILOGY INTERIOR DESIGN INC. ©TRILOGY INTERIOR DESIGN 2015

revisions	date
00	UPDATED & ISSUED FOR TENDER 14JAN15
0	ISSUED FOR TENDER & CONSTRUCT 22DEC15
-	ISSUED FOR 99% REVIEW 04DEC15
-	ISSUED FOR 90% REVIEW 20NOV15

project

POLARIS BUILDING RENOVATIONS

BEDFORD INSTITUTE OCEANOGRAPHY
DARTMOUTH – NS

drawing

LEVEL 3 REFLECTED CEILING PLAN AND FINISH PLAN

designed	DH	conçu
date	NOV 2015	
drawn	TRI	dessiné
date	NOV 2015	
approved	JEFF HILCHEY	approuvé
date	JAN 04, 2016	
Tender	JEFF HILCHEY	Submission
PWGSC Project Manager	JAN 04-16	
project number	no. du projet	

drawing no.

A-6

E-DRM/GDD-E: #XXXXX