



1 H2 SPRINKLER DEMOLITION PLAN – LEVEL TWO





- ### GENERAL NOTES
- Ⓐ VERIFY EXISTING SITE CONDITIONS BEFORE COMMENCING WORK.
  - Ⓑ COORDINATE WORK WITH OTHER SERVICES TO AVOID INTERRUPTION OR CHANGES TO PIPING AND/OR EQUIPMENT IN CEILING SPACE OUTSIDE SCOPE OF WORK.
  - Ⓒ EXISTING SERVICES OUTSIDE SCOPE OF WORK ARE NOT SHOWN FOR CLARITY.
  - Ⓓ THE CONTRACTOR AND ALL SUB-CONTRACTORS SHALL NOT SCALE DRAWINGS AND VERIFY ALL JOB SITE DIMENSIONS.

LEGEND	
○	EXISTING SPRINKLER HEAD
○●	NEW PENDANT SPRINKLER HEAD (K=5.0) RATED 150°C, 1.5 L/min, 1.5 m
○●	NEW PENDANT SPRINKLER HEAD (K=5.0) RATED 150°C, 1.5 L/min, 1.5 m

- ### SPRINKLER NOTES
- ① PROVIDE 25MM SCH40 STEEL PIPE TO SAT NEW HEAD LOCATION. REPLACE EXISTING SPRINKLER HEAD WITH NEW PENDANT SPRINKLER HEAD.
  - ② PROVIDE A FIRE RATED FIRE EXTINGUISHER CABINET TO MATCH THE FIRE RATING OF THE WALL.
  - ③ INSPECT ALL SPRINKLER HEADS AFTER WORK IS COMPLETE FOR SIGNS OF DAMAGE AND REPLACE ALL DAMAGED SPRINKLERS WITH NEW HEADS.



2 H2 NEW SPRINKLER PLAN – LEVEL TWO



consultant:

**onsa**

F.C. O'Neill, Scriven & Assoc's Limited  
Consulting Engineers

5450 Cornwallis Street  
Halifax, Nova Scotia, B3K 1A9  
P: (902) 429-0701  
F: (902) 429-9729  
W: www.onsa.ca



B	ISSUED FOR TENDER		01/18/2016
A	ISSUED FOR 100% REVIEW		01/14/2016
revisions			date
project			
POLARIS BUILDING FLOOR PLAN UPGRADES			
BEDFORD INSTITUTE OCEANOGRAPHY DARTMOUTH – NS			
drawing			
LEVEL 2 DEMO & NEW SPRINKLER			
designed	BS	conçu	
date	DEC 2015		
drawn	BS	dessiné	
date	DEC 2015		
approved	MR	approuvé	
date	JAN 2016		
Tender			
Soumission			
PWGSC Project Manager      Administrateur de projets TPSGC			
project number		no. du projet	
F5654-150080			
drawing no.		no. du dessin	
H2			